

DOCUMENT NUMBER 131262


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS :

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

West Meander Corner, Section 6 and Section 31,  
T.35N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 8th day  
of October A.D., 1986 at  
1:25 o'clock P. M. and recorded  
in Vol. CORNER RESTORATIONS  
page A-3,4  
Paul A. Schenck  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1857, Alfred Millard set wood post with the following BTs: Cedar, 10", N.70°W., 14 links; Cedar, 10", N.4°E., 27 links.

In 1946, the G.L.O. set a 6" x 24" concrete monument with the following BTs: Yellow Birch, 12", S.77½°W., 293 links; Cedar, 10", N.33 3/4°W., 101 links; Wilderness Resort Lodge, South, 90 links.


In 1962, Victor Hedman found the monument under surface of blacktop and noted that the brass cap was broken off and 1" pipe in center was bent over. The following references were made: Cedar, 10", N.49°09'W., 80.1 feet; Cedar, 18", N.89°06'W., 273.1 feet; (1946 BT) Yellow Birch, 14", S.76°39'W., 193.0 feet; Power Pole 3514-31R2, N40-45-30E, 421.3 feet, northwest corner lodge, S.54°43'W., 86.8 feet, northeast corner lodge, S.11°10'W., 66.7 feet.

In 1986, the corner and a 20" Cedar snag, West, 273.1 feet were found and references made.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 1" iron pipe 5" below surface of road.
2. Red Pine, 6", N.63°E., 122.54 feet
3. Northeast corner of Wild Rose Supper Club, S.52°W., 87.19 feet
4. Double Oak, 13", N.14°W., 81.78 feet
5. Cedar snag, 20", West, 273.1 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/11/86  
Date



139177


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.
- - Corner monument restored.

CORNER TO SECTIONS - 5, 6, 31, 32 - TWP 1 S.  
34 & 35 R. 14 E. IN FOREST COUNTY



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1857 - ORIGINAL SURVEY BY MILLARD

1946 - RESURVEY OF SECTION 6 BY CRAWFORD, SET CONCRETE MONUMENT, 3 FT. LONG, 5" DIA., 34" IN GROUND WITH AN IRON POST 3 FT. LONG 1" IN DIA., EMBEDDED IN CENTER WITH BRASS CAP MARKED TO IDENTIFY CORNER, B.T.s - MAPLE 8" N.20 $\frac{1}{4}$ ° E. 76 lks, BIRCH 9" S.38° E. 42 lks, MAPLE 12" S.62° W. 35 lks, MAPLE 8" N.56° W. 65 $\frac{1}{2}$  lks.

1962 - RESTORATION BY KAPITZ R.L.S. # S-670, FOUND CORNER AS MARKED ABOVE, FOUND THESE B.T.s- BIRCH 10" S.38° E. 27.72 FT., MAPLE 17" S.62° W. 23.10 FT., MAPLE 14" N.56° W. 43.23 FT. ESTABLISHED NEW ACCESSORIES AS FOLLOWS; NE CORNER OF CABIN - S.23 $\frac{1}{2}$ ° W. 17.70 FT., BALSAM 6" N.33° W. 12.50 FT., 4X4 WOOD POST 2 FT. NE OF CORNER

1989 - RESTORATION BY DOBBRATZ R.L.S. # S-973, FOUND MONUMENT AS DESCRIBED ABOVE, ONE ACCESSORY REMAINING. BALSAM 6" N.33° W. 12.50 FT.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

## WITNESS


- 1 - POWER POLE S.70° E. 63.60 FT.
- 2 - NE CORNER OF GARAGE SOUTH 130.10 FT.
- 3 - NW CORNER OF RESIDENCE, S.22° W. 131.42 FT.
- 4 - BALSAM 14" N.28° W. 12.59 FT. (EXISTING)
- 5 - SECTION CORNER, BRASS CAP IN CONCRETE (EXISTING)  
4 X 4 WOOD POST, N.46° E. 1.85 FT.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26 day  
of February 1990 at  
10:10 o'clock AM and recorded  
in Vol. A-5

CORNER RESTORATIONS

Paul H. Schumacher  
Register of Deeds




(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, WAYNE G. DOBBRATZ

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

*Wayne G. Dobbratz*

Date

*9/4/89*

CERTIFICATE READY FOR FILING:

*Dale S. Haeger*  
District Ranger



State of Wisconsin

County of FOREST

ss.

I L. ERNEST GEORGE, do hereby certify that on the SIXTEENTH day of OCTOBER 19 68, I established the WEST ONE SIXTEENTH CORNER BETWEEN SECTION 32, TOWNSHIP 35 NORTH, RANGE 14 EAST AND SECTION 5, TOWNSHIP 34 NORTH, RANGE 14 EAST Fourth Principal Meridian. as described hereon.

**History:**

There is no record of this corner having ever been previously established.

**Description of monument and accessories I established to perpetuate the location of this corner:**

At the point determined for the location of the corner I emplaced a:


GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY-CLARK CORP. T34-35N W 1/16 BTWN. 32 & 5 R14E GEORGE S-0309 10/16/68."

This pipe is witnessed by:

Aspen 7 N 60 W 29 links. (SCRIBED S 32 BT)

Aspen 6 S 30 W 34 links. (SCRIBED S 5 BT)

**Description as to how corner was located:** The section corner  $\frac{1}{4}$  mile west and the quarter corner  $\frac{1}{4}$  mile east have been previously set with a distance of 39.97 chains between them. Thus set the W 1/16th corner 19.98 $\frac{1}{2}$  chains from either corner and on a straight line between them.



O = Corner monument  
restored

Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 18th day of March, 19 74.

Signature L. Ernest George

Title Registered Land Surveyor Registration No. S-0309

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 19th day of March 19 74, and was filed in Book No. Corner Page No. A-6 of County Records.

Restorations  
DOCUMENT NUMBER 105005

Signature Eugene J. [unclear] Title Register of Deeds

Surveyor's Seal

43514320030

Index No.

A 6


U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
O = Corner monument restored.

$\frac{1}{4}$  CORNER TO SECTIONS 5 AND 32, TOWNSHIP  
34 AND 35 N., R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1857 MILLARD, SURVEY TOWNSHIP LINE  
1859 JAMES McBRIDE, SURVEY OF SECTION 5  
1946 GOV'T. LAND OFFICE, REMAINS OF ORIGINAL B.T. FOUND, SET CONCRETE MONUMENT  
WITH BRASS CAP TO IDENTIFY CORNER, NEW B.T.s TAMARACK 4" S.22°E. 164 LKS.,  
DEAD CEDAR 7" N.63°W. 8 LKS.  
1963 RESVICK R.L.S. NO. S-802, NEW B.T., ASPEN 10" N.33°W. 45.50FT.  
1982 FISHER R.L.S. NO. S-836, SUBDIVISION OF SECTION 5, FOUND MONUMENT, RESVICK B.T.,  
NOTED THE FOLLOWING B.T.s TAMARACK 4"S.22°E. 10.20FT., CEDAR (DEAD) 7" N.63°W.  
5.90FT., SET STEEL SIGN POST 1 FT. EAST OF CORNER  
1989 DOBBRATZ R.L.S. NO. S-973, FOUND MONUMENT, STEEL SIGN POST AND 2 B.T.s AS NOTED  
BY FISHER IN 1982.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.


B.T.s ① ASPEN 10" N.33°W. 45.32FT. (EXISTING)  
④ TAMARACK 4" S.22°E. 108.2FT. (EXISTING)  
⑤ ASPEN 7" S.82°W. 62.35FT. (NEW)

WITNESS MONUMENT ② FOUND CONCRETE MONUMENT  
WITH BRASS CAP AT CORNER  
③ FOUND STEEL SIGN POST 0.35FT.  
EAST OF CORNER.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26<sup>th</sup> day  
of February A.D. 1990 at  
10:10 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page A-7

Paul H. Brennan  
Register of Deeds



NOT TO SCALE


(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

NONE

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED CORNER

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?



(i) 1. WAYNE G. DOBBRATZ

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

10/20/89

Date

CERTIFICATE READY FOR FILING:

Dale Stange  
District Ranger

CERTIFIED LAND CORNER RESTORATION


Index No. **135**  
**A 9**

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby  
certify that on the 10th day  
of July, 19 63, I found  
evidence of the Section  
corner of Section 4, 5, 32 and 33  
Township T34N and T35N, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_


FORM 985 H. C. MILLER CO., MILWAUKEE



○ = Corner monument restored.

History of original corner establishment:  
Surveyed in 1859 by James McBride  
Set wood post from which:  
Tamarack 7" bears N30°E, 69 Lks  
Tamarack 12" bears S5°E, 312 Lks  
W. Pine 20" bears S86°W, 725 Lks  
4.00 ch. east leave open swamp  
3.50 ch. south leave open swamp  
6.00 ch. west leave open swamp  
4.00 ch. north leave marsh  
Description of corner evidence found:  
3x3 squared scribed post 3-feet high, 393 east of west edged swamp, 288 feet south of north  
edge of swamp.  
Tamarack snag 4", bears N30°E, 45 feet, scribed bearing tree  
Tamarack 13" snag, bears S5°E, 204 feet  
1.40 feet north of post found point of original post

Description of monument and accessories I established to perpetuate the original location of this corner.  
I replaced point of original post with a 2-inch inside diameter galvanized iron pipe, 5-feet  
long, flanged at bottom, filled with concrete, with brass cap marked:



from which the following new blazed and scribed bearing trees bear:  
Spruce 4", N45°E, 10.75 ft. (16 Lks)  
Spruce 4", S58°E, 28.25 ft. (43 Lks)  
Spruce 5", S36°W, 41.28 ft. (62½ Lks)  
Tamarack 3", N39°W, 10.90 ft. (16½ Lks)

Dated at Rhineland, Wis., this 10th day of December, 19 63

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 30 day of January, 19 64  
at 9:00 o'clock A M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy

88139

43514320000

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

West meander corner to Sections 4 and 33,  
T.34-35N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Found stump of original White Pine bearing tree. Meander corner now falls in lake.  
Position witnessed by a 2" x 60" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

Witness corner, West, 40.00 feet from M.C. in lake.  
References:

1. Red Oak, 14", S.82°W., 58.69 feet
2. Red Pine, 8", N.47°W., 16.89 feet
3. Red Pine, 6", N.16°W., 36.50 feet
4. Steel Sign Post, Southeast, 1.50 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... day  
of... A.D., 19... at  
... o'clock... M. and

recorded in Vol. ... CORNER RESTORATIONS  
on page ...

Paul A. Schendanner  
REGISTER

43514330020

A-9, 10

A 9,10

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(1) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

12/24/84


U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

MEANDER CORNER 490.70FT. WEST OF  $\frac{1}{4}$  CORNER TO SECTIONS 4 AND 33, TOWNSHIPS 34 AND 35 N. R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1859 JAMES Mc BRIDE, ORIGINAL SURVEY OF SECTION 4

1982 STEFAN R.L.S. NO. S-1558, SUBDIVISION OF SECTION 4, SET 2" DIA. ALUMINUM MONUMENT AT MEANDER CORNER ON EAST SHORE OF HIMLEY LAKE, 490.70FT. WEST OF  $\frac{1}{4}$  CORNER TO SECTIONS 4 AND 33, B.T.s HEMLOCK 4" N.84°E. 21.17FT., HEMLOCK 15" S.58°E. 18.20FT., YELLOW BIRCH 7" S.22°W. 12.42FT., SET STEEL SIGN POST 3.60FT. EAST OF MEANDER CORNER.

1989 DOBBRATZ R.L.S. NO. S-973, FOUND MEANDER CORNER, B.T.s AND STEEL SIGN POST AS SET BY STEFAN IN 1982.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- B.T.s ① HEMLOCK 4" N.78°E. 21.35FT. (EXISTING)  
② HEMLOCK 15" S.64°E. 18.55FT. (EXISTING)  
③ YELLOW BIRCH 7" S.14°W. 12.88FT. (EXISTING)


- WITNESS MONUMENT ④ 2" DIA. ALUMINUM MONUMENT (EXISTING) AT MEANDER CORNER.  
⑤ STEEL SIGN POST 1.52FT. (EXISTING) EAST OF MEANDER CORNER.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26<sup>th</sup> day  
of February, 1990 at

10:10 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page A-10, 11

*Paul Schenckner*  
Register of Deeds



43514330023

A-10, 11

N  
TOWNSHIP 34  
RANGE 14 E

A 10, 11

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED CORNER

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

WAYNE G. DOBBRATZ

(i) I, Wayne G. Dobbratz (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.


Signature

10/20/89

Date

CERTIFICATE READY FOR FILING:

Dale B. Staeger  
District Ranger





## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## I N S T R U C T I O N S :

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

East meander corner to Sections 4 and 33,  
T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored at the intersection of the east shore of Himley Lake and an east-west fence line. Placed a 2" x 60" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Hemlock, 4", N.84°E., 21.17 feet
2. Hemlock, 15", S.58°E., 18.20 feet
3. Yellow Birch, 7", S.22°W., 12.42 feet
4. Steel Sign Post, East, 3.60 feet



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this... 21st day  
of January... A.D., 1925 at  
11:00 o'clock... A.M. and

recorded in Vol. CORNER RESTORATIONS

on page 10, 11.

Paul Aechenbrenner  
REGISTER

43514330020

A-10, 11

A  
10,11

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(1) 1. Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

12/24/84

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 3 and 34,  
 T.33-34 N., R.14E., Langlade County,  
 and Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 79738.99982-N  
 2289683.33935-E

Geographic Coordinates  
 45-22-42.27935-N  
 088-45-00.48660-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1857 by Alfred Millard. Set wood post and the following bearing trees; Hemlock, 14", S.59°W., 10 links, Spruce, 18", N.40°E., 7 links, East, 2.80 chains stream 10 links wide runs SW.


On September 14 1983, Alan Harrison, R.L.S., found an old fence corner from which a Black Cherry stump bears East 2.0 feet as noted on Form #874. Also found the original creek call East to fit, and local testimony in agreement with this location. At the old fence corner, set a 2" x 36" aluminum monument with a tablet stamped to identify corner. Blazed and scribed new bearing trees; Aspen, 12", N.82°E., 27.24 feet, Sugar, 8", S.04°E., 47.39 feet, Black Cherry, 7", N.85°W., 13.18 feet, Steel Sign Post, South, 1.3 feet.

On October 21 1993, Alan Harrison, R.L.S., found monument and bearing trees as set in 1983. The N.E. and S.E. bearing trees are dead. Cut down Black Cherry for G.P.S. Observation. Blazed and scribed 3 new bearing trees; Black Cherry, 11", West, 40.27 feet, Aspen, 14", N.28°W., 24.30 feet, Black Cherry, 5", N.50°W., 28.62 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument with tablet stamped to identify corner.
2. Black Cherry, 11", West, 40.27 feet.
3. Black Cherry, 5", N.50°W., 28.62 feet.
4. Aspen, 14", N.28°W., 24.30 feet.
5. Steel Sign Post, South, 1.3 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23rd day  
of November, A.D., 19 94 at  
9:00 o'clock A.M. and recorded  
in Vol. Corner Restoration  
page 34-14-A-11

Paul Clithero, Deputy  
Register of Deeds

Affix Land Surveyor Seal:



(1) 1, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison

Signature

10/26/94

Date

CERTIFICATE READY FOR FILING:

Sue Vap

District Ranger


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 4 and 33, T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found position marked by 1½" iron pipe from which remains of original stump northeast and subsequent N. Smith bearing tree stump remains from 1926 survey were found. Placed a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Oak, 15", N.11°E., 35.23 feet
2. Sugar, 6", N.59°W., 12.29 feet
3. Sugar, 7", S.83°W., 18.38 feet
4. Steel Sign Post, East, 3.20 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this 21st day  
of January A.D., 1975 at  
11:00 o'clock A.M. and

recorded in Vol. CORNER RESTORATIONS

on page A-11

Paul Aschmussen  
REGISTER

43514330020

A-11

A  
1  
1

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(1) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

12/24/84  
Date

Affix Land Surveyor Seal



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Section Corner to Sections 3, 4, 33 and 34, T.33-34N., R.14E., Langlade County, WI., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 79793.57089-N  
 2292334.45408-E  
 Geographic Coordinates  
 45-22-42.40449-N  
 088-44-23.34075-W




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.
- Original survey in 1857 by Alfred Millard. Set wood post and the following bearing trees; Linn, 12", S.49°W., 37 links, Sugar, 24", N.50°W., 42 links, Yellow Birch, 40", S.45°E., 30 links, Hemlock, 10", N.25°E., 48 links.
- In 1962, Victor Hedman, R.L.S., found a 2" diameter iron pipe and the original Hemlock stump, scribed N.25°E., 32 feet. Replaced iron pipe with a 2" x 60" galvanized iron pipe with a brass cap stamped to identify corner. Blazed and scribed new bearing trees; Yellow Birch, 5", N.15°E., 74.58 feet, Elm, 7", S.47°E., 21.78 feet, Sugar, 12", S.63°W., 39.60 feet, Sugar, 14", N.52°W., 55.77 feet, center-line of road, West, 14 feet.
- In 1976 Jean Resvick, R.L.S., found monument damage and replaced it with a 2" x 36" aluminum monument. Placed nails in 1962 bearing trees for the following new measurements; Yellow Birch, 8", N.16°E., 75.00 feet, Elm, 10", S.47°E., 21.65 feet, Sugar, 15", S.63°W., 39.30 feet, Elm, 17", N.52°W., 55.80 feet.
- On September 29 1983, Alan Harrison, R.L.S., found monument and bearing trees as noted in 1962 and 1976. Elm bearing trees are dead. Made 2 new bearing trees; White Ash, 9", S.81°E., 83.82 feet, Sugar, 8", N.49°W., 75.25 feet, Steel Sign Post, East, 6.3 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument with tablet stamped to identify corner.
2. Yellow Birch, 9", N.16°E., 75.00 feet.
3. White Ash, 9", S.81°E., 83.82 feet.
4. Sugar, 17", S.63°W., 39.30 feet.
5. Center-line of road, West, 14 feet.
6. Sugar, 9", N.49°W., 75.25 feet.
7. Steel Sign Post, East, 6.3 feet.



F.R. #2126

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23rd day  
of November A.D., 1994 at  
2:00 o'clock A.M. and recorded  
in Vol. Case Restoration  
page 344-13  
Paul Clithero Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 3, 4, 33, and 34,  
T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position recovered from the remains of the original bearing tree stumps. Placed a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Spruce, 6", S.88°E., 24.41 feet
2. Red Maple, 6", S.20°W., 32.09 feet
3. White Birch, 9", S.82°W., 72.57 feet
4. Red Maple, 4", N.20°W., 21.46 feet
5. Steel Sign Post, South, 2.50 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 21st day

of... January... A. D., 1985

at... 11:00 o'clock... A. M. and

recorded in Vol. CORNER RESTORATIONS

on page 13  
Paul A. Schenck  
REGISTER

43514330000

A-13

A 13

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

Affix Land Surveyor Seal



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 3 and 34,  
 T.33-34N., R.14E., Langlade and  
 Forest Counties, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 79863.56878-N  
 2294981.34714-E

Geographic Coordinates  
 45-22-42.67918-N  
 088-43-46.25053-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1857 by Alfred Millard, set wood post and the following bearing trees; Yellow Birch, 24", N.52°W., 64 links, Yellow Birch, 20", S.30°E., 45 links.


In 1976, Jean Resvick, R.L.S., found a scribed 4" x 4" wood post and stump remains from both original bearing trees. Replaced wood post with a 2" x 36" galvanized iron pipe with a brass cap stamped to identify corner. Blazed and scribed new bearing trees; Sugar, 15", S.83°E., 30.25 feet, Basswood, 10", N.54°W., 22.28 feet, Steel Sign Post, North, 0.50 feet.

On October 22 1993, Alan Harrison, R.L.S., found monument and bearing trees as set by Resvick in 1976. Blazed and scribed 1 new bearing tree; Sugar, 9", S.57°W., 25.36 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" galvanized iron pipe with brass cap stamped to identify corner.
2. Sugar, 15", S.83°E., 30.25 feet.
3. Sugar, 9", S.57°W., 25.36 feet.
4. Basswood, 10", N.54°W., 22.28 feet.
5. Steel Sign Post, North, 0.50 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23<sup>rd</sup> day  
of November, A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Cover Restoration  
page 34-14, A-15  
Leslie Chittie, Deputy  
Register of Deeds

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger



CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 10 day of May, 19 77, I found evidence of the North quarter corner of Section 3 Township 34 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:



Surveyed in 1854 by Alfred Millard  
40 chains west between Sections 3 and 34, set post  
Tamarack 7, N55W, 34 links  
Tamarack 10, S27E, 42 links  
14.0 ch. east leave open swamp bears SE-NW  
11.5 ch. west, tamarack 18"  
30.0 ch. west leave swamp bears SE-NW

Description of corner evidence found:

Tamarack stump, cut off above DBH blaze, scribing visible, was 10" when scribed.  
At N27W, 42 links from stump found post point under moss and small spruce  
11.5 ch. west fallen 18" tamarack  
14 ch. east leave swamp  
30 ch. west leave swamp

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced post point with a 2 inch inside diameter galvanized iron pipe, 3 feet long, filled with concrete with another 3 foot section of 2 inch pipe threaded on the bottom with standard pipe coupling, with brass cap stamped: T35N R14E, S34, 1/4, S3, T34N, 1977, S-802  
Blazed and scribed the following new bearing trees:  
Tamarack 5, N69E, 9.66 ft.  
Tamarack 7, S48E, 18.85 ft.  
Tamarack 5, S44W, 14.16 ft.  
Set steel sign post on east side monument



● - Corner monument restored  
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 9 day of August 19 77.

Signature *Jean F. Resvick* Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 113281

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of February 19 78, and was filed in Book No. Page No. of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 34 North, Range 14 East, Section 3, Index No. A-15, Page No. 15

43514340020


U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

NORTHWEST CORNER OF SECTION 2, TWP.  
34 N., R. 14 E. ALSO BEING THE SECTION  
CORNER TO SECTIONS 2-3-34-35 TWP. 34-35  
N., R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1859 \_\_\_\_\_ ORIGINAL SURVEY OF SECTION 2  
1963 \_\_\_\_\_ RESURVEY BY RESVICK R.L.S. NO. S-802, FOUND EVIDENCE OF ORIGINAL  
CORNER, SET 2" DIA. IRON PIPE WITH BRASS CAP.  
B.T.s SPRUCE 6" N.40° E. 29.85FT., WHITE PINE 13" S.74° E. 26.50FT.,  
MAPLE 8" S.75° W. 29.60FT., TAMARACK 6" N.53° W. 10.70FT.  
1989 \_\_\_\_\_ DOBBRATZ R.L.S. NO. S-973, FOUND B.T.s AND MONUMENT AS NOTED BY  
RESVICK IN 1963, 1 B.T. DOWN.


- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26<sup>th</sup> day  
of February, 1990 at  
10:10 o'clock A.M. and recorded  
in Vol. 4-17 **CORNER RESTORATIONS**  
page 1  
Paul H. Schenckner  
Register of Deeds

- B.T.s ① WHITE PINE 13" S.74° E. 26.50FT. (EXISTING)  
② YELLOW BIRCH 7" S.9° W. 22.95FT. (NEW)  
③ MAPLE 8" S.75° W. 29.60FT. (EXISTING)  
④ TAMARACK 6" N.53° W. 10.70 (EXISTING)  
WITNESS MONUMENT  
⑥ STEEL SIGN POST 0.50 EAST (EXISTING)  
⑤ 2" DIA. IRON PIPE WITH BRASS CAP STAMPED  
TO IDENTIFY CORNER AT SECTION CORNER  
(EXISTING)



NOT TO SCALE

A 17


- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

NONE

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?



- (i) I, WAYNE G. DOBBRATZ  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

10/6/89

Date

CERTIFICATE READY FOR FILING:

David Stagg  
District Ranger


CERTIFIED LAND CORNER RESTORATION

Index No. 10217  
A 17

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby  
certify that on the 10th day  
of July, 19 63, I found  
evidence of the Northwest Section  
corner of Section 2  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_




○ = Corner monument restored.

History of original corner establishment:  
Surveyed in 1859 by James McBride  
80.00 chains west between sections 2 and 35  
Set wood post from which  
Tamarack 12", bears N26°W, 17 Lks  
Y. Birch 10", bears N40°E, 74 Lks  
Tamarack, 14", bears S15°E, 24 Lks  
Y. Birch 6", bears S67°W, 28 Lks

1.00 ch. east leave swamp  
3.00 ch west leave swamp  
2.75 ch south leave swamp  
9.00 ch north leave cedar swamp

Description of corner evidence found:  
At a point north, 181 feet from south edge of swamp, found top of post under moss and tag  
alder roots. From top of post found point of original post in place.  
From point of post Tamarack snag 16", bears S15°E, 16.65 feet which has evidence of both  
top and lower blazes with the interior completely rotted out.  
Rotted tamarack stump under moss bears N26°W, 11 feet from point.  
From point edge of swamp bears east 85 feet.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Replaced point of post with 2-inch inside diameter galvanized iron pipe, 5-feet long,  
flanged at bottom, filled with concrete, tamped in sand, with brass cap marked.



From which the following new bearing trees bear:  
Spruce 6", N40°E, 29.85 feet (45 Lks)  
W. Pine 13", S74°E, 26.50 feet (40 Lks)  
Maple 8", S75°W, 29.60 feet (45 Lks)  
Tamarack 6", N53°W, 10.70 feet (16 Lks)

Dated at Rhinelander, Wis., this 10th day of December, 19 63

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 30 day of January, 19 64  
at 9.00 o'clock A. M.

Anna Peterson  
(Register of Deeds)

88138

By Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE

4351434060



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 2 and 35, T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored from remains of original bearing trees. Placed a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar, 6", S.27°E., 17.35 feet
2. Sugar, 12", S.51°W., 34.34 feet
3. Sugar, 12", N.31°W., 51.59 feet
4. Steel Sign Post, Northeast, 1.10 feet



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 11th day

of January, A. D., 1985, at

1:00 o'clock, P. M. and

recorded in Vol. CORNER RESTORATIONS

on page A-19

Paul Aschmussen  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/8/84  
Date


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**I N S T R U C T I O N S :** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 1, 2, 35, and 36,  
T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

At corner location, found post hole and remains of original bearing tree. Placed a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar, 11", N.14°E., 10.41 feet
2. Hemlock, 6", S.7°E., 44.33 feet
3. Sugar, 16", S.61°W., 42.30 feet
4. Basswood, 10", N.30°W., 29.03 feet
5. Steel Sign Post, South, 1.20 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... day  
of... A. D., 19... at  
... o'clock... A. M. and

recorded in Vol. ...  
on page ...

*Paul Aschenbrenner*  
REGISTER

43514350000

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(1) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

Affix Land Surveyor Seal




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 1 and 36, T.34-35N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position found marked by 2" iron pipe and a scribed wood post. Placed a 2" x 60" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Birch, 14", N.57°E., 33.01 feet
2. Balsam, 10", S.46°E., 12.13 feet
3. White Birch, 10", N.38°W., 41.42 feet
4. Steel Sign Post, West, 1.10 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this 21st day  
of January, 1985 at  
...11:00 o'clock... A...M. and

recorded in Vol. CORNER RESTORATIONS

on page A-23

Paul Aschenbrenner  
REGISTER


(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

12/24/84

ORIGINAL ON FILE IN CO CLERK'S OFFICE  
COPY HERE FOR REFERENCE

FIELD SURVEY NOTES


PRESERVATION OF LANDMARKS

(Pursuant to Section 59.635(7) Wisconsin Statutes

E-D-707-69

State of Wisconsin / Department of Transportation

COUNTY <i>FOREST</i>		
TOWN <i>FREEDOM, WABENO, LAONA</i>		
HIGHWAY <i>S.T.H. 32</i>		
SECTION <i>1</i>	TOWNSHIP <i>34 N</i>	RANGE <i>14 E</i>
TYPE OF LANDMARK <i>PK NAIL - AGREES WITH U.S.F.S. R.M.'s</i>		




LOCATION SKETCH

(Location of landmark indicated by "x")



This space for copy of field notes or ties to the above described landmarks

ALL MONUMENTS ARE BERNTSEN MAG.  
ALUMINUM MONUMENTS AND ARE STAMPED:  
WITH "W.C." & DIST. TO CORNER.  
BRS ARE REFERENCE TO S.T.H. 32 &



FILED UNDER PROJECT <i>9131-03-70</i>			COUNTY CLERK'S OFFICE COUNTY OF <i>Forest</i> WISCONSIN } 85	
DISTRICT OFFICE NUMBER <i>03-07</i>	CITY <i>RHINELANDER</i>	COUNTY <i>ONEIDA</i>	DATE RECEIVED FOR RECORD <i>11/20/85</i>	DATE COPY SENT TO COUNTY SURVEYOR <i>N/A</i>
LOCATED OR ESTABLISHED BY NAME <i>J.R. WALLIN under the direction of MICHAEL HESS 2nd Surveyor 500809</i> TITLE <i>SURVEY CREW CHIEF</i> DATE <i>5-16-85</i>			SIGNATURE OF COUNTY CLERK <i>Dora C. James</i>	

State of Wisconsin

County of Forest

ss.

I L. ERNEST GEORGE, do hereby certify that on the SIXTEENTH day of OCTOBER 1968, I established the CENTER OF THE NORTHWEST QUARTER OF SECTION 5, TOWNSHIP 34 NORTH, RANGE 14 EAST, Fourth Principal Meridian as described hereon.


History: Slowe's Second Plat of Roberts Lake surveyed by Chas. E. Walker in 1942 shows that a wooden post was set for this corner.

Description of monument and accessories I established to perpetuate the location of this corner: At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY-CLARK CORP. T34N CENTER NW $\frac{1}{4}$  5 R14E GEORGE RLS S-0309 10/16/68. W.C. - CORNER IS 25.00 FEET SOUTH - W.C." The pipe is witnessed by:

Maple 11 S 63°W 15 links. (SCRIBED S5 WC BT)  
Maple 4 N 65°E 105 links. (SCRIBED S5 WC BT)

Description as to how corner was located: From recent survey work I located the post set as the W 1/16th on the east-west quarter line of section 5 by Chas. E. Walker, County Surveyor for Forest County, when he surveyed "Slowe's Second Plat of Roberts Lake" in 1942. Also located four other posts on the W 1/16th line of section 5 as shown on the plat. Two of these posts were rotted off but located the point where they were set by the remaining portion still in the ground. I did not find the post set as the center of the Northwest quarter. From the northern-most post located on the W 1/16th line, this post being 885 feet north of the southeast corner of Slowe's plat, measured north 415 feet to where the center of the northwest quarter should be. This point is on the edge of the Town road used for access to Slowe's Plat. 22.93 feet north of this point was located a short, square wooden post. I believe this short, square post was set to mark the East-West position of the West 1/16th line of section 5 and that the center of the northwest quarter was set on the edge of the road and has been destroyed through the grading and improvement of the road.



O = Corner monument restored

I have accepted the work of Chas. Walker as being correct and have reset a 3/8ths inch by 12 inch iron "spike" as the center of the north west quarter. This "spike" is located 22.93 feet south of and on a straight line between the short, square post mentioned above and the W 1/16th of section 5. The center of the northwest quarter is also located as follows; it is 1176.59 feet south of the W 1/16th between sections 5 and 32, 1298.88 feet north of the W 1/16th of section 5, and is located 2.10 feet west of a straight line between these two corners. (continued on back)

Resident witnesses

Dated at Crandon, Wisconsin, this 18th day of March, 1974.

Signature L. Ernest George  
Title Registered Land Surveyor Registration No. S 0309

Office of Register of Deeds County of Forest  
I hereby certify that the within instrument was filed in this office for record on the 19th day of March 1974, and was filed in Book No. Corner Page No. B-6 of County Records. Restorations 105004

Signature Eugene Stutzman Title Register of Deeds

Surveyor's Seal

43414053030

Index No. B 6



I also set a Witness Corner to the center of the northwest quarter of section 5. This Witness Corner is stamped "W.C. Corner is 25.00 feet south W.C." and has two bearing trees located as stated above.

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

NORTH 1/16 CORNER BETWEEN SECTIONS  
2 AND 3 TWP. 34 N., R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1857 & 1859 \_\_\_\_\_ ORIGINAL SURVEY.

1982 \_\_\_\_\_ STEFAN R.L.S. NO. S-1558, SUBDIVISION OF SECTION 3,  
SET 2" DIA. ALUMINUM MONUMENT AT NORTH 1/16 CORNER  
B.T.s BLACK ASH 8" N.78° E. 29.60FT., BLACK ASH 8"  
S.28° E. 69.85FT. WITNESS MONUMENT STEEL SIGN POST  
EAST 5.80FT.

1989 \_\_\_\_\_ DOBBRATZ R.L.S. NO. S-973, FOUND MONUMENT SET BY STEFAN IN  
1982 HIT BY GRADER, STEEL SIGN POST GONE, B.T.s ARE GOOD.  
RESET MONUMENT FROM B.T. TIES.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.


- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

B.T.s ① BLACK ASH 8" N.78° E. 29.60FT. (EXISTING)

③ BLACK ASH 8" S.28° E. 69.85FT. (EXISTING)

② WITNESS MONUMENT STEEL SIGN POST 8.00FT. EAST (NEW)

④ RESET 2" DIA. ALUMINUM MONUMENT AT NORTH 1/16 CORNER  
12" BELOW ROAD SURFACE.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26 day  
of February A.D. 1990 at

10:10 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page B-17

Jean Fischelbauer  
Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

NONE

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

WAYNE G. DOBBRATZ


- (i) I, Wayne G. Dobbratz (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

David B. Stange  
District Ranger



REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this 2nd day  
of August A.D., 2002 at  
2:45 o'clock A M. and recorded  
in Vol. Corner Restoration  
page C-1  
Kay Swanson, Deputy  
Register of Deeds

Document Number  
**176285**

**U.S. PUBLIC LAND SURVEY MONUMENT RECORD**

(As Required by WI Adm. Code)

History of original corner establishment and subsequent restorations and descriptions of any record, monument, occupational, testimonial or other evidence considered:

- 1857 - Alfred Millard set original corner post and made the following B.T.'s:  
Hemlock 15", N 30° W, 112 lks., 73.92 feet  
Hemlock, 18", N 65° E, 64 lks., 42.24 feet.
- 1946 - The U.S. General Land Office performed a Dependent Resurvey of Section 6, T34N R14E. The point for the quarter corner was found marked by a 2" dia. iron pipe. A 6" dia. X 24" long concrete monument with a stamped brass cap was set at this location. The following new B.T.'s were made: Maple 6", N 78 1/4° E, 50.5 lks. 33.33 feet  
Maple 9", N 72° W, 20 lks, 13.20 feet
- 2002 - I found the 6" dia. concrete monument & the 2 B.T.'s mentioned above in excellent condition. I made 2 new B.T.'s described below:

Corner was: (Check All That Apply)




- ☐ Restored through acceptance of an obliterated evidence location.  
☒ Restored through acceptance of a found perpetuated location.  
☐ Considered a lost corner and reestablished through lost corner proportionate methods (include a plan view drawing showing distances and directions to other Public Land Survey Corners used for proportioning and determining the corner location).  
☐ Restored or reestablished in a location that differs from a previous restoration or reestablishment (include a plan view drawing and indicate what was set and/or found).

Describe the monument and accessories used to perpetuate the location of this corner (include a plan view drawing and indicate what was set and/or found).

LEGEND:

- Found 6" dia. Con. Mon.  
W/Stamped Brass Cap

Note: All distances are  
taken to nail in  
side of tree.



I, Michael A. Tremel, RLS  
(type or print name) certify that the corner location shown on  
this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record  
is correct and complete to the best of my knowledge and belief.

Michael A. Tremel 7/15/02  
Signature Date

The West Quarter corner of  
Section 6 T. 34 N., R. 14 E.  
Forest County, WI

Index No. C-1

43413012000

Document Number

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 2nd day  
of August A.D., 2002 at  
8:45.0 clock A.M. and recorded  
in Vol. Corner Restoration  
page C,D-1  
Kay Swanson, Deputy  
Register of Deeds

176286

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

(As Required by WI Adm. Code)

History of original corner establishment and subsequent restorations and descriptions of any record, monument, occupational, testimonial or other evidence considered:

- 1857 – Alfred Millard, marked a 36" Dia. W. Pine for Meander Corner and made the following B.T.'s:  
W. Pine 18", N 39° E, 17 lks., 11.22 feet  
W. Pine, 14", S 70° W, 33 lks., 21.78 feet.
- 1946 – The U.S. General Land Office performed a Dependent Resurvey of Section 6, T34N R14E. The meander corner was recovered in that survey and was mentioned as a rotted pine stump. A 6" dia. X 24" long concrete monument with a stamped brass cap was set at this location. The following new B.T.'s were made: Elm 6", N 62 1/2° E, 34 lks. 22.44 feet  
W. Pine 18", N 36 3/4° W, 122.5 lks, 80.85 feet
- 2002 – I found the 6" dia. concrete monument mentioned above in excellent condition. Made the following new B.T.'s: Oak 13", S 32° W, 9.87 feet; Oak 9", N 18° W, 38.28 feet  
Oak 9", S 77° W, 61.17 feet; 2" Iron Pipe, N 02° E, 21.04 feet

Corner was: (Check All That Apply)



- ☒ Restored through acceptance of an obliterated evidence location.  
☒ Restored through acceptance of a found perpetuated location.  
☐ Considered a lost corner and reestablished through lost corner proportionate methods (include a plan view drawing showing distances and directions to other Public Land Survey Corners used for proportioning and determining the corner location).  
☐ Restored or reestablished in a location that differs from a previous restoration or reestablishment (include a plan view drawing and indicate what was set and/or found).

Describe the monument and accessories used to perpetuate the location of this corner (include a plan view drawing and indicate what was set and/or found).

LEGEND:

- Found 6" dia. Con. Mon.  
W/Stamped Brass Cap

Note: All distances are  
taken to nail in  
side of tree.



I, Michael A. Trembl, RLS  
(type or print name) certify that the corner location shown on  
this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record  
is correct and complete to the best of my knowledge and belief.

Michael A. Trembl 7/15/02  
Signature Date

The North Meander corner of  
Section 6 T. 34 N., R. 14 E.  
Forest County, WI

Index No. C,D-1

43413011800


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

WEST WITNESS TO C.  $\frac{1}{4}$  OF SECTION 5,  
 TWP. 34 N., R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1859 ORIGINAL SURVEY OF SECTION 5 BY JAMES McBRIDE

1982 SUBDIVISION OF SECTION 5 BY FISHER R.L.S. NO. 836, SET 2" DIA. ALUMINUM MONUMENT STAMPED TO IDENTIFY CORNER, MONUMENT IS ON EAST-WEST  $\frac{1}{4}$  LINE 107.64FT. WEST OF CENTER  $\frac{1}{4}$  CORNER.

1989 DOBBRATZ R.L.S. NO.S-973, FOUND MONUMENT, STEEL SIGN POST AND 1 B.T. AS NOTED BY FISHER IN 1982.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

B.T.s ASPEN 7" N.60° W. 18.08FT. (NEW) ①  
 ASPEN 7" S.69° W. 12.56FT. (EXISTING) ④  
 WITNESS MONUMENT 2" DIA. ALUMINUM MONUMENT STAMPED (EXISTING) ②  
 TO IDENTIFY CORNER.  
 STEEL SIGN POST 1.60FT. EAST (EXISTING) ③


REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 26th day  
 of February, 1990 at

10:10 a.m. and recorded  
 in Vol. 11 and recorded

page

CORNER RESTORATIONS  
 Paul Hochstetler  
 Register of Deeds



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

NONE

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

- (g) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

WAYNE G. DOBBRATZ

- (1) I, Wayne G. Dobbratz (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.


Signature

10/20/89

Date

CERTIFICATE READY FOR FILING:

David Staege  
District Ranger




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through j).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 3 and 4, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner restored at the intersection of a line projected from the east quarter through the center quarter and the west section line of Section 3. Placed a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Oak, 16", N.6°E., 38.20 feet
2. Sugar, 7", N.64°E., 52.19 feet
3. Sugar, 8", S.62°E., 41.89 feet
4. Steel Sign Post, West, 1.00 feet



REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this 21st day  
of January ..... A. D., 1985 at  
... 11:00 o'clock... A ..... M. and  
recorded in Vol. C-13 **CORNER RESTORATIONS**  
on page 13  
Paul A. Schenck  
REGISTER

43414042000



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

Affix Land Surveyor Seal



139183

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

CENTER QUARTER CORNER TO SECTION 3,  
TWP. 34 N., R. 14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1857 & 1859 — ORIGINAL SURVEY OF SECTION 3  
1982 — SUBDIVISION OF SECTION 3, BY STEFAN R.L.S. NO. S-1558  
SET 2" DIA. ALUMINUM MONUMENT AT CENTER QUARTER CORNER  
B.T.s TAMARACK 6" N.17° E. 50.94FT., TAMARACK 8" S.29° E. 29.73FT.,  
TAMARACK 10" S.19° W. 26.00FT.  
WITNESS STEEL SIGN POST NORTH 15.00FT.  
1989 — DOBBRATZ R.L.S. NO. S-973, FOUND B.T.s AND POST AS NOTED BY  
STEFAN IN 1982, TOP OF MONUMENT SHEARED OFF BY ROAD GRADER.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 26<sup>th</sup> day  
of February, A.D. 1990 at  
10:10 o'clock A.M. and recorded  
in Vol. C-15 CORNER RESTORATIONS  
page 15


Register of Deeds

B.T.s — ① TAMARACK 6" N.17° E. 50.94FT. (EXISTING)  
② TAMARACK 8" S.29° E. 29.73FT. (EXISTING)  
③ TAMARACK 10" S.19° W. 26.00FT. (EXISTING)

## WITNESS MONUMENTS

- ⑤ 1" X 36" ALUMINUM MONUMENT 16.00FT. (NEW)  
NORTH OF CENTER QUARTER CORNER  
⑥ STEEL SIGN POST 15.05 NORTH OF (EXISTING)  
CENTER QUARTER CORNER  
④ CENTER QUARTER CORNER, REMAINS OF 2"  
DIA. ALUMINUM MONUMENT.

NOTE! 1" X 36" ALUMINUM MONUMENT IS STAMPED  
TO IDENTIFY CORNER.



NOT TO SCALE

43414032020

C-15

C 15

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(NONE)

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

WAYNE G. DOBBRATZ

- (i) I, Wayne G. Dobbratz (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature


10/6/89

Date

CERTIFICATE READY FOR FILING:

Dennis Stange  
District Ranger

Affix Land Surveyor Seal



## CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

} ss.

I Jean F. Resvick, do hereby certify that on the 5th day of May, 1978, I found evidence of the West quarter corner of Section 2 Township 34 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by James McBride

South corrected between Sections 2 and 3, 38.5 chains set quarter corner post.

Hemlock 10, N20E, 9 links

Hemlock 6, S43W, 15 links

N.H. Smith in 1923 replaced old post with iron stake in road.

Description of corner evidence found:

At road intersection north, south, west and fence east  
found iron stake, 14 inches long, 1 1/4 inches in diameter

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced iron stake with 2 inch, inside diameter, galvanized iron pipe,  
3 feet long, filled with concrete, with brass cap stamped:  
T34N, R14E, 1/4, S3, S2, 1978, S-802

Blazed and scribed the following bearing trees:


Maple 13, N71E, 49.80 feet

Maple 19, S20E, 45.71 feet

Maple 9, S47W, 117.39 feet

Northeast corner of house bears N55W

Monument 0.8 feet below surface of road.



● - Corner monument restored

□ -

Resident witnesses.....

Dated at Rhineland Wisconsin, this 17 day of May  
1978....

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER **114054**Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record  
on the 20th day of June 1978, and was filed in Book  
No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Signature Eugene J. Stagny Title Register of Deeds

Township 34 North, Range 14 East, Section 2, Index No. C-17, Page No. \_\_\_\_\_

43414032000

C-17


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 1 and 2, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position found marked by scribed wood post from which the original stumps were found along with 1925 Pine stump set by Nathan Smith. Placed a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Pine, 15", N.82°E., 38.61 feet
2. Tamarack, 5", S.86°W., 51.89 feet
3. Tamarack, 5", N.7°W., 43.25 feet
4. Steel Sign Post, South, 1.50 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 21st day  
of January... A. D., 1935 at  
11:00 o'clock... A... M. and

recorded in Vol. CORNER RESTORATIONS

on page 21...  
Paul Aschenbrenner  
REGISTER

43414022000

C-21

C 21

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date


12/24/84

ORIGINAL ON FILE IN CO CLERK'S OFFICE  
COPY HERE FOR REFERENCE


FIELD SURVEY NOTES  
PRESERVATION OF LANDMARKS  
(Pursuant to Section 59.635(7) Wisconsin Statutes  
E-D-707-69

State of Wisconsin / Department of Transportation


COUNTY <b>FOREST</b>		
TOWN <b>FREEDOM, WARREN</b>		
HIGHWAY <b>STN 32</b>		
SECTION <b>1</b>	TOWNSHIP <b>T 34 N</b>	RANGE <b>R 19 E</b>
TYPE OF LANDMARK <b>R.R. SPIKE &amp; AGREES WITH USFS</b>		



LOCATION SKETCH  
(Location of landmark indicated by "x")



REFERENCE MONUMENTS  
This space for copy of field notes or ties to the above described landmarks



FILED UNDER PROJECT <b>9131-03-70</b>			COUNTY CLERK'S OFFICE COUNTY OF <b>Forest</b> WISCONSIN } 55	
DISTRICT OFFICE NUMBER <b>03-07</b>	CITY <b>RHINELANDER</b>	COUNTY <b>ONEIDA</b>	DATE RECEIVED FOR RECORD <b>7-10-85</b>	DATE COPY SENT TO COUNTY SURVEYOR <b>N/A</b>
LOCATED OR ESTABLISHED BY NAME <b>ROBERT B. JOHNSON</b>			SIGNATURE OF COUNTY CLERK <b>Dora C. James</b>	
TITLE <b>SURVEY CREW CHIEF</b> DATE <b>6-20-85</b> Under the direct supervision of <b>MICHAEL HESS 500899</b>				

139364


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Corner common to Sections 6, 7, 1 and 12,  
 T.34N., R.13-14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1857, A. Millard set wood post and made the following B.T.'s: W. Pine, 40", N.45°W., 24 links (15.84 feet); W. Pine, 12", S.40°W., 37 links (24.42 feet); Sugar, 8", S.15°E., 72 links (47.52 feet); W. Pine, 22", N.80°E., 75 links (49.50 feet).


In 1946, H. Crawford, G.L.O. Surveyor found original B.T. remains. Set a G.L.O. concrete monument with brass cap and made the following B.T.'s: R. Oak, 17", N.14°E., 32 links (21.12 feet); Elm, 7", S.70 3/4°E., 52 links (34.32 feet); Maple, 7", S.56 3/4°W., 42 1/8 links (27.81 feet); Maple, 6", N.71 1/2°W., 21 links (13.86 feet).

In 1988, A. Harrison found corner as per Crawford with Elm B.T. dead and downed. Other B.T.'s alive. Made new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 6" diameter concrete monument with brass cap.
2. Db1. R. Oak, 27", N.12°E., 21.33 feet.
3. Sugar, 11", N.78°E., 29.28 feet.
4. Sugar, 9", S.57°W., 28.68 feet.
5. Sugar, 8", N.72°W., 13.99 feet.
6. Steel sign post, Southeast, 1.82 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29th day  
 of March, A.D., 1990 at  
10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page E-1  
Paul A. Schaeffer  
 Register of Deeds



(a) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Dale B. Staeger  
District Ranger




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

East Meander Corner #1 common to Sections 6 and 7, T.34N., R.14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride, over lake, set meander post and made the following B.T.'s: Hemlock, 12", N.27°E., 13 links (8.58 feet); Cedar, 6", S.30°W., 4 links (2.64 feet).


In 1946, H. Crawford, G.L.O. Surveyor, found original B.T. remains and set a G.L.O. concrete monument and made the following B.T.'s: Maple, 7", S.67°W., 8 links (5.28 feet); Cedar, 5", N.30°W., 16 links (10.56 feet).

In 1988, A. Harrison found corner as per Crawford. Added new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 6" concrete monument with brass cap.
2. R. Maple, 5", N.20°E., 25.51 feet.
3. R. Maple, 13", S.70°W., 5.80 feet.
4. Cedar, 10", N.31°W., 8.98 feet.
5. Steel sign post, South, 1.30 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March A.D., 1990 at  
10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 15-12  
Paul Ackermann  
 Register of Deeds

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

West Meander Corner #1 common to Sections 6 and 7; T.34N., R.14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride hits shore of lake, set a meander post and made the following B.T.'s: Birch, 8", S.21°E., 8 links (5.28 feet); Birch, 10", N.57°W., 7 links (4.62 feet).


In 1946, H. Crawford, G.L.O. Surveyor, found no corner evidence. Set a G.L.O. concrete monument at record distances and made the following B.T.'s: Elm, 8", S.07°W., 38 links (25.08 feet); Birch 12", N.29°W., 3 links (1.98 feet).

In 1988, A. Harrison found corner as per Crawford with Elm B.T. dead and down. Made new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 6" concrete monument with brass cap.
2. R. Oak, 12", S.39°W., 43.29 feet.
3. Hemlock, 8", N.60°W., 24.84 feet.
4. W. Birch, 13", N.28°W., 2.12 feet.
5. Steel sign post, South, 1.55 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29th day  
 of March A.D., 1990 at

10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 5-12

Shandra L. Deddo  
 Register of Deeds  
 Deputy

- (a) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

West Meander Corner #2 common to Sections 6 and 7, T.34N., R.14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride hit shore of lake, set meander post and made the following B.T.'s: Hemlock, 10", S.20°W., 20 links (13.20 feet); Hemlock, 8", N.03°W., 11 links (7.26 feet).


In 1946, H. Crawford, G.L.O. Surveyor, found iron pipe marking corner position. Replaced iron pipe with a G.L.O. concrete monument and made the following B.T.'s: Y. Birch, 6", S.61°W., 14 links (9.24 feet); R. Oak, 8", N.43 1/2°W., 52 links (34.32 feet). Called old railroad grade 1.00 chain West.

In 1988, A. Harrison found monument tipped over and Y. Birch B.T. now a dead stub. Reset monument from Crawford's B.T.'s and added references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 6" concrete monument with brass cap.
2. Sugar, 8", S.05°E., 50.14 feet.
3. Iron Pipe, 1 1/2", S.85°W., 14.57 feet.
4. R. Oak, 18", N.46°W., 34.30 feet.
5. Steel sign post, West, 1.88 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March A.D. 1990 at  
 10:00 o'clock A.M. and recorded  
 in Vol. E-2,3 **CORNER RESTORATIONS**  
 page 5-2,3  
Paul Hechenbrenner  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2) a found perpetuated position

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

Date

CERTIFICATE READY FOR FILING:

Doris Stange  
District Ranger


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

East Meander Corner #2 common to  
 Sections 6 and 7, T.34N., R.14E.,  
 Forest County, Wisconsin



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride over lake and set meander post and made the following B.T.'s: Tamarack, 12", N.79°E., 11 links (7.26 feet); Tamarack, 16", S.10°E., 12 links (7.92 feet).

In 1946, H. Crawford, G.L.O. Surveyor, found cedar post and original tamarack stumps. Set a G.L.O. monument and made the following B.T.'s: W. Birch, 9", N.60°E., 81 links (53.46 feet); W. Birch, 10", S.48°45'E., 49 1/2 links (32.67 feet).


In 1964, J. Resvick, R.L.S., found corner as per Crawford and set a 4" x 4" wood sign post by monument.

In 1990, A. Harrison found corner as per Crawford and Resvick. W. Birch B.T. southeast dead and down. Made new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 6" diameter concrete monument with brass cap stamped to identify corner location.
- W. Birch, 16", N.60°E., 53.20 feet.
- R. Maple, 9", S.38°W., 18.18 feet.
- R. Maple, 6", North, 23.11 feet.
- Wood sign post, South, 0.86 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March, A.D., 1990 at

10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page E-4,5

Paul H. Schaeffer  
 Register of Deeds



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger




U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
● - Corner monument restored.

SECTION CORNER TO SECTIONS - 5, 6, 7 & 8  
TWP. 34 N., R. 14 E. IN FOREST COUNTY



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1859 - ORIGINAL SURVEY BY McBRIDE  
1946 - RESURVEY BY CRAWFORD, SET CONCRETE MONUMENT WITH BRASS CAP TO IDENTIFY CORNER, B.T.s - BASSWOOD 5" N.60 $\frac{1}{2}$ ° E. 34 lks, BASSWOOD 5" S.20 $\frac{1}{2}$ ° E. 33 lks, MAPLE 6" S.32 3/4° W. 143 $\frac{1}{2}$  lks, MAPLE 3" N.47 $\frac{1}{2}$ ° W. 10 $\frac{1}{2}$  lks,  
1977 - RESVICK - STEFAN, FOUND MONUMENT AS SET BY CRAWFORD AND B.T.s, SET STEEL SIGN POST SE OF MONUMENT  
1982 - RESURVEY BY FISHER R.L.S. # S-836, FOUND CONCRETE MONUMENT AS DESCRIBED ABOVE AND B.T.s AS FOLLOWS: BASSWOOD 12" N.60° E. 22.4FT., BASSWOOD 6" S.20E. 21.8FT., MAPLE 12" S.32° E. 93.6FT., MAPLE 8" N.47° W. 6.9FT., STEEL SIGN POST 1FT. SE.  
1989 - CORNER RESTORATION, DOBBRATZ R.L.S. # S-973, FOUND MONUMENT AS DESCRIBED ABOVE CONFIRMED OR CORRECTED ACCESSORIES.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

REGISTER'S OFFICE  
Forest County, Wis.


Received for record this 26 day  
of February, D., 1990 at

10:10 o'clock AM and recorded  
in Vol. CORNER RESTORATIONS  
page E-5

Paul Heckenbrenner  
Register of Deeds

WITNESS B.T.s

- 1 - BASSWOOD 14" N.50° E. 22.05FT. (EXISTING)  
2 - BASSWOOD 6" S.32° E. 21.61FT. (EXISTING)  
3 - MAPLE 14" S.28° W. 94.85FT. (EXISTING)  
4 - MAPLE 10" N.58° W. 6.9FT. (EXISTING)  
5 - SECTION CORNER, CONCRETE MONUMENT WITH BRASS CAP TO IDENTIFY CORNER (EXISTING)  
STEEL SIGN POST, 1FT. SE OF MONUMENT.




43414060000

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED CORNER

(g) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?



(1) I, WAYNE G. DOBBRATZ  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature Wayne G. Dobbratz

Date 9/4/89

CERTIFICATE READY FOR FILING:

Dale H. Hagen  
District Ranger

# CERTIFIED LAND CORNER RESTORATION

Index No. **E 9**


State of Wisconsin }  
County of Forest } ss.

I, Jean F. Resvick, do hereby  
certify that on the 3rd day  
of June, 19 64, I found  
evidence of the Northeast section  
corner of Section 8  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

David Seaberg

Stanley Novak



○ = Corner monument restored.

History of original corner establishment:

Survey in 1859 by James McBride  
80.00 chains north between Sections 8 & 9 set post  
Hemlock 10", N5°E, 57 lks.  
Hemlock 10", S60°E, 70 lks.  
Birch 12", S12°W, 51 lks.  
Ironwood 8", N28°W, 44 lks.

Description of corner evidence found:

Post set by D. Seaberg to mark point of post found in 1962  
Hemlock stump and fallen snag, 15", S60°E, 46.2 feet, old face blaze  
Hemlock stump 14", N5°E, 37.60 ft.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced post with 2-inch inside diameter galvanized iron pipe flanged at bottom,  
filled with concrete, with brass cap stamped:

T34N R14E  
S 5 | S 4  
S 8 | S 9  
1964  
S-802

from which the following blazed and scribed bearing trees bear:

Maple 5", S13°E, 17.65 ft. (26.74 lks)  
Maple 6", S54°W, 35.82 ft. (54.27 lks)  
Cherry 4", N50°W, 19.75 ft. (29.92 lks)  
Maple 3", N49°E, 32.20 ft. (48.79 lks)

Dated at Rhineland, Wis., this 3rd day of August, 19 64.

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21 day of Oct., 19 64  
at 11 o'clock A. M. Doc. #89305 Vol. 1 Page **E-9 CORNER RESTORATIONS**

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 4 and 9, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found corner position marked by 1½" iron pipe and referenced by 2 scribed bearing trees. No original evidence existing. Found both stumps of N. Smith's bearing trees from 1912 survey at proper distance and bearing from said iron pipe. Placed a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Oak, 10", N.68°E., 43.45 feet
2. Sugar, 4", N.81°W., 5.78 feet
3. Sugar, 7", S.20°E., 5.67 feet
4. Steel Sign Post, South, 1.50 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... *21st* day

of *January*.....A. D., 19*85* at

...*11:00* o'clock... *A*.....M. and

recorded in Vol. *CORNER RESTORATIONS*

on page *E-11*

*Paul Aschenbrenner*  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) I, Milo E. Stefan  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

Affix Land Surveyor Seal




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).


- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Corner to Sections 3, 4, 9, and 10, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
 In 1859, James McBride set wood post and made the following BTs: Birch, 24", N.66°W., 18 links; Birch, 30", N.64°E., 72 links; Birch, 20", S.57°E., 54 links; Birch, 10", S.34°W., 7 links.  
 In 1912, N. Smith found corner and made new BTs: Hemlock, 26", N.50°45'E., 91 links; Sugar, 14", S.19°30'W., 81 links.  
 In 1961, Jean Resvick found location tag from CCCs.  
 In 1982, Milo Stefan found what was thought to be Smith's corner and monumented same.  
 In 1986, Alan Harrison--retracement of Smith's 1912 survey of north line of Section 9 from N 1/4 through E 1/16 corner indicates location 5 feet south of a Sugar found with location poster at base. Because of positive identification of N 1/4 and E 1/16 on north line of Section 9, I accept the above as the best location of this corner. Milo Stefan has verbally approved of this change in corner location.  
 (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.
- 2" x 36" aluminum monument stamped to identify the corner location.
  - Sugar, 7", N.25°E., 59.14 feet
  - Red Maple, 5", S.88°E., 10.48 feet
  - Sugar, 8", S.3°W., 16.61 feet
  - Sugar, 7", N.40°W., 42.93 feet
  - Steel Sign Post, Southwest, 1.02 feet



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
 1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page E-13  
 Paul Aschebrenner  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Yes. Corner location set by Milo Stefan, R.L.S., S.2°50'E., 122.06' (removed).

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

11/14/86  
Date






# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS :** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 3, 4, 9, and 10, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position recovered from original Birch stump and N. Smith's two resurvey bearing trees from 1912.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar, 4", N.33°E., 17.07 feet
2. Sugar, 7", S.43°E., 46.94 feet
3. Sugar, 6", S.15°W., 27.79 feet
4. Sugar, 5", N.84°W., 29.01 feet
5. Steel Sign Post, S.80°E., 1.60 feet



REGISTER'S OFFICE }  
 Forest County, Wis. }  
 Received for record this 21st day  
 of January, A. D., 1985 at  
11:00 o'clock A. M. and  
 recorded in Vol. CORNER RESTORATIONS  
 on page F-13  
Paul Aschenbrenner  
 REGISTER


(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated corner location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date


12/24/84

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 3 and 10, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set post and made the following BTs: Sugar, 10", S.64°E., 17 links; Hemlock, 8", N.12°E., 25 links.

In 1924, N. Smith found corner and made new BTs: Hemlock, 26", S.65°W., 47 links; Hemlock, 14", N.40½°E., 40 links.


In 1936, A. Vronch found scribed Hemlock post and put location poster on 6" Maple, N.63°E., 15 links.

In 1986, Alan Harrison retraced Smith's survey through center of Section 10 and set position from which the following were located: Hemlock stump, 18", N.40°E., 26.8 feet and location poster lying on ground at N.20°E., 10.9 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify the corner location.
2. Sugar, 8", N.41°E., 45.25 feet
3. Sugar, 7", S.77°W., 23.79 feet
4. Sugar, 7", N.32°W., 63.54 feet
5. Steel Sign Post, Northeast, 0.90 feet



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
 1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page E-15  
 Paul A. Schenck  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

No.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?


No.

- (i) Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

11/14/86



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## I N S T R U C T I O N S :

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 2, 3, 10, and 11,  
T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored from witness iron pipe and wood post 22 feet east of centerline of Richardson Lake Road. Distances of N. Smith's survey of 1925 fit. Placed a 2" x 30" aluminum monument 12" below surface of centerline of said road.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Maple, 9", N.48°E., 51.11 feet
2. White Pine, 22", S.39°E., 58.94 feet
3. Red Maple, 10", S.26°W., 57.75 feet
4. White Pine, 23", N.86°W., 38.01 feet
5. Steel Sign Post, East, 20.10 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 11<sup>th</sup> day  
of... January... A. D., 1985 at  
1:00... o'clock... P... M. and

recorded in Vol. CORNER RESTORATIONS  
on page E-17.

Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated position.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(1) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/8/84  
Date

Affix Land Surveyor Seal




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 2 and 11, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner restored from remains of original Hemlock bearing tree. Distances fit N. Smith's 1925 survey east and west. Placed a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Red Pine, 10", S.72°E., 28.50 feet
2. Red Pine, 8", S.82°W., 31.29 feet
3. Red Pine, 9", N.49°W., 3.04 feet
4. Steel Sign Post, West, 0.80 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 11<sup>th</sup> day  
of... January... A.D., 1985 at  
... 1:00... o'clock... P... M. and

recorded in Vol. ... CORNER RESTORATIONS

on page... F-19...  
Paul Aschenbrenner  
REGISTER

43414020020

E-19

T 34-14

E 1  
19

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(1) 1. Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/8/84  
Date



# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 1, 2, 11, and 12,  
T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

At corner position, found post point and original bearing tree stump and stump holes.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Balsam Fir, 5", N.14°E., 29.93 feet
2. Red Maple, 5", S.60°E., 40.94 feet
3. Red Pine, 10", S.5°W., 10.52 feet
4. Red Pine, 9", N.86°W., 37.06 feet
5. Steel Sign Post, West, 3.25 feet



REGISTER'S OFFICE )

Forest County, Wis. )

Received for record this... day

of... January... A. D., 1985

... 11:00 ... o'clock ... A. ... M. and

recorded in Vol. CORNER RESTORATIONS

on page... F. 21  
Paul A. Schenck  
REGISTER

43414 020000

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

12/24/84


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**I N S T R U C T I O N S :** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 1 and 12, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position found marked by a scribed wood post with original-type scribe marks.  
Placed a 2" x 120" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Tamarack, 5", N.69°E., 18.47 feet
2. Tamarack, 4", S.48°E., 32.63 feet
3. Tamarack, 5", N.71°W., 47.77 feet
4. Steel Sign Post, North, 2.40 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 21st day  
of... January ... A. D., 19... at  
... 11:00 o'clock... A ... M. and

recorded in Vol. CORNER RESTORATIONS

on page F-23

Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found original corner post.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(1) Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control, and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

12/24/84  
Date

127700

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 1, 6, 7, and 12,  
T.34N., R.14-15E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner restored at the extension of the centerline of State Highway #32 from the north and N. Smith's distance from the town corner 1 mile north, as per survey notes. Set a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Spruce, 7", N.33°W., 197.98 feet
2. "X" on north end of west bridge abutment, N.30°E., 215.45 feet
3. "X" on south end of west bridge abutment, N.49°E., 168.83 feet
4. Steel Sign Post, Northeast, 1.90 feet
5. Steel Sign Post, Southwest, 1.30 feet



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this... 1st... day  
of... April... A. D., 1985

2:05... o'clock... P... M. and  
recorded in Vol. ... of RESTORATIONS

on page E-25  
Paul Aschenbrenner  
REGISTER

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


Distances south and north fit with 1906 Nathan Smith survey.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) An obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.



- (i) I, Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

State of Wisconsin  
County of FOREST

ss. ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS.

I NEAL SPERHAKE, do hereby certify that on the TWENTIETH day of OCTOBER, 19 64, I established the NORTH ONE SIXTEENTH CORNER BETWEEN SECTION 12, TOWNSHIP 34 NORTH, RANGE 13 EAST, AND SECTION 7, TOWNSHIP 34 NORTH, RANGE 14 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:

At the point determined for the location of the corner I emplaced a:


GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N. N 1/16 BTWN. 12 & 7 R13-14E SPERHAKE RLS 463 10/20/64."

The pipe is witnessed by:

Maple 5 N 10°E 19 links. (SCRIBED S 7 BT).

Maple 5 N 72°W 23 links. (SCRIBED S12 BT).


Description as to how corner was located: Since both the section corner  $\frac{1}{4}$  mile north and the quarter corner  $\frac{1}{4}$  mile south have been previously established with a distance between them of 39.92 $\frac{1}{2}$  chains, the 1/16th. corner was set 19.96 $\frac{1}{4}$  chains from either corner and on a straight line between them.



0 = Corner monument restored

89627

REGISTRARS OFFICE  
FOREST COUNTY, WIS.



Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 12th day of January, 19 65.

Signature \_\_\_\_\_

Title Registered Land Surveyor Registration No. 463

~~County of~~ Forest ~~County of~~ Wisconsin,  
I hereby certify that the within instrument was ~~filed for record~~  
~~office for record~~ on the 12th day of January  
19 65, and was ~~filed for record~~ signed and ~~Page No.~~ sworn to  
~~of County Records~~ before me.

Surveyor's Seal

Signature Anna Peterson Title Notary Public

43413123000

Index No.

71

State of Wisconsin

County of FOREST

ss. RESTORATION OF LOST ORIGINAL GOVERNMENT SURVEY CORNER.

I NEAL SPERHAKE, do hereby certify that on the SEVENTH day of OCTOBER, 1964, I established the CENTER OF THE NORTHEAST QUARTER OF SECTION 7, TOWNSHIP 34 NORTH, RANGE 14 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:

At the point determined for the location of the corner I emplaced a:


GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N CENTER NE $\frac{1}{4}$  S7 R14E SPERHAKE RLS 463 10/7/64."

The pipe is witnessed by:


Bass 4 N 81°W 56 links. (SCRIBED S7 BT).

Description as to how corner was located: The U. S. Forest Service owns the entire section 7, T34N-R14E, with the exception of government lots 1, 2 and 3, which are owned by the Kimberly-Clark Corporation. To determine the boundary line between forest service and corporation lands, it was agreed upon by Neal Sperhake, registered land surveyor and employee of the Kimberly-Clark Corporation, and David Seaberg, district ranger for the forest service, to do a straight line survey between the previously established north sixteenth corners on the east and west sides of section 7. The center of the northeast quarter was to be established on this east-west sixteenth line at a proportioned east-west distance. The expense of sub-dividing the entire section prohibited using this more proper method of determining the line and corner in question. The northeast and northwest section corners and the east quarter section and west quarter section corners of section 7 had been previously established. From them the north sixteenth between sections 7 and 8, and the north sixteenth between section 7, T34N-R14E, and section 12, T34N-R13E, were determined. The original length of the north side of section 7 was 82.18 chains. The original length of the south side of section 7 was 83.04 chains. The original distance between the east and west quarter section corners of section 7 would then have been assumed to be 82.61 chains, and the original distance between the two north sixteenth corners on the east and west boundaries of section 7 would have been assumed to be 82.39 $\frac{1}{2}$  chains. A straight line between the two north sixteenth corners was then run. It was agreed between the two representatives of the Forest service and the Kimberly-Clark Corporation that the south boundary of

(continued on back)



O = Corner monument restored



Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 12th day of January, 1965.

Signature Neal Sperhake

Title Registered Land Surveyor Registration No. 463

~~Office of~~ Forest County ~~of~~ Wisconsin,

I hereby certify that the within instrument was ~~filed in this~~ filed in this office for record on the 12th day of January, 1965, and was ~~filed in Book No.~~ signed and ~~Page No.~~ sworn to of ~~County Records.~~ before me

Surveyor's Seal

Signature Anna Peterson Title Notary Public

43413073010

Index No. F 4



139365


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter corner common to Sections 7 and 12,  
 T.34N., R.13-14E., Forest County, Wisconsin



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1857, A. Millard made a 12" Elm the corner and made the following B.T.'s: W. Birch, 12", N.50°W., 24 links (15.84 feet); Sugar, 18", N.78°E., 20 links (13.20 feet).


In 1961, N. Sperhake, R.L.S., found stump of original corner tree and set a K-C monument and made the following B.T.'s: Basswood, 4", S.07°W., 25 links (16.50 feet); Basswood, 9", N.08°E., 48 links (31.68 feet).

In 1988, A. Harrison found corner as per Sperhake with Northeast Basswood dead. Made new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Kimberly-Clark monument with cap stamped to identify corner location.
2. Sugar, 4", N.35°E., 47.44 feet.
3. Basswood, 12", S.87°E., 31.80 feet.
4. Basswood, 8", S.07°W., 16.13 feet.
5. Steel sign post, South, 0.62 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March A.D., 1990 at  
10:00 o'clock A.M. and recorded  
 in Vol. 6-1 **CORNER RESTORATIONS**  
 page 6-1  
Paul Acklenbrenner  
 Register of Deeds

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter corner common to Sections 7 and 8,  
 T.34N., R.14E., Forest County, Wisconsin



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride set quarter post and made the following B.T.'s: Tamarack, 12", S.08°W., 23 links (15.18 feet); Birch, 7", N.46°E., 17 links (11.22 feet).

In 1946, H. Crawford, G.L.O. Surveyor, found original tamarack B.T. Set G.L.O. monument and made the following B.T.'s: Y. Birch, 7", N. 70 3/4°W., 32 links (21.12 feet); Elm, 5", S.43°E., 21 1/2 links (14.19 feet).


In 1977, J. Resvick, R.L.S., found corner as per Crawford.

In 1988, A. Harrison found corner as per Crawford and added new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 6" concrete monument with brass cap.
2. W. Birch, 12", N.11°E., 62.83 feet.
3. R. Maple, 7", S.69°E., 36.15 feet.
4. Y. Birch, 8", N.73°W., 20.88 feet.
5. Steel sign post, Northwest, 0.65 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29 day  
 of March A.D. 1990 at

10:00 o'clock A.M. and recorded  
 in Vol. 6-5 **CORNER RESTORATIONS**  
 page 5

Paul A. Schaeffer  
 Register of Deeds

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison


(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

District Ranger



## DOCUMENT NUMBER

136770

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Quarter corner to Sections 8 and 9,  
T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 13<sup>th</sup> day  
of January A.D., 1989 at  
10:00 o'clock P.M. and recorded  
in Vol. 3-9 **CORNER RESTORATIONS**  
page 3-9

Paul H. Schaeffer  
Register of Deeds.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
In 1859, James McBride set a wood post with the following B.T.s: Sugar, 8", S.25N., 12 links, (7.92'); Sugar, 7", N.22E., 11 links, (7.26').


In 1932, J. W. White found a burned stake with one B.T.: Maple, 24", S. of E., 6 feet, he set a new stake and placed a metal location poster on a Maple, 24" South of stake.

In 1987, Alan Harrison, (RLS) searched area and found 2½" iron well point in a mound of rock. Location tag on a Hemlock, 24", bears S.45E., 70 feet from well point. Found no evidence of original or Maple B.T. found by White in 1934. Well point fits section and is accepted as best remaining evidence on corner location. We replaced well point with a 2½" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2½" x 36" aluminum monument stamped to identify the corner location.
2. Hemlock, 13", N.09E., 54.54 feet.
3. Sugar, 4", S.20E., 26.80 feet.
4. Sugar, 14", N.59W., 45.64 feet.
5. Steel sign post, North, 0.88 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 1/6/89  
Signature Date

Certificate ready for filing: Dale S. Stage  
District Ranger




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 9 and 10, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set quarter post and made the following BTs: Hemlock, 10", N.43°W., 12 links; Hemlock, 8", N.84°E., 14 links.

In 1906, N. Smith found post and one BT standing. Set new BTs: Hemlock, 10", S.57°E., 51 links; Birch, 30", S.84°W., 51 3/4 links.


In 1937, A. Vronch found Pine post and put tag on Maple, 8", S.40°E., 47 links.

In 1986, Alan Harrison used retracement of Smith's survey of Section 10 to set position of corner. Could find no evidence of existing corner as area was burned extensively years prior.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 2" x 36" aluminum monument stamped to identify the corner location.
- Balsam, 11", N.19°E., 6.90 feet
- Sugar, 6", S.74°W., 67.82 feet
- Sugar, 8", N.55°W., 71.73 feet
- Steel Sign Post, Southeast, 0.74 feet



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 6-13  
*Paul Hochbrenner*  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.


- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

Date

11/14/86




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 10 and 11, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set witness corner at 32.60 chains on south shore of lake and made the following BTs: Birch, 8", S.74°E., 20 links; Birch, 6", S.73°W., 18 links.

In 1906, N. Smith set new post and made the following BTs: Birch, 8", N.40°W., 11½ links; Birch, 7", N.89°15'E., 15 links.

In 1963, Jean Resvick found lake dammed and water raised--fence line south of lake. Found no evidence of corner.


In 1986, Alan Harrison restored quarter corner position in lake by retracement of Smith's surveys of interior and east line of Section 10. Witness the quarter corner on south and west sides of lake.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Witness Corner, South, 471.36 feet
2. Hemlock, 10", S.45°E., 32.94 feet
3. Hemlock, 9", S.16°E., 35.52 feet
4. Hemlock, 12", S.54°W., 27.25 feet
5. Steel Sign Post, South, 0.70 feet

1. Witness Corner, West, 1189.01 feet
2. Hemlock, 15", S.20°E., 30.09 feet
3. Red Maple, 7", S.66°W., 22.96 feet
4. Balsam, 5", N.50°W., 38.21 feet
5. Steel Sign Post, West, 0.91 feet



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
 1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 9-17  
 Paul Achenbrenner  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?


No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

11/14/86  
Date

Affix Land Surveyor Seal



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 11 and 12, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position found marked by a scribed wood post from which the remains of the original bearing trees were found. Placed a 2" x 60" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Pine, 18", S.4°W., 213.12 feet
2. White Birch, 14", S.76°W., 79.86 feet
3. Steel Sign Post, Northwest, 1.30 feet



REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this... 21st ...day  
of... January... A. D., 1985 at  
... 11:00... o'clock... A... M. and  
recorded in Vol. CORNER RESTORATIONS  
on page G-21  
Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found original location of corner.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(1) 1. Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

12/24/84  
Date


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

CENTER EAST 1/16 CORNER TO SECTION 12,  
 TWP. 34 N., R.14 E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1857 & 1859 — ORIGINAL SURVEY OF SECTION 12  
 1982 — SUBDIVISION OF SECTION 12, BY STEFAN R.L.S. NO. S-1558,  
 SET 2" DIA. ALUMINUM MONUMENT AT CENTER EAST 1/16 CORNER  
 B.T.s SUGAR MAPLE 9" S.25° E. 33.57 FT., SUGAR MAPLE 9" S.9° W.  
 52.6 FT., SUGAR MAPLE 7" N.51° W. 17.25 FT.  
 WITNESS STEEL SIGN POST WEST 4.32 FT.  
 1989 — DOBBRATZ R.L.S. NO. S-973. FOUND B.T.s AND POST AS NOTED BY STEFAN  
 IN 1982, NO MONUMENT FOUND!

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 26<sup>th</sup> day  
 of February, A.D., 1990 at


10:10 o'clock AM, and recorded  
 in Vol. CORNER RESTORATIONS  
 page 6-24

Paul Hohenbrenner  
 Register of Deeds

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

B.T.s SUGAR MAPLE 9" S.25° E. 33.57 FT. (EXISTING) ①  
 SUGAR MAPLE 9" S.9° W. 52.6 FT. (EXISTING) ②  
 SUGAR MAPLE 7" N.51° W. 17.25 FT. (EXISTING) ③  
 WITNESS MONUMENTS STEEL SIGN POST WEST 4.32 FT. (EXISTING) ④  
 1" X 36" ALUMINUM MONUMENT 1.28 FT. ⑤  
 SOUTH OF CENTER EAST 1/16 CORNER,  
 STAMPED TO IDENTIFY CORNER

NOTE! UNABLE TO SET MONUMENT AT TRUE CORNER  
 DUE TO BOULDER 10" BELOW SURFACE!  
 SET 1" DIAMETER IRON PIPE IN ROCK  
 PILE OVER BOULDER AT TRUE CORNER.




(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) FOUND PERPETUATED LOCATION

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?



(i) I, WAYNE G. DOBBRATZ  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

9/18/89

Date

CERTIFICATE READY FOR FILING:


Dale S. Stagg  
District Ranger

### INSTRUCTIONS:

(a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 7 and 12, T.34N.,  
R.14-15E.



(b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Corner restored incenterline of State Highway #52 off fence lines east and west. Corner marked by a railroad spike witnessed by a 2" x 36" aluminum monument.

(c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

Describe witness monuments.

(d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Witness Monument, N.85°35.6'E., 75.00 feet
2. Sugar, 20", N.33°E., 58.33 feet
3. Sugar, 8", N.61°E., 79.97 feet
4. Utility Pole, South, 3.85 feet
5. Steel Sign Post, East, 1.60 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this.....day  
of April.....A. D., 1985 at  
2:05.....o'clock.....P.....M. and

recorded in Vol. **CORNER RESTORATIONS**  
on page **G-25**

on page G-25  
Paul Aschenbrenner  
REGISTER

G-25

25

43414120000

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


An obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

- (i) I, Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

1/7/85  
Date





139369


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Corner common to Sections 7-12-13-18,  
 T.34N., R.13-14E., Forest County,  
 Wisconsin



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set post and made the following bearing trees: Elm, 18", N.75°W., 27 links (17.82'); Hemlock, 14", S.33°W., 19 links (12.54')  
 Hemlock, 14", S.62°E., 19 links (12.54'); Hemlock, 12", N.54°E., 74 links (48.84')


In 1961, N. Sperhake found original scribed Hemlock stump Southeast. Set iron pipe monument. Certificate on file.

In 1988, A. Harrison found corner as per Sperhake and added new reference.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 1" iron pipe with cap stamped to identify corner location.
2. Elm, 8", N.44°E., 33.65 feet (Sperhake)
3. Sugar, 10", S.31°E., 42.91 feet
4. Sugar, 6", S.40°W., 36.41 feet.
5. Elm, 8", N.55°W., 34.60 feet (Sperhake)
6. Steel sign post, North, 0.87 feet



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29th day  
 of March A.D. 1990 at

10:00 o'clock A.M. and recorded

in Vol. CORNER RESTORATIONS  
 page 5-1

Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2) a found perpetuated location

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 3/9/90  
Signature Date



CERTIFICATE READY FOR FILING:

Dale B. Staege  
District Ranger

139367


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter corner to Sections 7 and 18,  
 T.34N., R.14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set a wood post with the following B.T.'s: Sugar, 12", N.21°W., 15 links (9.90 feet); Hemlock, 36", S.63°E., 13 links (8.58 feet).


In 1937, A.J. Vronch found a 4" hemlock that had been recently placed with no b.t.s to post. He placed a metal location poster on the Northeast side of a 4" elm from which the corner bears N.41°E., 0.36 chains (23.76 feet).

In 1988, A. Harrison, R.L.S., found the metal location poster on the ground next to a 12" elm. At N.41°E., 23.76 feet from elm found a post hole with no remains of post evident. Accepted post hole as best available evidence of corner location and monumented same.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2½" x 36" aluminum monument with tablet stamped to identify the corner location.
2. Sugar, 4", N.60°E., 51.33 feet.
3. Sugar, 5", S.21°E., 20.61 feet.
4. Sugar, 5", S.73°W., 30.65 feet.
5. Steel sign post, Northwest, 0.79 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29 day  
 of March, A.D., 1990 at

10:00 o'clock AM and recorded  
 in Vol. CORNER RESTORATIONS

page J-3

Paul H. Schenck  
 Register of Deeds

43414070020

(a) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2) a found perpetuated location

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

Date

CERTIFICATE READY FOR FILING:

Dale S. Stage  
District Ranger


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Corner to Sections 7, 8, 17, and 18, T.34N., R.14E., Forest County, Wisconsin.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 3rd day  
 of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS

Page 5-5  
Paul Aschenbrenner  
 Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and made the following BTs: Hemlock, 24", N.73°W., 24 links; Hemlock, 10", N.12°E., 46 links; Hemlock, 24", S.55°E., 27 links; Hemlock, 30", S.60°W., 28 links.

In 1936, Jerome Breen, CCC Compassman, found 5" scribed wood post and Maple BT, 32", S.40°W., 0.15 links. Corner on old railroad right-of-way.


In 1963, Jean Resvick found 5" scribed wood post in rock mound and stumps of northeast and southeast original BTs and Maple BT found by CCC. Swamp calls south and west fit within 1/2 chain. Set brass cap monument in place of post.

In 1986, Alan Harrison made new BTs to reference <sup>THE</sup> corner.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 2" brass capped monument stamped to identify the corner location.
- White Ash, 12", N.56°E., 14.54 feet
- Sugar, 8", S.65°E., 45.46 feet
- White Ash, 6", S.26°W., 32.93 feet
- Sugar, 4", N.63°W., 43.81 feet
- Steel Sign Post, South, 1.60 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?


No.

(i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

12/3/86




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter corner to Sections 8 and 17, T.34N., R.14E., Forest County, Wisconsin.

REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D. 1986 at  
1:30 o'clock P.M. and recorded  
 in Vol. 1 **CORNER RESTORATIONS**  
 page 7  
*Paul Achenbrenner*  
 Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1857, James McBride set wood post at 39.85 chains and made the following BTs: Hemlock, 10", S.24°E., 12 links; Birch, 20", N.4°W., 41 links.

In 1934, J. White, CCC Land Examiner, found stake in good condition.


In 1937, A. Vronch, CCC, found Cedar stake in good condition. Put location poster on Hemlock, 5", on south side of tree, .08 links.

In 1986, Alan Harrison found rockpile with remains of old post lying on rocks and post point in center. Original Hemlock stump recovered and stump and root holes of large hardwood at bearing and distance of Birch BT. Set 2 1/2" aluminum monument and made BTs.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 2 1/2" aluminum monument stamped to identify the corner location.
- White Ash, 6", N.43°E., 13.65 feet
- Sugar, 6", S.27°E., 19.96 feet
- Sugar, 6", N.26°W., 19.03 feet
- Steel Sign Post, Southwest, 1.00 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

12/3/86  
Date






# CERTIFIED LAND CORNER RESTORATION

Index No. 59

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby  
certify that on the 3rd day  
of June, 19 64, I found  
evidence of the Southeast Section  
corner of Section 8  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

Surveyed in 1859 by James McBride  
80.00 chains north between sections 16 & 17 set post  
Linn 20", N52°W, 23 Lks (15.18 ft.)  
Hemlock 16", N51°E, 26 Lks (17.16 ft.)  
Hemlock 12", S57°E, 45 Lks (29.70 ft.)  
Hemlock 12", S33°W, 30 Lks (19.80 ft.)

Description of corner evidence found:

Squared hemlock post under fallen Yellow Birch with Forest Service tag on.  
Bottom of post found in mound of rock under yellow birch.  
24-inch hemlock stump, backgrowth of scribing readable in hollow center,  
S62°E, 29.70 ft. from post.  
Hemlock stump, rotted, N46°E, 17.20 ft.  
Hemlock stump, S45°W, 15.0 feet  
Black cherry 8", N46°E, 4.45 ft., scribed S9 B.T.  
Linn 6", S79°W, 9.70 ft., scribed S17 B.T.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced hemlock post with 2-inch inside diameter, galvanized iron pipe, 5 feet long,  
flanged at bottom, filled with concrete, with brass cap stamped:

T34N R14E  
S 8 | S 9  
S17 | S16  
1964  
S-802

from which the following new blazed and scribed bearing trees bear:

Ironwood 6", N34°E, 18.50 ft. (28.03 Lks)  
Maple 6", S20°E, 19.10 ft. (28.94 Lks)  
Maple 6", S61°W, 29.90 ft. (45.30 Lks)  
Maple 7", N55°W, 45.82 ft. (69.42 Lks)

Dated at Rhineland, Wis., this 3rd day of August, 1964

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21 day of Oct, 19 64  
at 11 o'clock A. M. Doc. #89306 Vol. 1 Page J-9 CORNER RESTORATIONS

Anna Peterson 89306  
(Register of Deeds)


By \_\_\_\_\_ Deputy

U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

Quarter corner to Sections 9 and 16,  
T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 13<sup>th</sup> day  
of January A.D., 1989 at  
10:00 o'clock AM and recorded  
in Vol. CORNER RESTORATIONS  
page 1-11  
Paul Hechenbrenner  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
In 1859, James McBride set a wood post with the following B.T.s: Hemlock, 16", S.52W., 16 links, (10.56'); Birch, 8", N.46E., 24 links, (15.84').


In 1936, H. Powell found a wood post scribed for the corner with the following B.T.s: Birch snag, 8", N.41½E., 12.21 feet; Hemlock, 12", S.28E., 13.86 feet. He placed a metal location poster on a Yellow Birch, 12", N.86W., 8.58 feet, poster is on the east side of the tree.

In 1987, Alan Harrison, R.L.S.) found: Location poster on a 14" Birch Snag, pulled S.86E., 8.58 feet and found a post point and remains of a rotted post. From post point at; N.41E. 12.2 feet a 10" birch stump; S.28W. 13.9 feet a 14" hemlock stump; S.52W. 10.6 feet to remains of a hemlock stump. Accepted post point as best remaining evidence of original corner. Replaced post point with a 2½" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2½" x 36" aluminum monument with tablet stamped to identify the corner location.
2. W. Pine, 9", N.67E., 37.41 feet.
3. Sugar, 7", S.02E., 26.41 feet.
4. Hemlock, 12", S.59W., 47.29 feet.
5. Steel sign post, East, 0.86 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

- (g) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.


- (1) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

1/6/89  
Date

Certificate ready for filing.

Paul S. Stange  
District Ranger



# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section Corner to Sections 9, 10, 15, and 16,  
T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 3rd day  
of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS  
page J-13  
Paul Achenbrenner  
Register of Deeds.

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride, section corner falls in lake--set witness corners on north, south, east, and west sides of lake and made BTs.

In 1909, N. Smith found south witness post and set N 1/8 to Sections 15 and 16. Witnesses o.k.


In 1934, J. W. White found north witness post and two BTs: White Birch, 8", Northwest, 12 feet; Tamarack, 9", Southwest, 12 feet.

In 1985, Alan Harrison, lake was dammed in mid-1960s, causing bog mats to float and move from original positions. Corner restored by retracement of Smith's survey from West 1/4 through North 1/16 corners of Section 15. Section corner witnessed on north and south shore of lake.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- A. Witness Corner, North, 965.30 feet  
1. 2" x 36" aluminum monument stamped as North W.C.  
2. Sugar, 8", N.30°E., 13.30 feet  
3. Sugar, 8", N.66°E., 19.20 feet  
4. White Birch, 12", N.11°W., 11.60 feet  
5. Steel Sign Post, 6', North, 1.00 feet
- B. Witness Corner, South, 648.81 feet  
1. 2" x 36" aluminum monument stamped as South W.C.  
2. Sugar, 4", South, 17.00 feet  
3. Sugar, 6", S.48°W., 18.54 feet  
4. Balsam, 6", S.88°W., 32.34 feet  
5. Steel Sign Post, 6', North, 0.70 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (gah) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

11/14/86  
Date




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 10 and 15, T.34N., R.14E.



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
 1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page J-15  
*Paul H. Schaeffer*  
 Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Fir, 10", N.26°E., 17 links; Birch, 16", S.52°E., 85 links.


In 1906, N. Smith found original Birch standing, Fir was a rotted stump.

April 16, 1986, Al Harrison searched area. Position falls in a 5-year old clearcut. Found no evidence of corner position. Set corner at retracement of N. Smith's survey of Section 15 from C<sub>4</sub> through CN 1/16.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. A 2 1/2" x 36" aluminum monument stamped to identify the corner.
2. Balsam, 5", S.10°W., 31.17 feet
3. Steel Sign Post, East, 1.11 feet
4. Steel Sign Post, Northwest, 1.42 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Section Corner to Sections 10, 11, 14, and 15,  
T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 3rd day  
of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS  
page J-17

Faul Achenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Birch, 14", N.27°W., 29 links; Sugar, 8", N.48°E., 4 links; Birch, 12", S.25°E., 28 links; Sugar, 12", S.29°W., 30 links.

1906, 1909, and 1916, N. Smith was at this corner for subdivisions of Sections 10, 11, and 15. Called stake by W. L. Harris in 1906.


In 1934, J. W. White found rotted stake. Location poster on fence corner north approximately 15 feet. Corner in center of road.

In 1986, Alan Harrison found corner falls in road. Set P.K. nail by aligning centerline of State Highway 52 east and south and off fence line north. This position fits Smith's 1909 survey of Section 15.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- Railroad spike at intersection of State Highway 52 and County Highway W. Center punched as corner position.
- Reference Monument, 2" x 36", North, 40.00 feet
- Sugar, 9", N.26°E., 66.37 feet
- Reference Monument, 2" x 36", South, 40.00 feet
- Power Pole #3414-10R1-25A, N.33°W., 42.81 feet
- Steel Sign Post, 6', North, 39.00 feet





- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

Alan D. Harrison

- (i) I, Alan D. Harrison (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 11/14/86  
Signature Date



# Document Number

195324

## REGISTER'S OFFICE Forest County, Wis.

Received for record this 29<sup>th</sup> day  
of August A.D., 2007 at  
2:09 o'clock P.M. and recorded  
in Vol. Corner Restoration  
page J-19

Kay Swanson, Deputy  
Register of Deeds

## U.S. PUBLIC LAND SURVEY MONUMENT RECORD

(As Required by WI Adm. Code)

History of original corner establishment and subsequent restorations and descriptions of any record, monument, occupational, testimonial or other evidence considered:

1859 - James McBride, set quarter post and made the following B.T.'s:

Fir, 12", N 19° E, 44 lks., 29.04 feet.  
Birch, 10", S 26° W, 30 lks., 19.80 feet.


2007 - I found no evidence of the original corner or accessories.

I set 1/4 corner midpoint and on line between the NW and NE corners of Section 14.

Corner was: (Check All That Apply)

- ☐ Restored through acceptance of an obliterated evidence location.
- ☐ Restored through acceptance of a found perpetuated location.
- ☒ Considered a lost corner and reestablished through lost corner proportionate methods (include a plan view drawing showing distances and directions to other Public Land Survey Corners used for proportioning and determining the corner location).
- ☐ Restored or reestablished in a location that differs from a previous restoration or reestablishment (include a plan view drawing and indicate what was set and/or found).

Describe the monument and accessories used to perpetuate the location of this corner (include a plan view drawing and indicate what was set and/or found).







### LEGEND:

- ☒ Existing Monument of Record
- ☒ North 1/4 Corner PK Nail Set
- ☒ 2" x 30" Forest County Aluminum Pipe Reference Monument Set
- ☐ Existing 4" x 4" wood plantation post
- ☐ Existing Utility Pole #3414-14w8 measured to PK nail in side
- ☐ 1" x 30" Iron Pipe Set

Note: Distances are taken to nail in side of tree.

Sketch Not To Scale



I, Michael A. Trembl, RLS  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Michael A. Trembl 8/2/07  
Signature Date

The North 1/4 corner of  
Section 14 T. 34 N., R. 14 E.  
Forest County, WI

Index No. J-19  
2007

43414110020

J-19

127702

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 11, 12, 13, and 14,  
T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored at the intersection of centerlines of State Highway #52 and Range Line Road. Position conforms with N. Smith's survey of 1908. Corner marked by a railroad spike in centerline of roads and referenced by a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Reference Monument, Northwest, 50.00 feet
2. Balsam Fir, 8", S.72°W., 5.48 feet
3. Red Maple, 7", N.9°W., 51.48 feet
4. Steel Sign Post, North, 0.70 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 1st day

of April... A.D., 1985 at

12:05 o'clock... P.M. and

recorded in Vol. 31 CARNER RESTORATIONS

on page 31 Paul Aschenbrenner  
REGISTER

34.10

43414110000

J-21

J 21

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

- (i) I, Milo E. Stefan  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

Affix Land Surveyor Seal



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 12 and 13, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Corner position restored at intersection of fence lines north and south and the centerline of State Highway 52. Corner marked by a railroad spike, referenced by a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Reference Monument, Southeast, 50.00 feet
2. Black Cherry, 12", N.89°E., 4.90 feet
3. Sugar, 18", S.10°W., 12.69 feet
4. Steel Sign Post, South, 0.90 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 21st day

of January... A.D., 1985

at 11:00 o'clock... A.M. and

recorded in Vol. CORNER RESTORATIONS

on page 23

Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

12/24/84  
Date


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 12, 13, 7, and 18, T.34N., R.14-15E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position found marked by an iron pipe below road surface at the intersection of State Highway #52 and town road--east. Placed a 2" x 30" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Basswood, 10", N.71°E., 86.73 feet
2. Butternut, 12", S.15°E., 140.74 feet
3. Sugar, 8", S.57°W., 113.00 feet
4. Sugar, 4", N.13°W., 159.25 feet
5. Steel Sign Post, S.12°E., 17.30 feet



REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this... 21st day  
of January... A.D., 1985  
11:00 o'clock... A.M. and  
recorded in Vol. CORNER RESTORATIONS  
on page J-25  
Paul Aschenbrenner

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



- (i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter corner common to Sections 13 and 18,  
 T.34N., R.13-14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set quarter post and made the following bearing trees:  
 Hemlock, 12", N.56°W., 24 links (15.84'); Y. Birch, 12", N.70°E., 26 links (17.16').


In 1961, N. Sperhake set iron pipe monument from remains of original Y. Birch  
 B.T. Certificate on file.

In 1988, A. Harrison found corner as per Sperhake and added new references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 1" Iron pipe with cap stamped to identify corner location.
- Sugar, 18", N.70°E., 120.60 feet (Sperhake)
- Spruce, 4", S.68°W., 6.09 feet
- Spruce, 5", N.23°W., 12.88 feet
- Steel sign post, South, 0.92 feet



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March A.D., 1990 at

10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 4-1

Paul Achenbrenner  
 Register of Deeds

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


None

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No



- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 3/9/90  
Signature Date



CERTIFICATE READY FOR FILING:

Dale B. Stargo  
District Ranger


R.O.P.

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

Quarter corner to Sections 17 and 18, T.34N., R.14E., Forest County, Wisconsin.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 3rd day  
of December, A.D., 1986 at  
1:30 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS

page L-5  
Paul Aschenbrenner  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


In 1859, James McBride set wood post at 40.00 chains and made the following BTs: Hemlock, 10", N.37°W., 29 links; Hemlock, 10", S.87°E., 11 links.

In 1985, Alan Harrison found 1" iron pipe on south side of marsh. Call from iron pipe to marsh fits original within 10 feet. No other evidence recovered. Set 2 1/2" aluminum monument and made BTs.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2 1/2" aluminum monument stamped to identify the corner location.
2. Red Oak, 14", N.70°E., 15.90 feet.
3. Red Oak, 12", S.42°W., 17.24 feet
4. Sugar, 6", N.22°W., 32.91 feet
5. Steel Sign Post, North, 0.90 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2) a found perpetuated location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 12/3/86  
Signature Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Quarter Corner to Sections 15 and 16, T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 3rd day  
of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS

page L-13  
Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Sugar, 16", N.54°E., 28 links; Hemlock, 10", N.46°W., 24 links.

In 1909, N. Smith found both original BTs still alive.

In 1936, H. Powell found Elm post in good condition (5" x 5" x 32"), also found a 30" Maple, N.10°W., 12 feet. Put tag on tree.


In 1963, J. Resvick found 1 1/4" iron pipe 18" above ground in mound of stone, scribed wood post lying next to pipe. A Maple, 22", N.12°W., 10 feet--possible BT, put Forest Service tag on it.

In 1985, Alan Harrison found corner as described by Resvick and remains of original Hemlock stump, N.46°W., 15.8 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. A 2 1/2" x 36" aluminum monument stamped to identify the corner.
2. Sugar, 4", N.22°E., 40.43 feet
3. Sugar, 4", S.32°E., 20.31 feet
4. Yellow Birch, 12", S.39°W., 15.16 feet
5. Steel Sign Post, 6', North, 0.7 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(1) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

11/14/86  
Date




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 14 and 15, T.34N., R.14E.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 3rd day  
 of December, A.D., 1986 at  
 1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 1-17

*Paul Aschabrenner*  
 Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and made the following BTs: Birch, 12", N.87°W., 24 links; Sugar, 10", N.71°E., 67 links.

In 1909, N. Smith found corner and used it to subdivide Section 15.


In 1985, Alan Harrison found old fence lines east and west of Highway 52, set corner in centerline of fences.

Position fits with Smith's survey distances of Section 15.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- Railroad spike set in surface of road to mark corner location.
- Witness Corner monument, West, 26.87 feet
- Steel Sign Post, West, 27.17 feet
- Witness Corner monument, East, 31.22 feet
- Steel Sign Post, East, 31.62 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(1) an obliterated evidence location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

Alan D. Harrison

(i) I, Alan D. Harrison (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

Date

11 | 14 | 86




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 13 and 14,  
 T.34N., R.14E., Forest County, WI.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1859 by James McBride. Set wood post and the following bearing trees; Sugar, 14", N.26°E., 48 links, Sugar, 7", S.65°W., 14 links.


In 1981, Milo Stefan, R.L.S., talked to local landowner Ed Rommel who stated that the corner is in the center-line of Range Line Road and on line with a fence line that bears West. Stefan accepted this evidence as the best available, and set a 2" x 30" aluminum monument with a tablet stamped to identify the corner. Made the following new bearing trees; Red Pine, 4", N.53°E., 42.23 feet, Red Pine, 4", S.37°E., 49.51 feet, Sugar, 6", N.47°W., 91.59 feet.

On October 6, 1993 Alan Harrison, R.L.S., found the monument and bearing trees as noted above. Removed the monument for road construction.

On August 27, 1994, Alan Harrison, R.L.S., set a railroad spike flush with a new blacktop road surface and set a 2 1/2" x 36" aluminum reference monument, East, 30.00 feet. Set a Steel Sign Post, 0.50 feet East of Reference Monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.



1. Railroad spike in blacktop.
2. Red Pine, 4", N.53°E., 42.23 feet.
3. 2 1/2" x 36" Reference Monument, East, 30.00 feet.
4. Sugar, 6", N.47°W., 91.59 feet.
5. Steel Sign Post, 0.50 feet, East of Reference Monument.

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d). above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of November, A.D., 19 94 at  
9:00 o'clock A.M. and recorded  
in Vol. Cape Restoration  
page 34-14-1-31  
Leah Chittenden Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 18 and 19, T.34N., R.14E., and Sections 13 and 24, T.34N., R.13E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored from original evidence by Neal Sperhake in 1961.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- Sugar Maple, 6" (\*8"), N.53°W. (\*N.52°W.), 30.46 (\*29.88) feet
  - White Elm, 6" (\*8"), S.44°W. (\*S.53°W.), 7.92 (\*7.73) feet
  - White Ash, 6" (\*6"), N.33°E. (\*N.30°E.), 22.44 (\*22.35) feet
  - Maple, 5" (\*5"), S.54°E. (\*S.51°E.), 7.92 (\*7.78) feet
- Above are Neal Sperhake's references of 1961 and (\*Robert Winat's references of 1982).
- Steel Sign Post, North, 1.00 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 16th day  
of... January... A.D., 1985 at  
2:30... o'clock... P.M. and

recorded in Vol. CORNER RESTORATIONS  
on page N-1

Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

9/21/84  
Date

Affix Land Surveyor Seal



## CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I Robert H. Winat, do hereby certify that on the 5 day of October, 1982, I found evidence of the set the North 1/4 corner of Section 19 Township 34 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

## Description of original monument and accessories and subsequent restorations:

James McBride, Deputy Surveyor, set post in 1859.

Witness trees (B.T's): 15" Sugar Maple S70°E, 19 lks. (12.54')  
10" Yellow Birch N30°W, 9 lks. (5.94')


## Description of corner evidence found:

An extensive and intensive search for original evidence at various possible sites did not disclose any conclusive evidence, so I proportioned against the original notes to determine this corner location.

## Description of monument and accessories I established to perpetuate the location of this corner:

Set 2" dia.x36" drive point aluminum monument with 3" dia. cap stamped:  
1/4, S18/S19, T34N, R14E, S-1040, 1982

Made and scribed bearing trees: 12" Basswood N82°W, 6.47'  
6" Basswood N5°E, 6.21'  
6" Basswood S69°E, 6.40'  
(To nail in side of tree) Metal marker post Northwest 3/4



● - Corner monument restored  
□ -

Resident witnesses.....

Dated at Eagle River Wisconsin, this 6 day of October 1982. Robert H. Winat

Signature Robert H. Winat Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-1040

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 16th day of January 1985, and was filed in Book No. Restoration Page No. N-3 of County Records.

Signature Paul Aschenbrenner Title Register of Deeds

Township 34 North, Range 14 East, Section 19, Index No. N-3, Page No.

43414180020




# CERTIFIED LAND CORNER RESTORATION

Index No. **101N 5**  
**101N 5**

State of Wisconsin }  
County of Forest } ss.

I, Jean F. Resvick, do hereby  
certify that on the 11th day  
of July, 1963, I found  
evidence of the Section  
corner of Sections 17, 18, 19 and 20  
Township 34, North, Range  
11 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:


**Surveyed in 1859 by James McBride**

80.00 ch. north between Sec. 19 and 20, set wood post from which  
Birch 5", N5°W, 27 Lks  
Birch 10", N52°E, 16 Lks  
Maple 12", S28°E, 16 Lks  
Maple 8", S65°W, 26 Lks  
1.00 ch. east to lake

Description of corner evidence found:

Iron pipe, 1½" diam. 4-ft. long alongside of point of post.  
Top of post 5-inches square lying by pipe.  
From point of post found maple stump 17" diam. S65°W, 17.16 feet.  
Piece of stump sticking up above rotted portion which was back growth of blaze with  
bearing tree readable.  
Found remains of birch stump N5°W, 10.56 feet.  
Found maple stump hole, S28°E, 10.56 feet  
Lake east, 66 feet.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Replaced point of post with 2-inch inside diam. galvanized iron pipe, 5-feet long, flanged  
at bottom, filled with concrete, with brass cap marked



from which the following new bearing trees bear:

Oak 4", S70°30'E, 5.93 feet (9 Lks)  
Maple 6", S70°W, 41.47 feet (63 Lks)  
Maple 8", N54°W, 26.67 feet (40 Lks)  
Southeast corner of block foundation of cabin bears  
N14°30'E, 60.94 ft. (92 Lks)

Dated at Rhineland, Wis., this 10th day of December, 1963

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)


Office of Register of Deeds, County of Forest I hereby certify that the within  
instrument was filed in this office for record on the 30 day of January, 1964  
at 9:00 o'clock A M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy

88137

CERTIFIED LAND CORNER RESTORATION




State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick do hereby certify that on the 24th day of May, 1965, I found evidence of the East Meander corner of Sections 16 and 21 Township T34N Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by James McBride  
45.00 chains west corrected between Sections 16 & 21.  
Set wood post from which:

- A Hemlock, 15 inches diam., bears south 10W, 19 lks. dist.
- A Hemlock, 12 inches diam., bears north 70E, 18 lks. dist.




Description of corner evidence found:


Hemlock, 24 inches diam., fallen, scribed slab readable.  
At S70W, 11.88 ft. from B.T. stump found hemlock post and point. From point of post S10W, 12.5 ft. found hemlock stump.

Description of monument and accessories I established to perpetuate the original location of this corner:

Replace hemlock post with 2 in. inside diam., galvanized iron pipe, 5 feet long, filled with concrete, flanged at bottom, 18 in. above ground with brass cap marked:



from which the following blazed and scribed new bearing trees bear:  
Yellow birch 9 in., S390E, 28.52 ft. or 43.2 lks.  
White birch 6 in., S9030'W, 16.19 ft. or 24.5 lks.  
Cedar, 10 in., N440W, 15.56 ft. or 23.6 lks.



● = Corner monument restored  
□ =

Resident witnesses

Dated at Rhinelander Wisconsin, this 14th day of June 1965.

Signature Jean F. Resvick Title Cadastral Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802

Office of County of

I hereby certify that the within instrument was filed in this office for record on the day of 19, and was filed in Book No. Page No. of County Records.

Signature Title

Township 34 North, Range 14 East, Section 21, Index No. L-10, 11, Page No.

43414160022

710-11  
N10.1-11

## DOCUMENT NUMBER


136768

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 16 and 21,  
 T.34N., R.14E.



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 13th day  
 of January A.D., 1989 at  
10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page N-11  
*Paul Heckenheuer*  
 Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set a wood post with the following B.T.s: Birch, 10", N.10E., 34 links, (22.44 feet); Birch, 8", S.43W., 19 links, (12.54 feet).


In 1913, N. Smith found corner and original B.T.s to be OK.

In 1987, Alan Harrison (R.L.S.) found no evidence of any corner. We restored corner position by proportion using N. Smith's 1913 survey from the east M.C. to the southeast section corner of Section 16 and marked position with a 2½" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2½" x 36" aluminum monument with tablet stamped to identify corner.
2. Sugar, 6", S.35E., 21.13 feet
3. Sugar, 7", S.54W., 30.08 feet
4. Basswood, 8", N.04W., 5.96 feet
5. Steel Sign Post, Northeast, 1.25 feet





- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?


Yes.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 1/11/89  
Signature Date

Certificate ready for filing:

Dale B. Staege  
District Ranger




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 15 and 22, T.34N., R.14E.



REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 3rd day  
 of December A.D., 1986 at  
1:30 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page N-15  
*Paul Achenbrenner*  
 Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and made the following BTs: Birch, 12", N.48°E., 28 links; Birch, 12", S.15°E., 20 links.


In 1908 and 1914, N. Smith found original BTs o.k. Made new references: Birch, 18", S.22½°W., 37¼ links; Sugar, 8", N.4°W., 66 links.

In 1985, Alan Harrison set corner in centerline of town road and off old fence line north. Position agrees with Smith's survey of Section 15.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- Railroad spike set in surface of road to mark corner location.
- Witness Corner Monument, North, 21.03 feet
- Sugar, 13", S.52°W., 68.72 feet
- Sugar, 12", N.29°W., 53.40 feet
- Steel Sign Post, North, 21.73 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?


No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

11/14/86



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter Corner to Sections 14 and 23, T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 17<sup>th</sup> day

of February A.D. 1988 at

10:00 o'clock A.M. and recorded

in Vol. CORNER RESTORATIONS

page N-19

Paul A. Schenck  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Elm, 12", S.34°W., 12 links; Elm, 14", N.55°E., 13 links.

In March, 1908, J. J. Melendy ran from NW corner of Section 23 east to  $\frac{1}{4}$  corner. Set an 8" x 10" x 14" stone with Hemlock witness posts, 2 rods north and south. Original BTs were stumps, marks plain and visible.

In 1934, John Faird found a post 18" above ground, 1' south of fence corner and put a location tag on fence corner. (Post found is most likely Melendy's witness, 2 rods north of corner.)


In 1985, Alan Harrison found fence lines north and south and set nail in centerline of road and tied to traverse.

In 1987, Alan Harrison found the position of the nail to fit well with the Melendy survey and replaced it with a 1" iron rod.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 1" iron rod marking corner location.
- 2 $\frac{1}{2}$ " x 36" Aluminum Monument Witness Corner, North, 29.97 feet.  
Steel Sign Post, 0.80' North of Witness Corner.
- 2 $\frac{1}{2}$ " x 36" Aluminum Monument Witness Corner, South, 34.06 feet.
- Steel Sign Post, 1.00' South of Witness Corner.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 2/11/88  
Signature Date




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Section Corner to Sections 13, 14, 23 and 24, T.34N., R.14E., Forest County, WI.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1859 by James McBride. Set wood post and the following bearing trees; Sugar, 10", N.39°E., 24 links, Hemlock, 10", S.09°E., 48 links, Sugar, 10", S.53°W., 14 links, Sugar, 12", N.19°W., 31 links.

On February 27, 1980 Milo Stefan, R.L.S., talked to local landowner Ed Rommel. He stated that the corner position is at the intersection of roads, North, South and West, and in line with a fence line East. Stefan accepted this evidence as the best available and set a 2" x 30" aluminum monument with a tablet stamped to identify the corner. Made the following new bearing trees; Sugar, 6", N.77°E., 42.24 feet, Sugar, 7", S.25°E., 56.77 feet, Sugar, 22", S.63°W., 106.03 feet, Sugar, 18", N.31°W., 99.06 feet, Steel Sign Post, East, 19.60 feet.


On October 6, 1993, Alan Harrison, R.L.S., found the monument and bearing trees as noted above. Removed monument for road construction.

On August 27, 1994, Alan Harrison, R.L.S., set a railroad spike flush with a new blacktop road surface, and set a 2 1/2" x 36" aluminum witness corner monument East, 22.00 feet. Steel Sign Post bears West, 2.30 feet from witness corner monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Railroad Spike in blacktop.
2. Sugar, 6", N.77°E., 42.24 feet.
3. 2 1/2" x 36" Witness Corner Monument, East, 22.00 feet.
4. Sugar, 7", S.25°E., 56.77 feet.
5. Sugar, 22", S.63°W., 106.03 feet.
6. Sugar, 18", N.31°W., 99.06 feet.
7. Steel Sign Post, 2.30 feet West of Witness Corner Monument.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23<sup>rd</sup> day  
of November, A.D. 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Land Restoration  
page 34-14-11-21

Paul C. H. Deputy  
Register of Deeds

Alan D. Harrison

(1) I,

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison

Signature


10/31/94

Date

CERTIFICATE READY FOR FILING:

Sue Vap

District Ranger




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 19 and 24, T.34N., R.13E., and R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Corner position restored from remains of the original bearing trees and post hole, as placed by Alfred Millard in 1857.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar Maple, 8", N.87°E., 10.50 feet
2. Sugar Maple, 6", S.48°W., 23.16 feet
3. Sugar Maple, 5", N.89°W., 13.56 feet
4. Steel Sign Post, South, 1.20 feet
5. Kimberly Clark Monument, S.67°26'42"E., 37.11 feet

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 16th day  
of January, A.D., 1985, at  
.....2:30 o'clock.....P.....M. and  
recorded in Vol. CORNER RESTORATIONS  
on page P-1  
Paul Aschenbrenner  
REGISTER





(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature


3/21/84  
Date

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter corner to Sections 19 and 20, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Corner position restored by lost methods.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. \*Black Cherry, 7", S.14°E., 41.59 feet
  2. \*Black Cherry, 7", S.66°W., 45.53 feet
  3. Sugar Maple, 5", N.52°W., 31.76 feet
  4. Steel Sign Post, West, 0.50 feet
- \*By Resvick - 1978



REGISTER'S OFFICE }  
 Forest County, Wis. }  
 Received for record this... 16th day  
 of January... A.D., 1985 at  
 ... 2:30... clock... P... M. and  
 recorded in Vol. **CORNER RESTORATIONS**  
 on page... 5  
*Paul Aschenbrenner*  
 REGISTER


43414192000

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d) above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Corner restored by single proportionate measure



Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

*Milo E. Stefan*  
Signature

3/21/84  
Date

203482

## U.S. PUBLIC LAND SURVEY MONUMENT RECORD

(As Required By WI Adm. Code)

History of original corner establishment and subsequent restorations and description of any record, monument, occupational, testimonial or other evidence considered:

1859 - J. McBride, contract surveyor, set original wooden corner post with these bearing trees: 51M 12° N75W 70 LINKS

ELM 12" N35°W 32 LINKS

HEMLOCK 10" N72°E 25 LINKS

2010 - Casey J. Swanson, RLS, Traversed around Sections 21 and 22 locating the centerline at the Center of Section 21 and locating a fence corner at the Center of Section 22. I also located a fence at the north sixteenth corner that was not used in the monumentation due to the other evidence located in the traverse. The fence corner in Section 22 fit well with the North-South quarter line of said Section and with a line between the East quarter corner and the intersection of centerlines at the West quarter corner location of said Section. The centerline at the Center of Section 21 fit well with a line between the West quarter corner of said Section 21 and the intersection of centerlines at the East quarter corner of said Section 21. The intersection of centerlines was excavated and monumented as best available evidence with ties as follows:

Corner was: (Check All That Apply)

- ☒ Restored through acceptance of an obliterated evidence location.
- ☐ Restored through acceptance of a found perpetuated location.
- ☐ Considered a lost corner and reestablished through lost corner proportionate methods (include a plan view drawing showing distances and directions to other Public Land Survey Corners used for proportioning and determining the corner location).
- ☐ Restored or reestablished in a location that differs from a previous restoration or reestablishment (include a plan view drawing and indicate what was set and/or found).





Describe the monument and accessories used to perpetuate the location of this corner (include a plan view drawing and indicate what was set and/or found).

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 11<sup>th</sup> day of June A.D., 2010 at 9:00 o'clock A.M. and recorded in Vol. Corner Restoration page P-13.

Kay Swanson, Deputy  
Register of Deeds

## ***FREEDOM CORNERS***



I, **Casey J. Swanson**

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U. S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

**Signature:**

Date \_\_\_\_\_

The EAST QUARTER corner of  
Section 21 T. 34 N., R. 14 E.

Forest County, WI

Index No.            P-13

43414212000

317


# CERTIFIED LAND CORNER RESTORATION

Index No. **P17**

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby  
certify that on the 5th day  
of June, 19 64, I found  
evidence of the East quarter  
corner of Section 22  
Township 34N, North, Range  
14E, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

Surveyed in 1859 by James McBride  
40.00 chains N1°E between Sections 22 and 23 set post for quarter corner  
Tamarack 8", N33°E, 35 lks.  
Tamarack 7", S6°W, 17 lks.

Description of corner evidence found:

Cedar post, scribed in place  
Tamarack stump, N33°E, 21.4 ft. (32.42 lks)  
Tamarack stump, S6°W, 11.0 ft. (16.67 lks)

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced cedar post with 2-inch inside diameter, galvanized iron pipe, 5 feet long,  
flanged at bottom, filled with concrete, with brass cap marked:

T34N R14E  
1/4  
S22 | S23  
1964  
S-802

from which the following blazed and scribed new bearing trees bear:

Tamarack 4", N59°E, 19.10 ft. (28.94 lks)  
Spruce 5", N50°W, 21.00 ft. (31.82 lks)  
Power pole, Number 94, S52°W, 35.20 ft. (53.33 lks)

Dated at Rhineland, Wis., this 3rd day of August, 19 64.

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21 day of Oct, 19 64  
at 11 o'clock A. M. Doc. # 89304 Vol. 1 Page P-17 CORNER RESTORATIONS

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

O = Corner monument restored.

Quarter Corner to Sections 23 and 24,  
T.34 N., R.14 E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 17<sup>th</sup> day

of February, A.D. 1988 at

10:00 o'clock A.M. and recorded

in Vol. CORNER RESTORATIONS

page P-21

Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, J. McBride set a wood post with the following BTs; Hemlock, 8", N47E, 6.60'; Tamarack, 12", S17E, 12.54'.

In 1907, J. Melendy set a cedar post, 4"x4" in a mound of rock. Original southeast BT as a Spruce, not a Tamarack. Northeast tree is gone. Made a new BT: Spruce, 7" N20W, 26.89'.


In 1910, N. Smith found Melendy's 1/4 corner when surveying section line.

In 1987, A. Harrison set a railroad spike in road surface for corner by retracement of N. Smith's survey of the section line to Sections 23 and 24.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. R.R. Spike in road surface as corner position.
2. 2 1/2" x 36" aluminum monument stamped as witness corner. East, 26.10 feet.
3. Power Pole (3414-24W5), N11E, 205.13 feet.
4. Aspen; 5" S47W, 29.79' feet.
5. Aspen, 7" N08W, 87.49 feet.
6. Steel Sign Post, 6', East, 26.94 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

2/16/88  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner common to Sections 19 and 30, T.34N., R.14E., and Sections 24 and 25, T.34N., R.13E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found fallen post and post point supported by remains of the original bearing trees from Alfred Millard's survey of 1857.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar Maple, 6", N.60°E., 9.41 feet
2. Sugar Maple, 6", S.60°E., 9.66 feet
3. Sugar Maple, 6", S.50°W., 22.27 feet
4. Sugar Maple, 8", N.80°W., 16.55 feet
5. Steel Sign Post, North, 2.80 feet
6. Kimberly Clark Monument, N.81°24'33"E., 72.80 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 16th day

of... January... A.D., 1985 at

... 2:30 o'clock... P... M. and

recorded in Vol... CORNER RESTORATIONS

on page R-1

Paul Aschenbrenner  
REGISTER

R-1

43414240000

ALSO SEE R25 734 R13

21



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

This corner is restored from the remains of the original bearing trees of Alfred Millard's survey of 1857. Neal Sperhake's monument bears N.81°24'33"E., 72.80 feet.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found-perpetuated location?

An obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date


U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS :

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
○ = Corner monument restored.

Quarter corner to Sections 19 and 30, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
  
Monument was placed by lost methods.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Basswood, 12", N.83°E., 15.64 feet
2. Basswood, 9", S.24°E., 14.15 feet
3. Sugar Maple, 5", N.84°W., 59.37 feet
4. Steel Sign Post, North, 1.90 feet




REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this 16th day  
of January, 1925 at  
2:30 o'clock P.M. and  
recorded in Vol. CORNER RESTORATIONS  
on page 3  
Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Corner restored by lost methods, single proportionate measure.



Affix Land Surveyor Seal



(1) I, Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 19, 20, 29, and 30,  
T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found monument in place, as set by Genisot Engineering in 1959, Document Number 82173.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Cedar, 14", N.15°E., 12.50 feet
2. Cedar, 12", N.20°E., 12.20 feet
3. Cedar, 12", S.56°E., 18.60 feet
4. Cedar, 10", N.62°W., 22.60 feet
5. Steel Sign Post, Southeast, 1.50 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this... 16th day

of January... A.D., 1985 at

... 2:30 o'clock... P.M. and

recorded in Vol. CORNER RESTORATIONS

on page R-5  
Paul Hechenbrenner  
REGISTER

43414190000

R-5

R5


(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

A found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name.) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Section Corner to Sections 20, 21, 28 and 29,  
 T.34N., R.14E., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 90385.44305-N  
 2287000.60519-E

Geographic Coordinates  
 45-24-27.79034-N  
 088-45-35.73492-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and bearing trees; Elm, 10", N.59°W., 18 links, (11.88 feet), Elm, 10", N.48°E., 25 links (16.50 feet), Elm, 12", S.33°E., 72 links (47.52 feet), Elm, 16", S.31°W., 37 links (24.42 feet), North 9.50 chains pond and marsh bears East and West; West 16.0 chains stream runs Southwest.


In 1978 Jean Resvick, R.L.S., at position and of T road South and fence North set 2" inside diameter galvanized pipe 3 feet long, filled with concrete with brass cap stamped T.34N., R.14E., S.20, S.21, S.29, S.28, 1978, S-802; Bearing trees and ties are as follows: U.S.G.S. Bench Mark TT31L, 1939, North, 26.95 feet, Basswood, S.31°E., 97.69 feet, North corner of boiler house of the dry kiln, S.37°W., 120.0 feet, Monument 0.5 feet below surface.

On October 14 1993, Allan Harrison R.L.S., found corner monument and ties. Set a P.K. flush with black top over monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" galvanized pipe with stamped brass cap to identify corner.
2. U.S.G.S. Bench Mark, North, 26.95 feet.
3. Basswood, 12", S.31°E., 97.69 feet.
4. N.E. Corner of boiler house foundation S.37°W., 120.0 feet.
5. Steel Sign Post, North, 21.8 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)


(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23rd day  
of November, A.D., 1994 at  
9:05 o'clock A.M. and recorded  
in Vol. Corner Restoration  
page 34 H, P. 2

Lisa Chittenden  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 21 and 28,  
 T.34N., R.14E., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 90486.31171-N  
 2289634.16758-E

Geographic Coordinates  
 45-24-28.37846-N  
 088-44-58.80540-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and made the following bearing trees; Elm, 14" N.18°W., 18 links (11.88 feet), Sugar, 12", S.70°E., 19 links, (12.54 feet).

In 1934 John Laird, a Forest Service Examiner found a wood stake which bears North 2 feet from a metal location poster on the North side of a 2" diameter Maple sapling. Corner is buried in road which bears West and North. This info is recorded on Form # 874.

In 1987 Paul Smith, R.L.S., surveyed section 28 and restored the corner using Nathan Smiths R.L.S., 1905 and 1910 records. He set an aluminum Forest County Monument and new bearing trees.


On October 5, 1993, Alan Harrison, R.L.S., found the Forest County Monument as set by Paul Smith in 1987. This position does not line up with the road center-lines West and North.

On November 18, 1993, Alan Harrison, R.L.S., and Paul Smith R.L.S., located a metal location poster inside a 16" diameter maple tree. Road center-lines bear West and North. This evidence is in agreement with the info as noted on Form #874 dated in 1934. It is agreed between Alan Harrison and Paul Smith that this is the best available evidence for restoring the corner. At a point 2 feet North of location Poster set a 2 1/2" x 36" aluminum monument and new bearing trees as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.


1. 2 1/2" x 36" Aluminum Monument with tablet stamped to identify corner.
2. Sugar, 10", N.61°E., 40.12 feet.
3. Sugar, 8", S.70°E., 16.74 feet.
4. Maple, 16", South, 2.00 feet.
5. Forest County Monument, S.00°-31'-23"W., 14.84 feet.
6. Basswood, 7", S.40°W., 26.38 feet.
7. Steel Sign Post, Northwest, 1.10 feet.





- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Drawing



- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1)

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23rd day  
of December, A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Corporation  
page 34-14, R-11

Paul Chitts Deputy  
Register of Deeds

Affix Land Surveyor Seal



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Section Corner to Sections 21, 22, 27 and 28,  
 T.34N., R.14E., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 90517.55304-N  
 2292296.97006-E

Geographic Coordinates  
 45-24-28.27131-N  
 088-44-21.48138-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and made bearing trees; Sugar, 15", N.60°W., 19 links, Sugar, 15", N.60°E., 39 links, Sugar, 15", S.22°E., 27 links, Sugar, 14", S.45°W., 25 links, East 2.40 chains (158.40 feet) leave marsh.

In 1934 John Laird a Forest Service Land Examiner, found a wood stake which bears Northeast 36 feet from an 18" Yellow Birch with a metal location poster attached. This info. is recorded on Form #874.

In 1987 Paul Smith R.L.S., surveyed Section 28 and restored the corner using N.Smith, 1905 and 1910 records. He set an aluminum Forest County Monument and made bearing trees.


On September 21 1993, Alan Harrison, R.L.S., found monument as set by P.Smith in 1987, approximately 24 feet North of an East-West fence line.

On October 5 1993, Alan Harrison, R.L.S., found a metal location poster at the base of a 24" diameter Yellow Birch as noted on Form #874 dated in 1934. From a point Northeast 36 feet from Yellow Birch the East-West fence line bears North approximately 1.5 feet. It is agreed between Alan Harrison and Paul Smith that this evidence is the best available for restoring the corner. At a point N.45°E., 36.00 feet, set a 2 1/2" x 36" aluminum monument and made new bearing trees as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)


- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2 1/2" x 36" Aluminum Monument with cap stamped to identify corner.
2. Balsam, 5", N.62°E., 23.70 feet.
3. Basswood, 10", S.10°E., 15.30 feet.
4. Maple, 8", S.75°W., 26.21 feet.
5. Yellow Birch, 24", S.45°W., 36.00 feet.
6. Steel Sign Post, South, 1.80 feet.
7. Forest County Monument, N.42°06'34"W., 32.23 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d). above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Drawing



- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1)


- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23<sup>rd</sup> day  
of November A.D., 1994 at  
2:00 o'clock A. M. and recorded  
in Vol. Casey Restoration  
page 34-N, R-13

Paul Clithero Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 10/26/94  
Signature Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Section 22 and 27,  
 T.34N., R.14E., Forest County, WI.

## State Plane Coordinates

Wisconsin North Zone


90561.43565-N

2294674.27760-E

## Geographic Coordinates

45-24-28.33061-N

088-43-48.15553-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and the following bearing trees; Hemlock, 7", N.74°W., 19 links (12.54 feet), Hemlock, 7", S.10°W., 39 links (25.74 feet), 4.50 chains East leave swamp, 12.00 chains West over lake.


In 1910 and 1911 Nathan Smith R.L.S., found the witness corner with both of the original bearing trees. Measured East 45.90 chains (3029.40 feet), to section corner. Also measured West 36.14 chains (2385.24 feet) to section corner.

On November 15, 1993, Alan Harrison, R.L.S., restored the corner by retracement of N. Smiths North Section line and utilizing the occupation within Section 27 for verification of corners location. Set a 2 1/12" x 36" Aluminum Monument and new bearing trees as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2 1/12" x 36" Aluminum Monument with tablet stamped to identify corner.
2. Sugar, 11", N.37°E., 11.00 feet.
3. Sugar, 10" S.23°W., 14.06 feet.
4. Sugar, 5", N.67°W., 16.55 feet.
5. Steel Sign Post, Southeast, 0.99 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d). above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location ?

No

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Yes

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of January A.D., 19 94 at  
9:00 o'clock A.M. and recorded  
in Vol. Land Restorations  
page 341 R-15  
Paul Chillo, Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

# CERTIFIED LAND CORNER RESTORATION


Index No. **R17**

State of Wisconsin }  
County of Forest } ss.

I Thomas R. Arnott, do hereby certify that on the 22 nd day of April, 1977, I found evidence of the section corner of sec. 22, 23, 26 & 27 Township 34 North, Range 14 E., Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Larry Lyons  
\_\_\_\_\_  
\_\_\_\_\_



○ = Corner monument restored.


History of original corner establishment:

Original survey by James McBride 10 Aug 1859 - 20 Aug 1859

Flr	8	N47W	11 Lks.
Hemlock	24	N33W	42 Lks.
Sugar	15	S75E	23 Lks.
Flr	6	S67W	25 Lks.

Description of corner evidence found:

No evidence found. Replaced corner from old survey that was made in the area.



Description of monument and accessories I established to perpetuate the original location of this corner.

Set R.R. Spike for section corner.  
Set Forest County Aluminum W.C.

Ties:

Forest Co. Alu. Mon.	S58E	33.81 feet
1 1/2" iron pipe	S70W	25.13 feet

Dated at Grandon Wis., this 25th day of April, 1977.

Signature Thomas R. Arnott Title Surveyor Registration No S-887  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 25th day of April, 1977 at 3 o'clock P. M.

Eugene Stegny Document Number **111285**  
(Register of Deeds)

By \_\_\_\_\_ Deputy

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Section Corner to Sections 22, 23, 26 and 27  
 T.34N., R14E., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 90617.15426-N  
 2297692.90593-E

Geographic Coordinates  
 45-24-28.40194-N  
 088-43-05.83943-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and bearing trees; Fir, 8", N.47°W., 11 links (7.26 feet), Hemlock, 24", N.39°W., 42 links (27.72 feet), Sugar, 15", S.75°E., 23 links, (15.18 feet), Fir, 6", S.67°W., 25 links (16.50 feet).

In 1908 J. Melindy, R.L.S., set a stone 8" x 8" x 34" marked with an "X" level with the surface in a pit of stones. Set witness posts of Cedar, 1 1/2 rods East and West. Original bearing trees are decayed stumps.

In 1909 Nathan Smith, R.L.S., found stone set by J. Melindy in 1908. Original bearing trees are blown over.


In 1977 Thomas Arnott, R.L.S., did not recover any corner evidence. He restored the corner from an old survey that was made in the area. He set a Railroad Spike for the corner and the following ties: Forest County Aluminum Monument, S.58°E., 33.81 feet, 1 1/2" iron pipe, S.70°W., 25.13 feet.

On October 13 1993, Alan Harrison, R.L.S., found Railroad Spike in center-line of State Highway 52 and witness monument S.58°E., 33.81 feet. The iron pipe S.70°W., could not be found. Made additional corner references as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Railroad Spike in Center-line of State Highway "52"
2. 2 1/2" x 36" W.C. Monument, S.58°E., 33.81 feet.
3. Power Pole # 3414 22 R 9, S.80°W., 46.25 feet.
4. 2 1/2" x 36" Reference Monument, West 45.00 feet.
5. Steel Sign Post, 0.50 feet, Southeast of W.C. Monument.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d). above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of November A.D., 19 94 at  
9:00 o'clock A.M. and recorded  
in Vol. Case Restorations  
page 34-14 P.17  
Evelyn Little Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison

Signature

10/26/94

Date

CERTIFICATE READY FOR FILING:

Sue Vap

District Ranger



# CERTIFIED LAND CORNER RESTORATION


Index No. **R19**

State of Wisconsin }  
County of Forest } ss.

I Thomas R. Arnott, do hereby  
certify that on the 20th day  
of April, 1977, I found  
evidence of the 1/4  
corner of sec. 23 & 26  
Township 34, North, Range  
14 E, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

Larry Lyons  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



○ = Corner monument restored.


History of original corner establishment:

Original survey by James McBride 10 Aug 1859 - 20 Aug 1859

Birch 8 S30W 8 Lks.  
Hemlock 24 N8W 42 Lks.

Description of corner evidence found:

Post point found 8" below ground level



Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced post point with Forest County Aluminum monument and set  
monument 1" below ground surface.

Ties:

W. Birch	14	N68E	71.60 feet
W. Birch	14	S19W	15.60 feet
W. Birch	6	N56W	22.30 feet

Dated at Crandon Wis., this 25th day of April, 1977

Signature Thomas R. Arnott Title Surveyor Registration No S-887  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 25th day of April, 1977  
at 3 o'clock PM.

Eugene Stetson Document Number **111284**  
(Register of Deeds)

By \_\_\_\_\_ Deputy

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter Corner to Sections 23 and 26, T.34N., R.14E.


REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 17<sup>th</sup> day  
of February A.D., 1988 at

10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS

page 8-19

Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Birch, 8", S.30°W., 8 links; Hemlock, 24", N.8°W., 42 links.

In 1908, J. J. Melendy reestablished corner, setting irregular shaped stone 10" x 10" x 24" in a pit of stones.


In 1977, T. Arnott found post point 8" below ground level and set a county monument and made the following BTs: White Birch, 14", N.68°E., 71.60 feet; White Birch, 14", S.19°W., 15.60 feet; White Birch, 6", N.56°W., 22.30 feet.

In 1987, Alan Harrison found that the corner position fell in the north wheel track of a woods road and the monument was gone. He replaced the monument from T. Arnott's bearing trees.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2½" x 36" aluminum monument stamped to identify the corner, 0.5 feet below ground level.
2. White Birch, 15", N.71°E., 70.53 feet
3. White Birch, 14", S.22°W., 15.61 feet
4. White Birch, 7", N.57°W., 22.35 feet
5. Steel Sign Post, North, 8.84 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

2/11/88  
Date



# CERTIFIED LAND CORNER RESTORATION

Index No.


R21

State of Wisconsin }  
County of Forest } ss.

I Thomas Arnott, do hereby  
certify that on the 11 day  
of May, 1976, I found  
evidence of the section  
corner of sections 23, 24, 25, & 26  
Township 34, North, Range  
14 E, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



○ = Corner monument restored.

History of original corner establishment:

Original subdivision by James McBride 10 Aug. - 20 Aug., 1859

Tamarack	8	N47W	19 Lks.
Tamarack	6	N15E	107 Lks.
tamarack	10	S5W	214 Lks.
Tamarack	10	S88W	37 Lks.

Description of corner evidence found:


Wood Post Found

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced wood post with Forest County Aluminum Monument

Ties:

Tamarack	8	N6W	7.43 feet
Spruce	8	N73E	25.84 feet
Tamarack	8	S18E	6.25 feet



Dated at Crandon, Wis., this 11th day of May, 1976.

Signature Thomas R. Arnott Title Surveyor Registration No. S-887  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 11th day of May, 1976.  
at 3 o'clock P. M.

Eugene Staszny Document No. **109217**  
(Register of Deeds)

By \_\_\_\_\_ Deputy

FORM 985 R. C. MILLER CO., MILWAUKEE

43414230000

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.


Section Corner to Sections 23, 24, 25, and 26,  
T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 17<sup>th</sup> day  
of February, A.D., 1988 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page R-21  
Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
In 1859, James McBride set post with the following BTs: Tamarack, 8", N.47°W., 19 links; Tamarack, 6", N.15°E., 107 links; Tamarack, 15", S.5°E., 214 links; Tamarack, 10", S.88°W., 37 links.  
In 1934, J. White found stake in poor condition and replaced it with a new one. Placed a metal location poster on a 14" White Pine about 2 chains west of corner.  
In 1936, A. J. Vronch found Cedar post in poor condition and a location poster on a 24" White Pine, 1.75 chains west of corner.  
In 1975, Jean Resvick and Milo Stefan found a post point with post lying down. Found a Tamarack stump at S.5°E., 211 links, a possible Tamarack stump at N.47°W., 19 links, and a Tamarack stump, North, 110 links.  
In 1976, Milo Stefan found a Forest County monument in place of post found in 1975.  
In 1987, Alan Harrison made new accessories to the corner.
- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.
- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Forest County Monument
2. Spruce, 5", N.73°E., 25.94 feet
3. Spruce, 4", S.51°E., 6.92 feet
4. Tamarack, 7", S.28°W., 31.96 feet
5. Tamarack, 5", N.10°W., 7.54 feet
6. Steel Sign Post, 6', West, 0.74 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

2/11/88  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 24 and 25,  
T.34 N., R.14 E.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 17<sup>th</sup> day  
of February A.D., 1988 at  
10:00 o'clock AM and recorded  
in Vol. CORNER RESTORATIONS  
page R-23  
Paul Schenck  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.  
In 1859, J. McBride set wood post with the following BTs: Birch, 12" S.11 E., 23.11"; Sugar, 15", N 7 E, 30.36'

In 1907, N. Smith found original corner and BTs okay.


In 1907, J. Melendy found Ironwood post and both original BTs okay.

In 1987, A. Harrison searched area and found no evidence of corner position. Restored corner by retracement of N. Smith's and J. Melendy's surveys of Section 25 done in 1907.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. A 2" x 36" aluminum monument stamped to identify the corner.
2. Sugar, 6", N64E, 29.94 feet
3. Sugar, 12", South, 51.21 feet
4. Sugar, 10", N75W, 54.93 feet
5. Steel sign post, South, 0.65 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None


- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

Date


2/16/88



State of Wisconsin }  
County of Forest } ss.

I Robert E. Bandow, do hereby  
certify that on the 3rd day  
of July, 1959, I found  
evidence of the Quarter Corner--center of  
Section 30  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

# CERTIFIED LAND CORNER RESTORATION

83255

Index No.

241

History of original corner establishment:

Original corner established by John Hammes, County Surveyor, Forest County,  
in the course of subdivision of the section. Record of survey and notes  
were not recorded.

Post marking position of corner was well scribed and remains of bearing  
tree shows definite evidence of scribing. It appears as though corner  
was set at least 35 years ago.

Description of corner evidence found:

4"x4" post at corner and remains of bearing tree.



Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 2"x5' Galvanized Iron Pipe filled with concrete, capped with bronze cap and  
stamped as follows:

T34N R14E  
0 1/2 S30  
1959

RLS No. S-104

Blazed and scribed the following bearing trees: Balsam 6" N66°30'W 17.7 feet  
Tamarack 6" N33°30'W 16.0 feet  
Spruce 6" N55°E 18.2 feet

Genisot Engineering Company

Dated at Rhinelander, Wis., this 30th day of November, 1959

Signature Robert E. Bandow Title Registered Land Surveyor Registration No. S-104  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21st day of March, 1960  
at 9:00 o'clock A. M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy


Subscribed and sworn to before me this 30th day of  
November, 1959. Joseph E. Ruby Notary Public,  
Chelda County, Wis.  
My Commission expires May, 1960

43414362020

State of Wisconsin }  
County of Forest } ss.

I Robert E. Bandow, do hereby  
certify that on the 3rd day  
of July, 1959, I found  
evidence of the East 1/16th Corner on E-W  
Quarter line of Section 30  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner:

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:


Position for corner was established by the United States Forest Service after running between the East Quarter Corner as re-established by Genisot Engineering Company, Rhinelander, Wisconsin, and the center of the Section as previously established by John Hammes, County Surveyor, Forest County. 4"x4" wood post marks position of corner.

Corner was set on a straight line midway between the East Quarter Corner and the center of the section.

Field notes of survey are located in the U.S. Forest Service Supervisor's office.

Description of corner evidence found:

4"x4" wood post set by United States Forest Service.



Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 2"x5" Galvanized Iron Pipe filled with concrete, capped with a concrete cap and stamped as follows:

T34N R14E  
E 1/16  
c ————— c  
S30  
1959

RLS No. S-104

Blazed and scribed the following bearing trees: White Birch 7" S36°30'E 4.4 feet  
Elm 3" N75°30'E 15.4 feet

Genisot Engineering Company

Dated at Rhinelanders, Wis., this 30th day of November, 1959

Signature Robert E. Bandow Title Registered Land Surveyor Registration No. S-104  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 21st day of March, 19 60 at 9:00 o'clock A M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy

Subscribed and sworn to before me this 30th day of November 1959. Joseph E. Kirby Notary Public, Oneida Co.


Wisconsin.  
My Commission expires May 1, 1960  
43414302010

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter corner to Sections 29 and 30, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Found monument in place, as set by Genisot Engineering in 1959.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Birch, 5", S.55°E., 46.45 feet
2. Black Cherry, 7", S.68°W., 67.00 feet
3. Witness Corner (2" Iron Pipe/Brass Cap), South, 32.81 feet
4. Steel Sign Post, West, 56.10 feet

REGISTER'S OFFICE }  
 Forest County, Wis. }  
 Received for record this... 16<sup>th</sup> day  
 of... January... A.D., 1985 at  
 ... 2:30 o'clock... P... M. and  
 recorded in Vol. CORNER RESTORATIONS 2  
 on page T-5  
*Paul Heckenbranner*  
 REGISTER



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

A found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Quarter corner to Sections 28 and 29, T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at  
10:00 o'clock A M. and recorded  
in Vol. CORNER RESTORATIONS  
page T-9

Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Sugar, 10", S.84°E., 33 links; Birch, 15", S.77°W., 14 links.


In 1914 and 1922, N. Smith found original BTs standing. He set new post and the following new BTs in 1922: Sugar, 8", N.70°E., 42.24 feet; Sugar, 8", N.85°W., 38.94 feet.

April 3, 1985, Al Harrison found fence line running west from town road. He found Sugar stump and pulled S.85°E., 38.94 feet and set P-K nail, pulled N.71°E., 42 feet and fell in a depression. Accepted as corner.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Railroad spike, 3 feet East of center of McArthur Road.
2. Hemlock, 12", N.74°E., 50.09 feet
3. Sugar, 8", S.41°E., 88.10 feet
4. Sugar, 6", S.47°W., 60.78 feet
5. 2" x 36" aluminum monument, West on line, 50.00 feet
6. Steel Sign Post, East of monument, 2.34 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.



- (i) I, Al Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 27 and 28,  
 T.34N., R.14E., Forest County, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 90561.43565-N  
 2294674.27760-E

Geographic Coordinates  
 45-24-28.33061-N  
 088-43-48.15553-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and made bearing trees: tamarack, 8", N.74°E., 87 links (57.42 feet), Tamarack, 6", N.58°W., 44 links (29.04 feet), South, 6.00 chains, enter swamp, South, 5.50 chains stream 12 links wide, North, 8.00 chains leave swamp.

In 1910 Nathan Smith R.L.S., measured 40.55 2/3 chains from the Northwest Section Corner of Section 27.


In 1987 Paul Smith R.L.S., surveyed Section 28 and restored the corner using records of Nathan Smith R.L.S., 1900 and 1908 surveys. He set a Forest County Aluminum Monument and made new bearing trees.

On October 12 1993, Alan Harrison, R.L.S., found the Forest County Monument as set by P. Smith in 1987. Also found a dead 8" Tamarack, scribed, N.30°W., 4.50 feet from Monument. Pulled S.58°E., 29.04 feet from this bearing tree and could not recover any post evidence. On October 19, 1993, A. Harrison talked to E. Huettl (adjoining property owner). He questions P. Smith's East-West Quarter line. On November 29 1994, A. Harrison tied to fence corner 1/4 mile South. The position of the fence corner would support the Tamarack bearing tree as being an original. It is agreed between A. Harrison and P. Smith that this bearing tree is original evidence for restoring the corner position. At a point S.58°E., 29.04 feet, set a 2 1/2" x 60" aluminum monument and made new bearing trees as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)


- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2 1/2" x 60" aluminum monument with tablet stamped to identify corner.
2. Spruce, 6", N.79°E., 22.79 feet.
3. Tamarack, 7", S.23°E., 21.78 feet.
4. Spruce, 8", N.24°E., 50.79 feet.
5. Steel Sign Post, North, 1.45 feet.
6. Forest County Monument, N.57°-27'-43"W., 24.70 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Drawing




- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1)

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23<sup>rd</sup> day  
of March, A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Case Histories  
page 34-14 T-13  
*Paul C. Deady*  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

*Sue Vap*  
District Ranger



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 26 and 27,  
 T.34N. R.14E., Forest County, Wisconsin

State Plane Coordinates  
 Wisconsin North Zone  
 87929.74763-N  
 2297649.63316-E

Geographic Coordinates  
 45-24-01.88040-N  
 088-43-07.05351-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and the following bearing trees; Tamarack, 10", N.70°E., 12 links(7.92 feet), Tamarack, 10", N.67°W., 24 links(15.84 feet), South 2.00 chains, stream 6 links wide.

In 1908 J. Melindy (RLS) re-established the corner position and set a 5"x5" cedar post and the following bearing trees; Tamarack, 10", N.37°W., 7.59 feet, Tamarack, 6", N.63½°E., 11.44 feet

In 1909 Nathan Smith (RLS) found Melindy's post from 1908.

In 1922, Nathan Smith (RLS) set a new corner post. Did not recover previous post.

In 1923, Nathan Smith (RLS) measured 40.59 chains from the Section Corner to the North. Then measured 20.30 chains to the South 1/8th corner.


On 12-1-93, Alan Harrison (RLS) restored the corner position at proportionate distance (which is mid-point) and on line between opposing Section Corners. Set 2 Witness Corner Monuments as noted below.

No other corner evidence was recovered.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. True corner position not monumented.
2. 2½" x 36" Aluminum Monument for Witness Corner, S.00°-55'-20"W., 658.81 ft.
3. Spruce, 12", S.30°E., 52.92 ft.
4. Aspen, 7", S.46°W., 37.04 feet
5. Steel Sign Post, North, 0.97 ft.
6. 2½" x 60" Aluminum Monument for Witness Corner, N.00°-55'-20"E., 212.58 ft.
7. Spruce, 6", N.29°E., 78.36 ft.
8. Aspen, 6", N.65°W., 69.14 ft.
9. Steel Sign Post, South, 1.26 ft.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

No


(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Yes



REGISTER'S OFFICE }  
Forest County, Wis. }  
Received for record this 23rd day  
of March, A.D., 1994 at  
2:00 o'clock A.M. and recorded  
in Vol. Land Restoration  
page 34-14, 7-17

Paul C. H. Dwyer  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison

Signature

10/26/94

Date

CERTIFICATE READY FOR FILING:

Sue Vap

District Ranger


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 25 and 26, T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 10th day  
of October A.D., 1985 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page T-21  
Paul Aschenbrenner  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and the following BTs: Hemlock, 20", S.88°E., 6 links; Hemlock, 12", N.12°W., 12 links.

In 1914, N. Smith set new BT: Hemlock, 24", S.36°50'W., 131 1/3 links.


In 1976, T. Arnott found 1 1/2" well point in road at extension of road centerlines from north, east, and west. Set a Forest County monument and following references: Road Sign Post, N.4°E., 33.04 feet; Elm, 10", N.20°W., 62.24 feet.

In 1985, Al Harrison found monument set by Arnott was destroyed by road construction. From Elm BT, set new monument 6" below road surface and references.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify the corner location.
2. Fence corner, South, 22.09 feet
3. Elm, 10", S.84°W., 136.93 feet
4. Elm (Arnott's BT), 10", N.20°W., 62.24 feet
5. Steel Sign Post, North, 17.84 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Al Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



# CERTIFIED LAND CORNER RESTORATION


Index No. \_\_\_\_\_

**T21**

State of Wisconsin }  
County of Forest } ss.

I Thomas Arnott, do hereby  
certify that on the 14th day  
of April, 1976, I found  
evidence of the 1/4  
corner of sections 25 & 26  
Township 34, North, Range  
14 E, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

Original subdivision by James McBride 10 Aug - 20 Aug., 1859

Hemlock	20	S88E	6 Lks.
Hemlock	12	N12W	12 Lks.

Description of corner evidence found:

Found 1 1/2" well point



Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced well point with new Forest County Aluminum Monument  
4" below ground surface

Ties:

Road sign post	10	N4E	33.04 feet
Elm		N20W	62.24 feet

Dated at Crandon, Wis., this 13th day of May, 1976.

Signature Thomas R. Arnott Title Surveyor Registration No. S-887  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 14th day of May, 1976  
at 3 o'clock P. M.

Eugene Stutzman Document No. **109219**  
(Register of Deeds)

By \_\_\_\_\_ Deputy


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner Common to Sections 25 and 26,  
 T.34N., R.14E., Forest County, Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and the following B.T.'s: Hemlock, 20", S.88°E., 6 links; Hemlock, 12", N.12°W., 12 links.

In 1914, N. Smith set new B.T: Hemlock, 24", S.36°50'W., 131 1/3 links.

In 1976, T. Arnott found 1½" well point in road at extension of road centerlines from north, east, and west. Set a Forest County monument and following references: Road Sign Post, N.4°E., 33.04 feet; Elm, 10", N.20°W., 62.24 feet.

In 1985, Alan D. Harrison (RLS) found monument set by Arnott was destroyed by road construction. From Elm B.T., set new monument 6" below road surface and references.

In 1994, Alan D. Harrison (RLS) found the monument as described above. Found the following bearing tree evidence; Elm stump, N.20°W., 62.24 feet, fence corner, South, 22.09 feet, dead and down, Elm, S.84°W., 136.93 feet. Set a reference monument, 2½" x 36" aluminum monument, North, 20.00 feet. Tablet stamped; T.34N., R.14E., R.M., ¼, S26, S25, 1994, R.L.S. 1651, S-00-E, 20.00 feet. Moved Steel Sign Post to a position 1.0 feet North of reference monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" Aluminum monument with tablet stamped to identify corner.
2. 2½" x 36" Reference Monument North, 20.00 feet.
3. Fence Corner, South, 22.09 feet.
4. Steel Sign Post, North, 1.0 feet from Reference Monument.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) a found perpetuated location.

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 15<sup>th</sup> day  
of September, A.D., 1994 at  
1:00 o'clock PM and recorded  
in Vol. Cover Perpetuations  
page 7-21  
*Shelley D. Dwyer*  
Register of Deeds



(1) I, Alan D. Harrison  
(type or print name) certify that the corner location shown  
on this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record is  
correct and complete to the best of my knowledge and belief.

*Alan D. Harrison* 8/17/94  
Signature Date

CERTIFICATE READY FOR FILING:

*She Vap*  
District Ranger

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## I N S T R U C T I O N S :

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner common to Sections 30 and 31, T.34N., R.14E., and Sections 25 and 36, T.34N., R.13E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found post point hole, from which stump holes remain of the original bearing trees from Alfred Millard's survey of 1857.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar Maple, 8", N.83°E., 44.67 feet
2. Sugar Maple, 4", S.41°E., 33.65 feet
3. Sugar Maple, 4", S.01°W., 12.40 feet
4. White Ash, 8", N.24°W., 10.70 feet
5. Steel Sign Post, South, 1.10 feet
6. Kimberly Clark Monument, N.74°E., 31.84 feet



REGISTER'S OFFICE }  
Forest County, Wis.

Received for record this 16th day

of January A.D., 1985

at 2:30 o'clock P.M. and

recorded in Vol. CORNER RESTORATIONS

on page 11  
Paul Hochbrenner  
REGISTER



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

This corner is restored from the remains of Millard's original survey of 1857. Neal Sperhake's monument bears north  $74^{\circ}$  east, 31.84 feet, which was restored by lost method from one mile south and two miles north.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

An obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



- (i) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

State of Wisconsin

County of FOREST

ss. RESTORATION OF LOST ORIGINAL GOVERNMENT SURVEY CORNER.

I NEAL SPERHAKE, do hereby certify that on the TWENTIETH day of OCTOBER, 19 64, I established the NORTHWEST SECTION CORNER OF SECTION 31, TOWNSHIP 34 NORTH, RANGE 14 EAST, Fourth Principal Meridian, as described hereon.

**History:** This corner was established during the original survey of this township, as noted in the original field notes for the original survey of T34N-R14E, 4th. p.m.

**Description of monument and accessories I established to perpetuate the location of this corner:**


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N 25, 36, 30, 31 T13-14E SPERHAKE RLS 463 10/20/64."

The pipe is witnessed by:

Maple 4 N 50°W 68 links. (SCRIBED S25 NBT).  
Elm 9 N 73°E 47½ links. (SCRIBED S30 NBT).  
Cherry 8 S 34°W 28 links. (SCRIBED S36 NBT).  
Ash 7 S 55°E 43 links. (SCRIBED S31 NBT).


**Description as to how corner was located:** No evidence of the original corner present, thus, set by proportionate measurement. Since both the township corners of T34N-R13E, T34N-R14E, T33N-R13E, and T33N-R14E and the section corner common to 24, 25, 19, 30, have been previously established with a distance between them of 160.50 chains, I set the section corner of 25, 36, 30, 31 80.25 chains from either previously established corner and on a straight line between them.



O = Corner monument restored

89628

REGISTRARS OFFICE  
FOREST COUNTY, WIS.



M. Lo o'clock A in  
Anna Peterson Register of Deeds

Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 12th day of January, 19 65.

Signature \_\_\_\_\_

Title Registered Land Surveyor Registration No. 463

~~Office of~~ Forest County of ~~ex~~ Wisconsin,  
I hereby certify that the within instrument was ~~filed on the~~  
~~office records~~ on the 12th day of January  
19 65, and was ~~filed on Book No.~~ signed and ~~page no.~~ sworn to  
on ~~County Records~~ before me.

Signature Anna Peterson Title Notary Public

Surveyor's Seal

Index No. V 1

4341325 0000


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 30 and 31, T.34N., R.14E.




- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Monument was placed by lost methods.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Spruce, 3", N.12°E., 4.97 feet
2. White Spruce, 4", S.67°E., 19.36 feet
3. White Spruce, 4", S.79°W., 3.60 feet
4. Steel Sign Post, Southwest, 3.70 feet



REGISTER'S OFFICE }  
Forest County, Wis. }

Received for record this 16<sup>th</sup> day  
of January A.D., 1985 at

... 2:30 o'clock P.M. and

recorded in Vol. CORNER RESTORATIONS


on page 1-3  
Paul Aschenbrenner  
REGISTER

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Corner restored by lost methods, single proportionate measure.



Affix Land Surveyor Seal



(1) I, Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).


- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section Corner to Sections 29, 30, 31 and 32,  
T.34N., R.14E., Forest County, Wisconsin.

State Plane Coordinates  
Wisconsin North Zone  
84903.60886-N  
2281679.15705-E

Geographic Coordinates  
45-23-34.48975-N  
088-46-51.49039-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and bearing trees; Birch, 15", N.36°N., 21 links (13.86 feet); Birch, 7", N.70°E., 35 links (23.1 feet), Sugar Maple, 10", S.37°E., 47 links (31.02 feet), Birch, 24", S.21°W., 25 links (16.5 feet).

In 1910 Smith found wood post and bearing trees in good condition.

In 1959 Joseph Abernathy found point of wood post and bearing tree stumps; Birch, 15", N.36°W., 21 links (13.86 feet), Sugar Maple, 10", S.37°E., 47 links (31.02 feet): Replaced wood post point with a 2" x 5' galvanized pipe with bronze cap and new bearing trees; Maple, 18", N.69°W., 17.2 feet, chisel cross 1.8' x 1.4' stone, N.7°E., 11.1 feet, chisel cross, 3.8' x 4.0' stone, S.30°E., 23.22 feet.


In 1982 Winat found brass cap set by Abernathy and made a new bearing tree, Maple, 5", S.81°E., 31.36 feet, Steel Sign Post, South, 4.5 feet.

On 1993 Alan Harrison (RLS) found monument in place and bearing trees and chisel cross in stone. Cut down, Maple, 20", N.69°W., 17.25 for G.P.S. observation. Steel Sign Post was found at South, 3.5 feet. Set new bearing trees; Maple, 6", N.66°E., 29.20 feet, Maple, 7", S.67°W., 52.34 feet, Aspen, 10", N.45°W., 41.80 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 5' galvanized pipe with stamped brass cap.
2. Maple, 8", S.81°E., 31.36 feet.
3. Chisel stone, 1.8' x 1.4', N.7°E., 11.1 feet.
4. Chisel stone, 3.8' x 4.0', S.30°E., 23.22 feet.
5. Maple, 6", N.66°E., 29.20 feet.
6. Maple, 7", S.67°W., 52.34 feet.
7. Aspen, 10", N.45°W., 41.80 feet.
8. Steel Sign Post, South, 3.5 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 13<sup>th</sup> day  
of November, A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Case Restoration  
page 34-14-V-5  
Paul Chittlo, Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name), certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section Corner to Sections 16, 15, 22, and 21,  
T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 3rd day  
of December A.D., 1986 at  
1:30 o'clock P. M. and recorded  
in Vol. CORNER RESTORATIONS  
page N-13

Fred Aschenhener  
Register of Deeds.

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set a wood post with the following BTs: Sugar, 15", N.2°W., 56 links; Sugar, 12", N.57°E., 20 links; Sugar, 10", S.47°E., 26 links; Birch, 24", S.15°W., 27 links.


In 1909, N. Smith used this corner but did not make any new BTs.

In 1985, Alan Harrison searched area, but due to roads and cultivation no evidence was found. He then used the intersection of roads east, west, and south and fence line to north. Position fits N. Smith's survey east and north. Marked position with a 2" x 36" aluminum monument with cap stamped for corner.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument with cap stamped to identify corner.
2. Chiseled "X" on a 2' x 4' x 3' rock, N.07°E., 54.20 feet
3. Power Pole, #3414-15L7, N.53°E., 27.65 feet
4. 2" x 36" aluminum reference monument, S.39°W., 37.77 feet
5. Basswood, 6", N.42°W., 47.56 feet
6. Steel Sign Post, North, 24.18 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown  
on this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record is  
correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

11/14/86  
Date






# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS :** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 29, 30, 31, and 32, T.34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Found monument in place, as set by Genisot Engineering in 1959.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.


- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar Maple, 26", N.69°W., 17.29 feet
2. Sugar Maple, 5", S.81°W., 31.36 feet
3. Cross on Boulder (1.8' x 1.4'), N.7°E., 11.12 feet
4. Cross on Boulder (3.8' x 4.0'), S.30°E., 23.22 feet
5. Steel Sign Post, South, 4.50 feet

REGISTER'S OFFICE }  
Forest County, Wis.

Received for record this 16th day  
of January A.D., 1985 at  
... 2:30 o'clock... P... M. and  
recorded in Vol. CORNER RESTORATIONS  
on page 15

Paul Aschenbrenner  
REGISTER



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

A found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Affix Land Surveyor Seal



(i) I, Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

3/21/84  
Date

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 29 and 32, T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
Page V-7  
Paul A. Schenck  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BT: Lind, 16", S.45°E., 16 links.


In 1914 and 1922, N. Smith found original BT still standing.

May 2, 1985, Al Harrison found no evidence of corner position. Corner was restored by retracement of Smith's 1914 survey, using Smith's southwest and west one-sixteenth corners.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify the corner.
2. Sugar, 14", N.13°E., 27.76 feet
3. Sugar, 10", S.24°E., 46.43 feet
4. White Ash, 10", N.28°W., 32.21 feet
5. Steel Sign Post, North, 13.35 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Al Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Section corner to Sections 28, 29, 32, and 33,  
T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at  
10:00 o'clock A. M. and recorded  
in Vol. CORNER RESTORATIONS  
page V-9

Paul Aschendrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Birch, 18", N.24°W., 55 links; Hemlock, 10", N.12°E., 36 links; Hemlock, 16", S.60°E., 47 links; Hemlock, 8", S.54°W., 34 links.


1914 and 1922, N. Smith found BTs in good shape. He marked a new BT: Hemlock, 20", S.73°E., 29.70 feet.

April 3, 1985, Al Harrison found iron pipe in center of McArthur Road. From pipe, at S.60°E., 31.02 feet, remains of large Hemlock stump. All other BTs fall in cut of road. Distances north, south, and west fit with Smith's survey.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. An iron pipe in the roadbed.
2. Sugar, 6", N.66°E., 38.11 feet
3. Sugar, 4", S.86°E., 39.57 feet
4. Power Pole #3414-32E3, S.63°W., 23.59 feet
5. Reference corner, 2" x 36" aluminum monument, West, 33.0 feet.
6. Iron pipe, 1½" diameter, East, 32.95 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Al Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).


- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section Corner to Sections 28 and 33,  
T.34N., R.14E., Forest County, Wisconsin.

State Plane Coordinates  
Wisconsin North zone  
85116.08206-N  
2289576.62837-E

Geographic Coordinates  
45-23-35.37546-N  
088-45-00.79608-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and bearing trees; Hemlock, 16", N.71°W., 5 links (3.30 feet), Hemlock, 8", S.23°E., 25 links (16.50 feet).

In 1922 N. Smith found  $\frac{1}{2}$  corner post and original bearing trees in good condition.

In 1936 A.J. Vaonch (CCC) found  $\frac{1}{2}$  post in good condition and bearing tree stump; Hemlock, 14", S.54°W., 7 links (4.62 feet).


In 1987 Paul Smith (RLS) found old post hole with 1" iron pipe at fence corner: Set a Forest County Monument with bearing trees; Maple, 10", S.88°E., 22.61 feet, Maple, 14", S.37°E., 21.52 feet, Maple, 20", N.70°W., 24.14 feet.

On 1993 Alan Harrison found Smith's monument and bearing trees: adding a Steel Sign Post, Southwest, 1.70 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Forest County Monument
2. Maple, 9", S.76°E., 22.80 feet.
3. Maple, 12", S.44°E., 22.29 feet.
4. Maple, 17", N.74°W., 24.80 feet.
5. Steel Sign Post, Southwest, 1.70 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.


- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of November, A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Capa Restorations  
page 34-14-11-11  
Seal Chittie Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Section Corner to Sections 27, 28, 33, 34, T34N R14E  
 Forest County, Wisconsin.

State Plane Coordinates  
 Wisconsin North Zone  
 85164.65016-N  
 2292260.01157-E

Geographic Coordinates  
 45-23-35.43632-N  
 088-44-23.18968-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859 James McBride set a wood post and bearing trees; Birch, 12", N.12°W., 37 links, (24.42 feet), Hemlock, 10", S.30°E., 62 links (40.92 feet), Hemlock, 20", N.39°E., 16 links (10.56 feet), Sugar, 14", S.44°W., 16 links (10.56 feet).

In 1922 N. Smith use double proportioning to restore corner.


In 1959 Robert Bandow found a buried axel shaft in road intersection: set Reference Corner; 2" x 5' galvanized pipe, North, 24 feet of corner in road; bearing tree; Box Alder, 8", N.38°30'W., 32.6 feet.

On 1993 Alan Harrison (RLS), found the following: Box Elder stump, N.35°W., 32.6 feet, bottom blazed, 2" axle shaft 1" below gravel, Box Elder, 20", N.51°W., 43.13 feet (B.T. tag on ground), witness corner monument, N.4°E., 24.06 feet, Steel Sign Post, 0.5 feet North of witness corner. Set a new reference; Power Pole #3414-28R5, N.10°W., 22.34 feet, 2½" x 36" stamped Aluminum Monument, S.47°W., 40.50 feet; Steel Sign Post, Southwest, 1.32 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" Axel Shaft.
2. Box Elder, 20", N.51°W., 43.13 feet.
3. Witness Corner Monument, N.4°E., 24.06 feet.
4. Steel Sign Post, North of witness corner, 0.50 feet.
5. Power Pole #3414-28R5, N.10°W., 22.34 feet.
6. 2½" x 36" Aluminum stamped Reference Monument, S.47°W., 40.50 feet.
7. Steel Sign Post, Southwest of witness corner, 1.32 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 25<sup>th</sup> day  
of March A.D., 1994 at  
9:00 o'clock A.M. and recorded  
in Vol. Casey Restorations  
page 34-14-V-13

Paul Chitt Deputy  
Register of Deeds

(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison

Signature


10/26/94

Date

CERTIFICATE READY FOR FILING:

Sue Vap

District Ranger




FORM 985 H. C. MILLER CO., MILWAUKEE

State of Wisconsin }  
County of Forest } ss.

I, Robert E. Bandow, do hereby  
certify that on the 3rd day  
of July, 19 59, I found  
evidence of the North-West  
corner of Section 34  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

CERTIFIED LAND CORNER RESTORATION

83261

Index No. 30V13  
V13


History of original corner establishment:

Original corner established in 1859 by James McBride, Government  
Deputy Surveyor.

Original bearing trees: Birch 12" N12°W 37 lks.  
Hemlock 10" S30°E 62 lks.  
Hemlock 20" N39°E 16 lks.  
Sugar 14" S44°W 16 lks.

Description of corner evidence found:

2" axle shaft buried in road (12").  
Corner is on the intersection of the center-  
lines extended of State Highway No. 52,  
and the road to the west of the corner.  
The centerline of the bituminous surfacing  
of State Highway 52 (on the curve) lies  
approximately 66 feet S45°E of the corner.  
Corner is accepted locally as being in it's  
proper position.



Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 2"x5' galvanized iron pipe capped with brass cap, (filled with concrete) as  
reference corner, 24 feet north of corner in road and stamped as follows to  
identify corner:

WC  
T34N R14E  
S28/S27 24's  
S33/S34  
1959

RLS No. S-104

Blazed and scribed the following bearing tree: Box Elder 8" N38°30'W 32.6 feet.

Genisot Engineering Co.

Dated at Rhineland, Wis., this 3rd day of December, 19 59

Signature Robert E. Bandow Title Registered Land Surveyor Registration No. S-104  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21st day of March, 19 60  
at 9:00 o'clock A. M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy

Subscribed and sworn to before me this 30th day of  
December 1959. Joseph C. Kelly Notary Public,  
Oneida County, Wis.  
My Commission expires May 1, 1960  
43414280000

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 27 & 34,  
 T.34N., R14E., Forest County, Wisconsin.

State Plane Coordinates  
 Wisconsin North Zone  
 85208.73538-N  
 2294935.15589-E

Geographic Coordinates  
 45-23-35.45074-N  
 088-43-45.69969-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1859 by James McBride. Set wood post and the following bearing trees; Birch, 12", S.67°E., 12 links, Sugar, 15", N.11°E., 20 links.


In 1976, Thomas Arnott (RLS), found a 1" diameter iron pipe bent over. He replaced it with a new 1" diameter iron pipe and made the following corner references; Forest County Aluminum Monument, S.01°E., 25.39 feet, guy pole, N.16°E., 51.78 feet, guy pole, S.75°W., 51.76 feet, Power Pole #3414-27L9, N.49°W., 71.93 feet.

On 10-13-93, Alan Harrison (RLS), found 1" diameter iron pipe at intersection of Hwy 52 and Rangeline Road, from which Forest County witness corner monument bears S.01°E., 25.40 feet. Power Pole and guy pole references are gone. Made the following new corner references; Power Pole #3414-27R3, N.50°E., 39.50', Power Pole #3414-34E1, S.48°E., 41.20 feet. Set a Steel Sign Post, 0.60 feet, South of witness monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 1" diameter iron pipe.
2. 2½" x 36" Forest County Aluminum W.C. Monument with tablet stamped to identify corner, South, 25.54 ft.
3. Power Pole #3414-27R3, N.50°E., 39.50 feet.
4. Power Pole #3414-34E1, S.48°E., 41.20 feet.
5. Steel Sign Post, 0.60 feet South of witness corner monument.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 23rd day  
of November, A.D., 1994 at  
9:00 o'clock A. M. and recorded  
in Vol. Casey, Restoration  
page 34-14-15

Paul Chitts, Deputy  
Register of Deeds


(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 10/26/94  
Signature Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger




# CERTIFIED LAND CORNER RESTORATION

Index No. **V15**

State of Wisconsin }  
County of Forest } ss.

I Thomas Arnott, do hereby  
certify that on the 14th day  
of April, 1976, I found  
evidence of the 1/4  
corner of sections 27 & 34  
Township 34, North, Range  
14 E, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

Original subdivision by James McBride 10 Aug - 20 Aug 1859

Birch	12	S67E	12 Lks
Sugar	15	N11E	20 Lks.

Description of corner evidence found:

**1" iron pipe found bent over**



Description of monument and accessories I established to perpetuate the original location of this corner.

**Replaced 1" iron pipe with new 1" iron pipe**

**Ties:**

Forest Co. Aluminum Monument	S1E	25.39 feet
guy pole	N16E	51.78 feet
guy pole	S75W	51.76 feet
Power Pole (3414-27L9)	N49W	71.93 feet

Dated at Crandon, Wis., this 13th day of May, 1976

Signature Thomas R. Arnott Title Surveyor Registration No. S-887  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 14th day of May, 1976  
at 3 o'clock P M.

Eugene Staszny Document No. **109221**  
(Register of Deeds)

By \_\_\_\_\_ Deputy

139370


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD.

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Corner common to Sections 26-27-34-35,  
 T.34N., R.14E., Forest County,  
 Wisconsin.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and made the following B.T.'s: Birch, 36", N.33°W., 13 links (8.58 feet); Hemlock, 12", N.48°E., 41 links (27.06 feet); Hemlock, 7", S.05°E., 24 links (15.84 feet); Sugar, 7", S.42°W., 15 links (9.90 feet).

In 1907, J. Melendy found original B.T.'s. He set a 4" x 4" Hemlock post and added the following B.T.'s: Maple, 10", N.74 1/2°W., 12.95 feet; Maple, 12", S.47 1/4°W., 27.80 feet.


In 1909, N. Smith found post set by Melendy. Original bearing trees okay. He added the following new B.T.: Hemlock, 16", N.80°-50'E., 34.76 feet.

In 1987, Al Harrison set traverse station in E of Town Road, off E of road north and old fence 24.80 feet south. Original corner and B.T.'s would fall in road right-of-way. Distance east and south to one quarter corner fits Melendy's 1907 distance within 0.10 feet. Accepted E of roads and fence line south as best evidence of corner location.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Railroad spike in E of surfaced road marking corner location.
2. 2 1/2" x 36" aluminum monument, witness corner, South, 23.16 feet.
3. Sugar, 4", S.06°E., 37.84 feet.
4. Sugar, 14", N.66°W., 94.75 feet.
5. Sugar, 4", N.13°W., 86.89 feet.
6. Steel Sign Post, 6 feet, South, 23.86 feet.



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 29<sup>th</sup> day  
 of March A.D., 1990 at  
10:00 o'clock A.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page V-17

Register of Deeds

V-17

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Alan D. Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 3/12/90  
Signature Date



CERTIFICATE READY FOR FILING:

Dale S. Stage  
District Ranger



# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 26 and 35, T.34N., R.14E.


REGISTER'S OFFICE {  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at

10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS

Page V-19

Paul Aschendrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Birch, 12", S.19°W., 33 links; Lind, 12", N.30°W., 24 links.

In 1907, J. J. Melindy found Hemlock post 3" x 3" set by Smith from original BTs.


In 1961, R. Kolbe found iron pipe.

In 1985, Al Harrison found 2" iron pipe and old blazed lines north and east.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify the corner.
2. Yellow Birch, 12", S.63°E., 11.20 feet
3. White Ash, 12", S.87°W., 9.86 feet
4. Sugar, 6", N.16°W., 31.29 feet
5. Steel Sign Post, West, 1.47 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Al Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Section corner to Sections 25, 26, 35, and 36,  
T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October, A.D., 1985 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page V-21

Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Sugar, 12", N.38°W., 28 links; Birch, 15", N.28°E., 67 links; Sugar, 10", S.64°E., 50 links; Sugar, 12", S.61°W., 42 links.

In 1906, N. Smith found corner and original BTs.


In 1907, J. J. Melindy found corner and original BTs and made new references as follows: "X" on boulder, 3' x 5', N.30°E., 38 3/4 links; "X" on boulder, 4' x 6', S.32 3/4°E., 37 links.

April 25, 1985, Milo Stefan found window weight in rock pile and Melindy's two "Xs" on boulders and stump hole of original southwest BT.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

- 2" x 36" aluminum monument stamped to identify the corner.
- Melindy's rock with "X", 3' x 5', N.30°E., 25.31 feet
- Melindy's rock with "X", 4' x 6', S.32°E., 24.61 feet
- Sugar, 14", S.78°W., 23.98 feet
- White Ash, 13", N.43°W., 19.83 feet
- Steel Sign Post, West, 1.20 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (gah) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (1) I, Milo Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

9/16/85  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:**

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Quarter corner to Sections 25 and 36, T.34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page V-23

Paul Achenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1857, James McBride set wood post with the following BTs: Sugar, 10", S.25°E., 27 links; Sugar, 12", N.26°E., 37 links.

In 1907, N. A. Smith found both BTs and set two new BTs as follows: Sugar, 10", S.74°E., 6 3/4 links; Sugar, 20", S.13°E., 45 links.


In 1909, J. J. Melindy found original and Smith's BTs. He made two new BTs: Elm, 10", N.10°E., 17.3 links; Sugar, 12", S.21°W., 40 links.

April 25, 1985, Milo Stefan found original BT stump, N.26°E., 37 links; stump hole, S.25°E., 27 links; stump hole, S.20°E., 45 links; Sugar stump, S.21°W., 40 links; Elm stump, N.10°E., 17 links.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify the corner.
2. Sugar, 5", N.60°E., 21.97 feet
3. Sugar, 6", S.4°E., 27.69 feet
4. Sugar, 7", N.54°W., 27.83 feet
5. Steel Sign Post, Southwest, 1.62 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (1) I, Milo Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

Date




# CERTIFIED LAND CORNER RESTORATION

Index No. **V25**

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby  
certify that on the 5th day  
of June, 19 64, I found  
evidence of the Northeast section  
corner of Section 36  
Township 34, North, Range  
11 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

80.00 chains N1°E between Sections 31 and 36, set post for section corner  
section 25, 30, 31 & 36  
Ironwood 10", S85°W, 44 lks.  
Elm 9", N67°W, 27 lks  
Yellow Birch 18", N85°E, 19 lks  
Sugar 9", S2°E, 24 lks.


Description of corner evidence found:

Elm 13", fallen snag with face blazes.  
From a point S67°E, 17.82 ft. from elm  
1. Yellow Birch stump, N85°E, 12.54 ft.  
2. Stump hole, S2°E, 15.8 ft.  
3. Scribed post S85°W, 6 ft., post set on uphill side of boulder and held  
by two large stones.

I accept the bearing tree evidence as the location of the corner and I believe that  
the post had been found down and placed behind boulder.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 2-inch inside diameter galvanized iron pipe, 5 feet long, filled with concrete,  
flanged at bottom, with brass cap stamped:



from which the following blazed and scribed new bearing trees bear:

Maple 13", N14°30'W, 14.05 ft. (21.29 lks)  
Maple 8", N74°E, 23.92 ft. (36.24 lks)  
Ironwood 8", S52°E, 46.05 ft. (69.77 lks)  
Maple 16", S9°W, 34.85 ft. (52.80 lks)

Dated at Rhineland, Wis., this 3rd day of August, 19 64.

Signature Jean F. Resvick Title Cadastral Surveyor Registration No. S-802  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of FOREST, I hereby certify that the within  
instrument was filed in this office for record on the 21st day of Oct., 19 64  
at 11 o'clock A. M. Doc. # 89307 Vol 1 Page V-25 CORNER RESTORATIONS

Anna Peterson 89307  
(Register of Deeds)

By \_\_\_\_\_ Deputy

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD



### INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 36 and 31, T.34N.,  
R.13-14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


June, 1857, Alfred Millard set wood post and made the following BTs: Yellow Birch, 22", N.52°W., 15 links; Elm, 18", S.18°E., 40 links.

March, 1983, Milo Stefan found no evidence of corner. Corner position restored by proportional measure. Placed a railroad spike in surface of State Highway "52" to mark corner position.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) 1-a
- Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Witness Corner, 2" x 36" aluminum monument,  
N.00°34.8'E., 51.88 feet.
  - a. Sugar, 10", N.25°E., 28.45 feet
  - b. Sugar, 5", S.88°E., 8.30 feet
  - c. Sugar, 7", N.70°W., 24.69 feet
  - d. Steel Sign Post, North, 1.20 feet
2. Witness Corner, 2" x 36" aluminum monument,  
S.00°34.8'W., 41.92 feet.
  - e. Sugar, 6", S.65°E., 44.35 feet
  - f. Sugar, 8", S.04°E., 55.68 feet
  - g. Sugar, 9", N.89°W., 15.02 feet
  - h. Steel Sign Post, North, 2.20 feet
3. Railroad spike in surface of road.





- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Yes.

- (i) Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

2/19/55  
Date



## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter Corner to Sections 31 and 32,  
 T.34N. R.14E., Forest County, Wisconsin

State Plane Coordinates  
 Wisconsin North Zone  
 82266.13768-N  
 2281715.46113-E

Geographic Coordinates  
 45-23-08.44845-N  
 088-46-51.54893-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Original survey in 1859 by James McBride. Set wood post and the following bearing trees; Birch, 15", N.87°W., 11 links, Birch, 10", N.65°E., 32 links.

On 11-9-93, Alan Harrison, RLS, searched for corner evidence. No evidence was recovered. Restored the corner position on line between opposing Section Corners and in the Center-Line of State Hwy 52. Set a railroad spike flush with the surface of Hwy 52 to mark the corner position. Made new bearing trees as noted below.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Railroad Spike in Center-Line of Hwy 52
2. Sugar, 9", S.23°E., 52.16 feet
3. 2½" x 36" Aluminum Monument for W.C. South, 33.58 feet
4. White Ash, 9", S.27°W., 54.40 feet
5. Sugar, 8", N.06°W, 58.70 feet
6. Steel Sign Post, 0.80 ft. South of W.C. monument.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.


None

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


No

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

Yes.



REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of November A.D., 19 94 at  
9:00 o'clock A.M. and recorded  
in Vol. Canu Restoration  
page 34 N. X-5  
*Leah Clith, Deputy*  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

*Alan D. Harrison*

Signature

10/26/94

Date

CERTIFICATE READY FOR FILING:

*Sue Vap*

District Ranger

Document Number

215240

REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 11<sup>th</sup> day  
of September A.D., 2014 at  
10:15 o'clock A. M. and recorded  
in Vol. Corner Restoration  
Page X-5

Erika S. Deaton, Deputy  
Register of Deeds

RS-7150-11 (9/1/66)

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I Randy R. Erickson, do hereby certify that on the 08 day of Sept., 192014  
I found evidence of the West Quarter corner of Section 32  
Township 34 North, Range 14 East, Fourth Principal Meridian, as described  
hereon; and that from this evidence I established a new monument and accessories as described hereon to per-  
petuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

1859 James McBride set a wood post and marked Bearing Trees:  
Birch 15" N 87° W 11 lks Birch 10" N 65° 32 lks

1993 Al Harrison, RLS #1651 restored corner on line in center of road. set  
a Rail Road Spike in road for corner. Set a 2½" x 36" aluminum monument  
33.58 feet South as a Reference monument. Marked Bearing Trees:

Sugar 9" S 23° E 52.16 feet White Ash 9" S 27° W 54.40 feet  
Sugar 8" N 06° W 58.70 feet Steel Sign post 0.8 ft south of Refernce  
Monument.

Description of corner evidence found:

Recovered Rail Road Spike and accessories in place. Refernce monument and  
Bearing Trees South of Highway 52 need to be removed for trail construction.

Bearing Tree north of Highway 52 is still good.

Reference monument south of highway was damaged by brusher.



Description of monument and accessories I established to perpetuate the location of this corner:

set a 1" x 36" aluminum drive monument North 50.00 feet as a Witness Corner.

Marked an Oak Bearing Tree; 6" N 12° E 64.95 feet, Set a Steel Sign  
post 1.40 feet North of Witness Corner monument.

Wisconsin North Zone State Plane Coordinates for Corner:

N 82266.138 E 2281715.461 NAD 83 1991 U.S. Foot



● - Corner monument restored

□ -

Resident witnesses.....

Dated at Park Falls Wisconsin, this 11 day of Sept  
19 2014

Signature [Signature] Title Professional L.S.  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. 1897

Office of \_\_\_\_\_ County of \_\_\_\_\_

I hereby certify that the within instrument was filed in this office for record  
on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_, and was filed in Book  
No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Signature \_\_\_\_\_ Title \_\_\_\_\_

Township 34 N, Range 14 E, Section 32, Index No. \_\_\_\_\_, Page No. 67

43414310020

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.


○ = Corner monument restored.

Quarter corner to Sections 32 and 33, T.34N., R.14E.

REGISTER'S OFFICE }  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at  
10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page X-9

Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post with the following BTs: Hemlock, 7", S.48°W., 10 links; Hemlock, 6", N.32°E., 8 links.


In 1922, N. Smith set new post. Original BT standing and dead. Made new BT--Hemlock, 16", S.75°10'W., 32 links.

In 1985, Al Harrison, from retracement of Smith's 1922 survey, found post point and Hemlock stump at S.75°W., 21.1 feet and conifer stump remains at N.32°E., 5.3 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 60" aluminum monument stamped to identify corner location.
2. Black Ash, 6", N.38°E., 29.30 feet
3. Black Spruce, 5", S.24°W., 38.13 feet
4. Red Maple, 10", N.17°W., 34.01 feet
5. Steel Sign Post, NW, 0.93 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) I, Al Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



## CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I, Jean F. Resvick, do hereby certify that on the 1st day of June, 19 76,  
I found evidence of the West Quarter corner of Section 34  
Township 34 North, Range 14 East, Fourth Principal Meridian, as described  
hereon; and that from this evidence I established a new monument and accessories as described hereon to per-  
petuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by James McBride  
Monumented in 1959 by Robert Badow, Certificate number 83262  
Recorded March 21, 1960.

2 in. diameter galvanized iron pipe filled with concrete with  
brass cap stamped to identify corner.  
White Birch 8, N79E, 43.5 feet  
Balsam 8, S35E, 30.0 feet


Description of corner evidence found:

Road construction south has buried this corner.  
Found monument lying along side of road, monument  
had recently been pulled out of road, bent and twisted.  
Bearing trees scribed by Badow in place.

Description of monument and accessories I established to perpetuate the location of this corner:

Locate position for corner from bearing trees and set 2 inch  
diameter aluminum monument 3 feet long, with cast aluminum base,  
and aluminum cap, 14 inches below the surface of road. Aluminum  
cap stamped:

T34N, R14E, 1/4, S33, S34, 1976, S-802  
White Birch 14, N81E, 43.50 feet  
Balsam 14, S35E, 30.00 feet  
These are the same bearing trees scribed by Badow in 1959.



● - Corner monument restored  
□ -

Resident witnesses.....

Dated at Rhineland Wisconsin, this 15 day of June  
19 76.

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802DOCUMENT NUMBER  
**109576**Office of REGISTER OF DEEDS County of FOREST

I hereby certify that the within instrument was filed in this office for record  
on the 2nd day of July, 19 76, and was filed in Book  
No. .... Page No. .... of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 34 North, Range 14 East, Section 34, Index No. X-13, Page No. ....


43414330020

X 13

State of Wisconsin }  
County of Forest } ss.

I, Robert E. Badow, do hereby  
certify that on the 3rd day  
of July, 19 59, I found  
evidence of the West Quarter  
corner of Section 34  
Township 34, North, Range  
14 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:



○ = Corner monument restored.

# CERTIFIED LAND CORNER RESTORATION

83262

Index No.

31X13  
X13

History of original corner establishment:

Original corner established in 1859 by James McBride, Government Deputy  
Surveyor. Original Bearing Trees:

Birch 12N57°E 14 links.  
Hemlock 10N74°W 33 Links.

Description of corner evidence found:

Iron rail on east side of road bearing south.  
Corner lies approximately 10 feet East of the centerline of U. S.  
Forest Service Road 2126, and is at the intersection of the center-  
lines extended from the North and from the West of State Highway  
No. 52. It also lies S45°E approximately 90 feet from the center-  
line of the bituminous surfacing on the curve of State Highway  
No. 52. Corner is accepted locally as being in it's proper  
position.

Description of monument and accessories I established to perpetuate the original location of this corner.  
Set 2"x5' galvanized iron pipe filled with concrete, capped with brass cap and  
stamped as follows to identify corner:

T34N R14E

S33 S34  
1959

RLS No. S-104

Blazed and scribed the following bearing trees: White Birch 8° N79°E 43.5 feet.  
Balsam 8° S35°E 30.0 feet.


Dated at Genisot Engineering Co., Wis., this 3rd day of December, 19 59  
Rhineland

Signature Robert E. Badow Title Registered Land Surveyor Registration No. S-104  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 21st day of March, 19 60  
at 9:00 o'clock A. M.

Anna Peterson  
(Register of Deeds)

By \_\_\_\_\_ Deputy



Subscribed and sworn to before me this 30th day of  
December 1959. Joseph C. Bailey Notary Public,  
Oneida County, Wis.  
My Commission expires May 1960

43414330020




## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 34 and 35,  
 R.34N., R.14E., Forest County, WI.



State Plane Coordinates  
 Wisconsin North Zone  
 82576.67596-N  
 2297626.05504-E

Geographic Coordinates  
 45-23-09.04195-N  
 088-43-08.59370-W

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1859 by James McBride. Set wood post and the following bearing trees; Sugar, 12", N.77°W., 23 links, Birch 15", S.56°E., 12 links.

In 1907, J.J. Melindy set a new Elm post and made the following new bearing trees; Maple, 10", S.30 1/4° E., 29 1/3 links, Maple, 8", S.36 1/2°W., 33 5/8 links.


In 1985, Alan Harrison, R.L.S., found an iron pipe in a rock pile with the top of an Elm post on ground. Found the following bearing tree remains; Large Turnout, N.77°W., 15.2 feet, Sugar Stump, 16", S.30°E., 19.4 feet, Stump hole, S.36°W., 22.1 feet. In place of iron pipe, set a 2 1/2" x 36" aluminum monument with a tablet stamped to identify corner. Blazed and scribed new bearing trees; Sugar, 7", N.26°E., 32.13 feet, Sugar, 10", S.36°E., 22.86 feet, Hemlock, 12", S.57°W., 20.58 feet, Steel sign post, North, 1.85 feet.

On October 28 1993, Alan Harrison, R.L.S., found the monument and bearing trees as set in 1985. Cut down the Hemlock bearing tree for G.P.S. Observations. Blazed and scribed a new bearing tree; Sugar, 8", N.52°W., 35.64 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2 1/2" x 36" aluminum monument with tablet stamped to identify corner.
2. Sugar, 7", N.26°E., 32.13 feet.
3. Sugar, 10", S.36°E., 22.86 feet.
4. Sugar, 8", N.52°W., 35.64 feet.
5. Steel sign post, North, 1.85 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found-perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23<sup>rd</sup> day  
of March, A.D., 1994 at  
2:00 o'clock A.M. and recorded  
in Vol. Cape Restoration  
page 34-14-K17  
Sue Vap Deputy  
Register of Deeds



(1) I, Alan D. Harrison  
(type or print name) certify that the corner location shown  
on this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record is  
correct and complete to the best of my knowledge and belief.

Alan D. Harrison 10/26/94  
Signature Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD


## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 34 and 35, T.34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 21st day  
of October A.D., 1985 at

10:00 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS

page X-17

Paul Aschenbrenner  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In 1859, James McBride set wood post and the following BTs: Sugar, 12", N.77°W., 23 links; Birch, 15", S.56°E., 12 links.


In 1907, J. J. Melindy set new Elm post (original Birch decayed, Maple o.k.) and made the following new BTs: Maple, 10", S.30½°E., 29 1/3 links; Maple, 8", S.36½°W., 33 5/8 links.

In 1985, Al Harrison found iron pipe in rock pile with top of Elm post on ground and following BT remains: Large turnout, N.77°W., 15.2 feet; Sugar stump, 16", S.30°E., 19.4 feet; Stump hole, S.36°W., 22.1 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument stamped to identify corner location
2. Sugar, 7", N.26°E., 32.13 feet
3. Sugar, 10", S.36°E., 22.86 feet
4. Hemlock, 12", S.57°W., 20.58 feet
5. Steel Sign Post, North, 1.85 feet



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.


- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (i) Al Harrison  
(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

9/16/85  
Date



Stock No. 26273

Document Number 127001

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 15th day  
of April, A.D., 1983 at  
3:00 o'clock P.M. and recorded  
in Vol. 34-14 CORNER RESTORATION  
page 34-14 Aschenbrenner  
Register of Deeds





SHEET 1 OF 4


# CERTIFIED LAND CORNER RESTORATION and ESTABLISHMENT

BEING THE CORNERS ON THE SOUTH AND WEST SECTION LINES  
OF SECTION 31 AND THE SOUTH SECTION LINE OF SECTION 32 ALL IN  
TOWNSHIP 34 NORTH, RANGE 14 EAST, FOURTH PRINCIPAL MERIDIAN,  
FOREST COUNTY, WISCONSIN



## LEGEND

-  4" LANGLADE COUNTY MONUMENT
-  2" ALUMINUM MONUMENT, 36" LONG
-  RAILROAD SPIKE IN SURFACE OF STATE HIGHWAY "52"
-  MARKED PROPERTY BOUNDARY OF U.S. GOVERNMENT LANDS



CONVERSION FACTOR  
FEET TO METERS - 0.304801  
METERS TO FEET - 3.28083

4341432000

Stock No. 26273

Sheet 2 of 4

SURVEY NOTES

This survey was made by the U. S. Department of Agriculture, Forest Service, for the purpose of restoring and establishing corners on the perimeter of Sections 31 and 32 and for locating and marking the boundaries of U. S. Government land on the perimeter of Sections 31 and 32, Township 34 North, Range 14 East, Fourth Principal Meridian, Forest and Langlade Counties, Wisconsin.

The original Government survey of this township was made in 1857 - 1859. Subsequent survey by Neal Spearhake in 1964.

The corner positions recovered, restored, and established by this survey are marked by the monument described in the map legend.

The corner positions established were located to an accuracy of one part in 3000.

The bearings between corner positions are true bearings as determined by solar observations.

The field notes of this survey and a copy of this plat are on file in the Forest Supervisor's Office at Rhinelander, Wisconsin.

CORNERS RECOVERED AND RESTORED1. Township Corner to T.33-34N., R.13-14E.

Corner position found marked by a 4" Langlade County monument, from which the remains of the original BTs were recovered.

Corner References:

White Spruce	14"	N.39°E.	123.26	feet
White Spruce	8"	N.87°E.	76.80	feet
Power Pole #3313-1E1		S.33°W.	63.41	feet
Red Maple	6"	N.83°W.	70.98	feet

2. Section Corner to Sections 30, 31, 25, and 36, T.34N., R.13-14E.

Corner position restored from the remains of the original bearing trees and post hole.

Corner References:

Sugar	8"	N.83°E.	44.67	feet
Sugar	4"	S.41°E.	33.65	feet
Sugar	4"	S.01°W.	12.40	feet
White Ash	8"	N.24°W.	10.70	feet
Steel Sign Post		South	1.10	feet
Kimberly Clark Monument		N.74°E.	31.84	feet

3. Section Corner to Sections 31, 32, 5, and 6, T.33-34N., R.14E.

Corner position restored from remains of the original bearing trees.

Corner References:

Balsam	8"	N.36°E.	30.60	feet
Aspen	6"	S.70°E.	27.30	feet
Balsam	3"	S.13°W.	6.70	feet
Balsam	7"	N.30°W.	15.26	feet
Steel Sign Post		West	1.87	feet
Kimberly Clark Monument		S.37°E.	5.80	feet

4. Section Corner to Sections 32, 33, 4, and 5, T.33-34N., R.14E.

Corner certificate on file.

Stock No. 26273

Sheet 3 of 4

5. Quarter Corner to Sections 36 and 31, T.34N., R.13-14E.

Corner position restored by proportional measure between the section corner, 1 mile north, and township corner, 1 mile south. Corner falls in surface of State Highway "52" and is witnessed by 2" x 36" aluminum monuments as follows:

Corner References:

<u>Witness Corner</u>		N.00°34.8'E.	51.88 feet
Sugar	10"	N.25°E.	28.45 feet
Sugar	5"	S.88°E.	8.30 feet
Sugar	7"	N.70°W.	24.69 feet
Steel Sign Post		North	1.20 feet
<u>Witness Corner</u>		S.00°34.8'W.	41.92 feet
Sugar	6"	S.65°E.	44.35 feet
Sugar	8"	S.04°E.	55.68 feet
Sugar	9"	N.89°W.	15.02 feet
Steel Sign Post		North	2.20 feet

6. Quarter Corner to Sections 31 and 6, T.33-34N., R.14E.

Corner position restored from the remains of the original bearing trees.

Corner References:

Sugar	10"	N.37°E.	48.39 feet
Basswood	6"	S.6°E.	13.84 feet
Sugar	7"	N.18°W.	35.18 feet
Steel Sign Post		East	2.30 feet

7. Quarter Corner to Sections 32 and 5, T.33-34N., R.14E.

Corner position found marked by a mound of stone with a post point in center and remains of original Hemlock stump at proper bearing and distance.

Corner References:

White Pine	8"	N.10°W.	80.08 feet
White Pine	6"	N.65°E.	45.98 feet
White Birch	7"	S.20°E.	37.51 feet
Steel Sign Post		West	1.80 feet

CORNERS ESTABLISHED1. East Sixteenth Corner to Sections 32 and 5, T.33-34N., R.14E.

Corner established midpoint and on line between the south quarter corner and southeast corner of Section 32.

Corner References:

White Pine	14"	N.72°E.	34.16 feet
Sugar	6"	S.50°W.	25.37 feet
Basswood	6"	N.58°W.	44.39 feet
Steel Sign Post		West	1.80 feet
White Pine Line Tree		West	86.34 feet

Stock No. 26273

Sheet 4 of 4

SURVEYOR'S AFFIDAVIT

State of Wisconsin  
Counties of Forest and Langlade ] SS

I, Milo E. Stefan, Cadastral Surveyor, U. S. Forest Service and a registered surveyor in the State of Wisconsin, hereby certify that I have surveyed the exterior lines of Sections 31 and 32, Township 34 North, Range 14 East, Fourth Principal Meridian, State of Wisconsin, as depicted on the plat map on Sheet 1.

The plat map and the notes herewith are a correct representation of the land surveyed. I have surveyed said sections in accordance with the rules for survey of the public lands and with the statutes of the State of Wisconsin.



Cadastral Surveyor, U. S. Forest Service  
R.L.S., State of Wisconsin  
Certificate S-1558

Plat Ready For Filing:

  
District Ranger

Date of Survey: 1983




# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a. through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Township corner to T.33-34N., R.13-14E.

REGISTER'S OFFICE  
 Forest County, Wis.  
 Received for record this 15th day  
 of April A.D., 1985 at  
3:10 o'clock P.M. and recorded  
 in Vol. CORNER RESTORATIONS  
 page 218  
Paul Aschenbrauner  
 Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


June, 1857, Alfred Millard set post for township corner and made the following BTs: Yellow Birch, 12", N.70°W., 11 links; White Pine, 14", S.62°W., 15 links; Yellow Birch, 10", S.71°E., 23 links; Yellow Birch, 11", N.28°E., 53 links.

1983, Milo Stefan found corner position marked by a 4" Langlade County monument, from which the remains of the original bearing trees were recovered.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Spruce, 14", N.39°E., 123.26 feet
2. White Spruce, 8", N.87°E., 76.80 feet
3. Power Pole #3313-1E1, S.33°W., 63.41 feet
4. Red Maple, 6", N.83°W., 70.98 feet
5. Langlade County Monument
6. Steel Sign Post, East, 2.05'



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


(2) a found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) 1. Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

2/19/85  
Date




U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-l).

(a) CORNER LOCATION  
1/4 Cor. of Secs. 6 & 31  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,181.19 USft  
E: 713,177.87 USft  
WISCRS - Forest County  
N: 500,534.89 USft  
E: 864,380.59 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS RTN



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT


Original Surveyor: Alfred Millard  
Original Accessories:  
Date of Survey Commenced: August, 1857  
Completed: August, 1857  
Sugar 10" N48°W, 23 lks.  
Hemlock 14" S60°E, 16 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Milo E. Stefan, RLS dated February 19, 1985 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 6, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap projecting 8" above the ground surface. I set a DEEP-1 magnet adjacent to the monument. I found or established accessories as shown below. A USFS steel sign post bears East, 2.2 ft. I set a white vinyl sign post bearing Southwest, 1.1 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD  
  
APR 27 2018  
  
Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-3

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

  
Signature  
MAY 4, 2017  
Date



# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 31 and 6, T.33-34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 15th day  
of April A.D., 1985 at  
3:10 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS  
page 2-3  
Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


June, 1857, Alfred Millard set wood post and made the following BTs: Hemlock, 14", S.60°E., 16 links; Sugar, 10", N.48°W., 23 links.

April, 1984, Milo Stefan restored corner position from the remains of the original bearing trees.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar, 10", N.37°E., 48.39 feet
2. Basswood, 6", S.6°E., 13.84 feet
3. Sugar, 7", N.18°W., 35.18 feet
4. Steel Sign Post, East, 2.30 feet
5. Squared Wood Post, East, 10.00 feet
6. 2" x 36" aluminum monument stamped to identify the corner.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Squared wood post of unknown origin appears to be at proportional position between township corner and Kimberly Clark corner to Sections 31, 32, 5, and 6, which was erroneously positioned.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.


- (g) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

- (1) I, Milo E. Stefan  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

01/19/85  
Date



U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-i).

(a) CORNER LOCATION  
Cor. of Secs. 5, 6, 31 & 32  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,220.16 USft  
E: 715,847.42 USft  
WISCRS - Forest County  
N: 500,560.62 USft  
E: 867,050.30 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS RTN

	SEC.	6	
	T33N	R14E	

(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857

Hemlock 28" S55°E, 40 lks.  
Y. Birch 14" S45°W, 48 lks.  
Hemlock 16" N43°W, 38 lks.  
Hemlock 14" N60°E, 58 lks.


(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Milo E. Stefan, RLS dated February 19, 1985 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*


*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated October 26, 1994 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 6, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap projecting 14" above the ground surface. I set a DEEP-1 magnet adjacent to the monument. All record bearing trees are gone or standing dead. I established accessories as shown below. A USFS steel sign post bears West, 1.8 ft. I set a white vinyl sign post bearing West, 0.8 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD  
  
APR 27 2018  
  
Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-5



(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

May 4, 2017  
Date


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Section corner to Sections 5, 6, 31, and 32, T.33-34N., R.14E.



REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 15th day  
of April A.D., 1985 at  
3:10 o'clock A.M. and recorded  
in Vol. CORNER RESTORATIONS  
page 2-5  
Paul Aschenbrenner  
Register of Deeds

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

In June, 1857, Alfred Millard set wood post and made the following BTs: Hemlock, 28", S.55°E., 40 links; Yellow Birch, 14", S.45°W., 48 links; Hemlock, 16", N.43°W., 38 links; Hemlock, 14", N.60°E., 58 links.


1962, Neal Spearhake set aluminum monument (Kimberly Clark) off scribed bearing tree-- see "e" on reverse side.

In April, 1984, Milo Stefan restored corner position from the remains of the original bearing tree stumps.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Balsam, 8", N.36°E., 30.60 feet
2. Aspen, 6", S.70°E., 27.38 feet
3. Balsam, 3", S.13°W., 6.70 feet
4. Balsam, 7", N.30°W., 15.26 feet
5. Steel Sign Post, West, 1.87 feet
6. Kimberly Clark monument, S.37°E., 5.80 feet
7. 2" x 36" aluminum monument stamped to identify the corner.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Kimberly Clark monument was set from resurvey bearing tree, origin unknown, which resulted in Kimberly Clark corner position being S.37°E., 5.8 feet from original corner position.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1) an obliterated evidence location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) Milo E. Stefan

(Type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

8/19/85  
Date





## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Section Corner to Sections 5, 6, 31, and 32,  
 T.33-34N., R.14E., Forest and Langlade  
 Counties, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 79585.37562-N  
 2281752.35877-E

Geographic Coordinates  
 45-22-41.97973-N  
 088-46-51.60845-W

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1857 by Alfred Millard. Set wood post and the following bearing trees; Hemlock, 28", S.55°E., 40 links, Yellow Birch, 14", S.45°W., 48 links, Hemlock, 16", N.43°W., 38 links, Hemlock, 14", N.60°E., 58 links.

In 1962 Neal Spearhake set an aluminum monument (Kimberly Clark) off a scribed bearing tree. See "e" on reverse side.

In 1983, Milo Stefan, R.L.S., restored the corner from the remains of 3 original bearing tree stumps. Set a 2" x 36" aluminum monument with a tablet stamped to identify corner. Blazed and scribed new bearing trees; Balsam, 8", N.36°E., 30.60 feet, Aspen, 6", S.70°E., 27.38 feet, Balsam, 3", S.13°W., 6.70 feet, Balsam, 7", N.30°W., 15.26 feet, Steel sign post, West, 1.87 feet. Kimberly-Clark monument, S.37°E., 5.80 feet.


On March 26 1991, Alan Harrison, R.L.S., found monument and bearing trees as set in 1983. Northwest bearing tree is dead. Made 1 new bearing tree; Balsam, 8", S.55°W., 26.50 feet.

On November 1 1993, Alan Harrison, R.L.S., found monument and bearing trees as set in 1983 and 1991. Cut down all but the Northeast bearing tree. Blazed and scribed 3 new bearing trees; Aspen, 7", S.69°E., 42.19 feet, Aspen, 8", S.17°W., 32.60 feet, Balsam, 9", N.83°W., 63.79 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument with tablet stamped to identify corner.
2. Balsam, 8", N.36°E., 30.60 feet.
3. Aspen, 7", S.69°E., 42.19 feet.
4. Kimberly-Clark Monument, S.37°E., 5.80 feet.
5. Aspen, 8", S.17°W., 32.60 feet.
6. Balsam, 9", N.83°W., 63.79 feet.
7. Steel sign post, West, 1.87 feet.



- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

Kimberly-Clark monument was set from a resurvey bearing tree, origin unknown, which resulted in Kimberly-Clark monument being S.37°E., 5.80 feet from original corner position.


- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(1)

- (g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23<sup>rd</sup> day  
of March A.D. 1994 at  
9:00 o'clock A. M. and recorded  
in Vol. Open Restorations  
page 34-14-2-5  
Paul Chillo, Deputy  
Register of Deeds



(1) I, Alan D. Harrison

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison 10/26/94  
Signature Date

CERTIFICATE READY FOR FILING:

Sue Vap  
District Ranger

# CERTIFIED LAND CORNER RESTORATION

88934

Index No. **Z 5 207**


State of Wisconsin } ss.  
County of FOREST

I NEAL SPERHAKE, do hereby  
certify that on the FIRST day  
of NOVEMBER, 1962, I found  
evidence of the SOUTHEAST SECTION  
corner of SECTION 31  
Township 34, North, Range  
14 EAST; Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

Richard Piontek - Waubesa

David Pichotta - Waubesa



○ = Corner monument restored.

History of original corner establishment:

This corner can also be described as: THE SECTION CORNER COMMON TO SECTIONS 5 AND 6,  
T33N-R14E, AND, 31 AND 32, T34N-R14E, 4TH P.M.

This corner was established during the original survey of the town line between towns  
33 and 34 North, as noted in the Original Field Notes for the Original Survey of  
T34N-R14E, 4th p.m.

Description of corner evidence found:

The original bearign three, described in the original field notes as:

"Hemlock 16 N43°W 38 links"

is still present at this date, with a portion of the original scribe marks still visible.

Description of monument and accessories I established to perpetuate the original location of this corner.

At the site of the original post, as determined from the existing original bearing  
tree noted above, I emplaced a "Galvanized iron pipe, three feet long, one inch in  
diameter, with an aluminum cap denoted as, 'KIMBERLY-CLARK CORP T33-34N  
31, 32, 5, 6, R14E SPERHAKE RLS 463 11-1-62".

The pipe is witnessed by:

Balsam 3 N34°W 32 links. (Scribed S31 NBT).

Balsam 5 N24°E 50 links. (Scribed S32 NBT).

Dated at Crandon, Wis., this 25th day of August, 1964

Signature Neal Sperhake Title Registered Land Surveyor Registration No. S-463  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 25 day of August, 1964  
at 2:00 o'clock P. M.

Anna Peterson  
(Register of Deeds)

Subscribed & sworn to before me by  
Neal Sperhake this 25th day of Aug 1964.

Anna Peterson  
Notary Public Forest Co., Wis.  
Com. expires Oct. 31, 1965

By \_\_\_\_\_ Deputy


225163

# U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-l).

(a) CORNER LOCATION  
1/4 Cor. of Secs. 5 & 32  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,221.43 USft  
E: 718,511.26 USft  
WISCRS - Forest County  
N: 500,548.70 USft  
E: 869,714.11 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS STATIC



## (b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey Commenced: August, 1857  
Completed: August, 1857

Sugar 16" S50°W, 9 lks.  
Hemlock 10" N58°E, 34 lks.


(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Milo E. Stefan, RLS dated February 19, 1985 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated October 26, 1994 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 6, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap projecting 8" above a ring of stone. I set a DEEP-1 magnet adjacent to the monument. I found or established accessories as shown below. A USFS steel sign post bears West, 1.7 ft. I set a white vinyl sign post bearing East, 1.2 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.




FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-7

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

  
Signature

May 4, 2017  
Date



3414320020 (INDEX NO. A-7)

43414320020

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:


This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 ○ = Corner monument restored.

Quarter Corner to Sections 5 and 32,  
 T.33-34N., R14E., Forest and Langlade  
 Counties, WI.

State Plane Coordinates  
 Wisconsin North Zone  
 79618.95709-N  
 2284416.00924-E

Geographic Coordinates  
 45-22-41.90593-N  
 088-46-14.29169-W



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

Original survey in 1857 by Alfred Millard. Set wood post and the following bearing trees; Sugar, 16", S.50°W., 9 links, Hemlock, 10", N.58°E., 34 links.

On October 3 1983, Alan Harrison, R.L.S., found a post point in a mound of stone, from which an original Hemlock stump bears N. 58°E., 34 links (22.44 feet).


In place of post point, set a 2" x 36" aluminum monument with a tablet stamped to identify corner. Blazed and scribed new bearing trees; White Pine, 8", N.10°W., 80.08 feet, White Pine, 6", N.65°E., 45.98 feet, White Birch, 7", S.20°E., 37.51 feet, Steel sign post, West 1.8 feet.

On March 26 1991, Alan Harrison, R.L.S., found the monument and bearing trees as set in 1983. Northeast bearing tree is gone. Blazed and scribed 1 new bearing tree; Sugar, 5", S.50°W., 35.94 feet.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. 2" x 36" aluminum monument with tablet stamped to identify corner.
2. White Pine, 8", N.10°W., 80.08 feet.
3. White Birch, 7", S.20°E., 37.51 feet.
4. Sugar, 5", S.50°W., 35.94 feet.
5. Steel sign post, West 1.8 feet.



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

None


(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2)

(g & h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 23rd day  
of December, A.D. 1994, at  
2:00 o'clock A.M. and recorded  
in Vol. Cape Restoration  
page 34-14-2-7  
*Seal Clith Deputy*  
Register of Deeds



(1) I, Alan D. Harrison  
(type or print name) certify that the corner location shown  
on this record was determined by me or under my direction and  
control and that this U.S. Public Land Survey Monument Record is  
correct and complete to the best of my knowledge and belief.

*Alan D. Harrison* 10/26/94  
Signature Date

CERTIFICATE READY FOR FILING:

*Sue Vgo*  
District Ranger

# U. S. PUBLIC LAND SURVEY MONUMENT RECORD


**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Quarter corner to Sections 32 and 5, T.33-34N., R.14E.

REGISTER'S OFFICE  
Forest County, Wis.  
Received for record this 15th day  
of April A.D., 1985 at  
3:10 o'clock P.M. and recorded  
in Vol. CORNER RESTORATIONS  
page Z-7  
Paul Aschenbrenner  
Register of Deeds



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


June, 1857, Alfred Millard set wood post and the following BTs: Sugar, 16", S.50°W., 9 links; Hemlock, 10", N.58°E., 34 links.

October, 1983, Alan Harrison found corner position marked by a mound of stone with a post point in center and remains of original Hemlock stump at proper bearing and distance.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. White Pine, 8", N.10°W., 80.08 feet
2. White Pine, 6", N.65°E., 45.98 feet
3. White Birch, 7", S.20°E., 37.51 feet
4. Steel Sign Post, West, 1.80 feet



(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

(2) a found perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

No.

(i) Milo E. Stefan

(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Milo E. Stefan  
Signature

2/19/85  
Date





225164

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-4).

(a) CORNER LOCATION  
Cor. of Secs. 4, 5, 32 & 33  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,217.26 USft  
E: 721,176.04 USft  
WISCRS - Forest County  
N: 500,531.31 USft  
E: 872,378.83 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCRS RTN

	SEC. 5		
	T33N	R14E	

(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857


Hemlock 24" N15°W, 29 lks.  
Hemlock 25" S57°W, 31 lks.  
Y. Birch 10" S54°E, 9 lks.  
Sugar 10" N75°E, 48 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated January 17, 1984 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 13, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap flush in the West track of a woods road. I set a DEEP-1 magnet adjacent to the monument. The record birch bearing tree is a stump. I found or established accessories as shown below. A USFS steel sign post bears South, 9.2 ft. I set a white vinyl sign post bearing West, 4.8 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-9

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

MAY 4, 2017  
Date

3414320000 (INDEX NO. A-9)

43414320000


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

**INSTRUCTIONS:** This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.

○ = Corner monument restored.

Corner common to Sections 4, 5, 32, and 33, T.33-34N., R.14E.



- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Corner position found witnessed by a scribed wood post in a mound of rock. Corner in abandoned railroad grade, 17 links east of witness post. Witness testimony and past surveys support the above position. Placed a 2" x 36" aluminum monument at corner position.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.) Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Sugar, 6", N81°W, 27.76'
2. W. Birch, 6", N14°W, 81.41'
3. Sugar, 13", S68°E, 25.37'
4. B. Cherry, 6", S30°W, 44.65'
5. Steel Sign Post, South, 9.20'
6. Witness Post and Rockpile, West, 11.22'

Document Number **126172**



REGISTER'S OFFICE  
Forest County, Wis.

Received for record this 31st day  
of July A.D., 1984 at  
2:00 o'clock P M. and recorded  
in Vol. 2-9 of CORNER RESTORATIONS  
page 2-9

*Eugene D. Steiny*  
Register of Deeds

43414320000

Corner #2-9

7  
9

- (e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

- (f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


Perpetuated location.

- (g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

- (i) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

1/17/84  
Date




U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-4).

(a) CORNER LOCATION  
1/4 Cor. of Secs. 4 & 33  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,277.10 USft  
E: 723,779.81 USft  
WISCRS - Forest County  
N: 500,578.25 USft  
E: 874,982.85 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS RTN



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857


Hemlock 14" S59°W, 10 lks.  
Spruce 18" N40°E, 7 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated October 26, 1994 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 12, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap projecting 12" above a ring of stone. The monument leans South as it's grown into a large mass of roots I was unable to remove. All measurements were taken to a nail set coinciding with the location of the monument when plumb. I set a DEEP-1 magnet adjacent to the monument. I found or established accessories as shown below. A USFS steel sign post bears South, 2.0 ft. I set a white vinyl sign post bearing Southeast, 0.9 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Val.: Corner Restoration  
Page Number: 2-11

Langlade Co. Grid  
1" = 30'

95 ft. North of Creek

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

May 4, 2017  
Date


# U. S. PUBLIC LAND SURVEY MONUMENT RECORD

## INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

- (a) Identify the corner by reference to the U.S. public land survey system.  
 O = Corner monument restored.

Quarter corner to Sections 4 and 33,  
 T.33-34N., R.14E.



T.34N., R.14E.

T.33N., R.14E

- (b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.


Corner position recovered from witness tree of previous survey, old fence corner, and witness testimony. Placed a 2" x 36" aluminum monument.

- (c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)  
 Describe witness monuments.

- (d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

1. Aspen, 12", N82°E, 27.24'
2. Sugar, 8", S4°E, 47.39'
3. B. Cherry, 7", N85°W, 13.18'
4. Steel Sign Post, South, 1.3'

Document Number **126173**



REGISTER'S OFFICE  
 Forest County, Wis.

Received for record this 31st day  
 of July A.D., 1984 at  
3:00 o'clock P.M. and recorded  
 in Vol.        of CORNER RESTORATIONS  
 page 2-11

*Eugene J. Stepien*  
 Register of Deeds

Corner #Z-11

43414330020

211

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Perpetuated location.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(1) I, Alan D. Harrison  
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Alan D. Harrison  
Signature

1/17/84  
Date



U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-i).

(a) CORNER LOCATION  
Cor. of Secs. 3, 4, 33 & 34  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,299.09 USft  
E: 726,431.53 USft  
WISCRS - Forest County  
N: 500,587.10 USft  
E: 877,634.65 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS STATIC

	SEC. 4		
	T33N	R14E	

(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857

Sugar 24" N50°W, 42 lks.  
Hemlock 10" N25°E, 48 lks.  
Lynn 12" S49°W, 37 lks.  
Y. Birch 40" S45°E, 30 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.


*This is a perpetuation of a previous USPLS Monument Record by Victor H. Hedman, RLS dated October 18, 1962 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*This is a perpetuation of a previous USPLS Monument Record by Jean F. Resvick, RLS dated June 15, 1976 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated October 26, 1994 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 4, 2016: I found and accepted the record monument, a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap 24" beneath the ground surface. I set a 3/4" diam., 20" long rebar over the aluminum cap. The record y. birch at N16°E is now a stump. A power pole bears S53°E, 5 ft. I found or established accessories as shown below. A USFS steel sign post bears East, 7.0 ft. I set a white vinyl sign post bearing East, 1.0 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-13

(I) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

MAY 4, 2017  
Date

# CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 1st day of June, 1976, I found evidence of the Southeast section corner of Section 33 Township 34 North Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:



Description of original monument and accessories and subsequent restorations: Surveyed in 1857 by Alfred Millard. 80.00 chains west between Sections 3 and 34, set post.  
Hemlock 10, N25E, 48 lks.  
Lynn 12, S49W, 37 lks.  
Y. Birch 40, S45E, 30 lks.  
Sugar 24, N50W, 42 lks.

Monumented in 1962 by Jean Resvick and Victor Hedman and recorded in Landglade County, Document number 202744, dated February 6, 1964, Volume 1, Page 9.  
Yellow Birch 5, N15-30E, 74.40 ft.  
Elm 7, S47-30E, 21.65 ft.  
Sugar 12, S63W, 39.30 ft.  
Sugar 14, N52W, 55.80 ft.  
Description of corner evidence found:

Monument set in 1962 bent over and brass cap removed.  
Hemlock stump found in 1962 with scribing, now down and only pieces  
Bearing tree set in 1962 in good shape although specie and distance did not agree.

Description of monument and accessories I established to perpetuate the location of this corner:  
Replace bent monument with 2 inch diameter aluminum pipe monument, 3 feet long with cast aluminum base and aluminum cap stamped:  
T34N, R14E, S33, S34, S4, S3, T33N, 1976, S-802.

Placed nails in bearing trees being the same as scribed in 1962  
Yellow Birch 8, N16E, 75.00 ft.  
Elm 10, S47E, 21.65 ft.  
Sugar 15, S63W, 39.30 ft.  
Elm 17, N52W, 55.80 ft.  
Monument set almost flush with ground.  
Set steel sign post NW of monument.



● - Corner monument restored  
□ -

Resident witnesses.....

Dated at Rhineland Wisconsin, this 15 day of June 1976.

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 109577

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 2nd day of July 1976, and was filed in Book No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 34 North, Range 14 East, Section 33, Index No. Z-13, Page No. \_\_\_\_\_

43414 33 0000

213




U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-i).

(a) CORNER LOCATION  
1/4 Cor. of Secs. 3 & 34  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,336.75 USft  
E: 729,079.09 USft  
WISCRS - Forest County  
N: 500,611.64 USft  
E: 880,282.36 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS STATIC



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857

Y. Birch 24" N52°W, 64 lks.  
Y. Birch 20" S30°E, 45 lks.


(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by William F. Kelly, RLS dated December 27, 1987 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*This is a perpetuation of a previous USPLS Monument Record by Alan D. Harrison, RLS dated October 26, 1994 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 4, 2016: I found and accepted the record monument, a 2-1/2" diam. iron pipe with a 3" diam. brass cap projecting 3" above the ground surface. The record bearing tree at N45°E is now a stump, the tree at S77°W is gone. I found or established accessories as shown below. A USFS steel sign post bears North, 0.5 ft. I set a white vinyl sign post bearing Southwest, 1.2 ft.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-15

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

MAY 4, 2017  
Date

# CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 1 day of June, 19 76, I found evidence of the South Quarter corner of Section 34 Township 34 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1857 by Alfred Millard  
40.00 chains west between sections 3 & 34  
Set Quarter Section Post  
Y. Birch 24", N52°W, 64 links  
Y. Birch 20", S30°E, 45 links


Description of corner evidence found:

4" x 4" wood post, scribed, from which evidence of original bearing trees were located. Large yellow birch stump and root remain N52°W, 64 links. Large yellow birch stump and root remains S30°E, 45 links.

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced wood post with a 2 inch inside diameter, galvanized iron pipe, 3 feet long, filled with concrete, with brass cap stamped: T34N & T33N, R14E, 1/4, S3, S34, 1976, S-802.

Blazed and scribed the following new bearing trees:  
Sugar maple, 15", S83°E, 30.25 feet  
Basswood, 10", N54°W, 22.28 feet  
Set a steel sign post north of the monument, 0.50 feet.



● - Corner monument restored  
□ -

Resident witnesses \_\_\_\_\_

Dated at Rhineland Wisconsin, this 1 day of April, 19 77.

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)


Surveyors Registration No. S-802 DOCUMENT NUMBER - **111428**

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of May, 19 77, and was filed in Book No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 34 North, Range 14 East, Section 34, Index No. Z-15, Page No. \_\_\_\_\_




225168

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-1).

(a) CORNER LOCATION  
Cor. of Secs. 2, 3, 34 & 35  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,373.55 USft  
E: 731,729.97 USft  
WISCRS - Forest County  
N: 500,635.31 USft  
E: 882,933.38 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS STATIC



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857


Lynn 30" N65°W, 22 lks.  
Sugar 14" S44°W, 31 lks.  
Lynn 28" N30°E, 3 lks.  
Ironwood 10" S52°E, 15 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

*This is a perpetuation of a previous USPLS Monument Record by Milo E. Stefan, RLS dated January 23, 1984 and filed in the office of the Langlade County Surveyor. A complete history of the corner can be found on the previous monument record. I accept the previous location as a true and faithful perpetuation or reestablishment of the original corner location and further perpetuate it as follows.*

*November 4, 2016: I found and accepted the record monument, a chiselled "X" on a large rock. I found reference monuments as described by Stefan: a 2-1/2" diam. aluminum pipe with a 3-1/4" diam. aluminum cap bearing East, 5.70' and South, 4.62'. I found or established accessories as shown below. USFS steel sign posts are adjacent to each reference monument. I set a white vinyl sign post bearing Northeast, 1.5 ft. from the corner point.*

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-17



(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Signature

MAY 4, 2017  
Date

3414340000 (INDEX NO. A-17)


43414340000

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-l).

(a) CORNER LOCATION  
1/4 Cor. of Secs. 2 & 35  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,411.39 USft  
E: 734,379.87 USft  
WISCRS - Forest County  
N: 500,660.02 USft  
E: 885,583.43 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS RTN



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857


Hemlock 24" N42°W, 14 lks.  
Hemlock 24" S54°E, 32 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

1976: "Land Corner Restoration" survey by Jean F. Resvick, RLS filed as Langlade County Surveyor Record #10900. Corner is marked by a brass-capped iron pipe with the following bearing trees: basswood 6" N89°E, 40.3', yellow birch 9" S29°E, 28.9', hemlock 12" S42°W, 65.0', sugar maple 12" N5°W, 44.9', hemlock 14" N63°E, 35.4'.

November 5, 2016: I found and accepted the record monument, a 2-1/2" diam. iron pipe with a 3" diam. brass cap projecting 6" above a ring of stone. The record basswood bearing tree is gone. I found or established accessories as shown below. A USFS steel sign post bears Southeast, 1.7 ft. I set a white vinyl sign post bearing South, 1.3 ft.

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-19

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature


May 6, 2017  
Date

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

Note: This form is intended and designed to fulfill all requirements of Wisconsin Administrative Code, Chapter A-E 7.08 U.S. Public Land Survey Monument Record (3)(a-4).

(a) CORNER LOCATION  
Cor. of Secs. 1, 2, 35 & 36  
Township 33 & 34 North  
Range 14 East of the 4th P.M.  
Town of Wolf River/Freedom  
County of Langlade/Forest

WISCRS - Langlade County  
N: 427,435.90 USft  
E: 737,026.06 USft  
WISCRS - Forest County  
N: 500,671.42 USft  
E: 888,229.70 USft  
Datum: NAD 83(2011)  
GNSS Method: WISCORS RTN



(b) HISTORY OF ORIGINAL CORNER ESTABLISHMENT

Original Surveyor: Alfred Millard

Original Accessories:

Date of Survey      Commenced: August, 1857  
Completed: August, 1857


Elm 10" N26°E, 32 lks.  
Elm 16" N20°W, 15 lks.  
Elm 14" S40°E, 11 lks.  
Lynn 18" S25°W, 46 lks.

(b)(f)(g)(h) Description of monument found at this corner and if it was accepted, state all evidence (material, testimonial, occupational, plats, records, other monuments) used as a basis for accepting. If not accepted or if nothing was found, state evidence used as basis for establishing location. If re-established through lost corner proportionate methods, indicate all monuments, distances and directions used to establish. Indicate type of monument and sign post found or set.

1976: "Land Corner Restoration" survey by Jean F. Resvick, RLS filed as Langlade County Surveyor Record #10900. Corner is marked by a brass-capped iron pipe with the following bearing trees: sugar maple 5° N35°E, 27.3', sugar maple 4° S10°E, 10.8', red maple 6° S41°W, 28.2', basswood 11° N58°W, 27.4'.

November 5, 2016: I found and accepted the record monument, a 2-1/2" diam. iron pipe with a 3" diam. brass cap projecting 6" above a ring of stone. I found or established accessories as shown below. A USFS steel sign post bears North, 1.3 ft. I set a white vinyl sign post bearing East, 1.3 ft.

(c)(d)(e) Plan view of corner with ties to at least 4 witness monuments. If in disagreement with previously established corner, show the distances between the two corners and also indicate the ties to the disputed.



FOREST COUNTY, WI  
CORTNEY BRITTEN CLEEREMAN  
REGISTER OF DEEDS  
RECEIVED FOR RECORD

APR 27 2018

Time: 10:00 A.M.  
Vol.: Corner Restoration  
Page Number: 2-21

(i) I, Jeffrey W. Austin, Professional Land Surveyor No. S-1885, hereby certify that the corner location on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.



Signature

MAY 6, 2017  
Date