

Stock No. 26273

Sheet 2 of 4

SURVEY NOTES

This survey was made by Gary L. Pisoni, a Registered Land Surveyor in the State of Wisconsin, for the U.S.D.A., Forest Service, for the purpose of recovering, restoring, establishing, marking, and perpetuating the corners and boundary lines of U.S. Government Land on the perimeter and within Section 13, Township 36 North, Range 14 East, Fourth Principal Meridian, Forest County, State of Wisconsin, as shown on the plat map herewith.

The Original Government Township Lines was done by Artemas Curtis, U.S. Deputy Surveyor in September of 1857. The original Government Sub-division of this township was done by James McBride, U.S. Deputy Surveyor in July of 1859.

The bearings between corner positions are true bearings referenced to the East One-Half of the North section line of Section 23, as determined by a solar observation by James J. Fronsoe, R.L.S. of Amberg, WI. from a Plat of Survey of August, 1986 of Section 23. All distances shown thereon are in feet and hundredths of feet. The control traverse was measured by use of an electronic distance measuring equipment.

The accuracy of this survey exceeds the State requirements of 1 in 3000.

The field notes and a copy of the Plat of Survey are on file in the Forest Supervisor's Office at Rhinelander, Wisconsin.

CORNERS RECOVERED AND RESTORED1. Northwest Section Corner

In 1964, Jean F. Resvick, RLS. restored corner position from original bearing tree evidence set by James McBride in 1859, and also found a old sand point marking corner position which he accepted. Resvick replaced sand point with 2" iron pipe with stamped brass cap.

In 1986, James J. Fronsoe, RLS. recovered corner position from evidence set by Jean F. Resvick in 1964.

1986 Corner References:

Cedar	7"	N 22°E	5.90 feet
Hemlock	14"	S 64°E	20.90 feet
Hemlock	18"	S 35°E	7.70 feet
Cedar	7"	S 47°W	30.05 feet
Cedar	6"	N 45°W	62.40 feet
Steel Sign Post	6'	South	0.70 feet

2. North Quarter Corner

Corner position restored by single proportionate measurement methods on line between the Southeast corner of Section 12 and the Southwest corner of Section 12.

Corner References:

Steel Sign Post	6'	S 29°W	1.05 feet
Steel Sign Post	6'	North	1.05 feet
Steel Sign Post	6'	N 72°E	0.92 feet

Stock No. 26273

Sheet 3 of 4

3. Northeast Section Corner

In 1967, Jean Resvick, RLS. restored the corner position from evidence of original bearing trees. Resvick set a galvanized iron pipe with stamped brass cap.

In 1993, Gary L. Pisoni, RLS. recovered the corner position where he found the monument but bearing trees were missing.

1993 Corner References:

Tamarack	4"	N 63°E	17.66 feet
Tamarack	4"	S 69°E	29.48 feet
Tamarack	3"	S 86°W	13.94 feet
Tamarack	5"	N 11°W	13.99 feet
Steel Sign Post		S 55°W	1.20 feet

4. East Quarter Corner

In 1993, Gary L. Pisoni, RLS. restored the corner position by single proportionate measurement. No evidence of original corner found. Set aluminum pipe monument with stamped aluminum cap at corner.

Corner References:

Cedar	12"	S 45°W	85.84 feet
Cedar	10"	S 87°W	54.28 feet
Cedar	13"	N 67°W	51.83 feet
Steel Sign Post		South	0.97 feet

5. Southeast Section Corner

Found an aluminum pipe monument marking corner position as stated in a Land Corner Certificate by Thomas R. Arnott, S-887, document No. 136727.

6. South Quarter Corner

In 1986, James J. Fronsoe, RLS. restored the corner position from a small stake hole next to an old fence post hole in line with East-West fence line. He accepted this and set aluminum monument with cap.

Corner References:

Maple	5"	N 15°E	4.30 feet
Maple (twin)	9"	S 68°E	4.00 feet
Maple	8"	S 19°E	18.30 feet
Maple	8"	S 85°W	16.40 feet
Steel Sign Post		East	1.00 feet

7. Southwest Section Corner

In 1986, James J. Fronsoe, RLS. restored the corner position from an ancient, buried, fence corner post hole that fit swamp calls. Fronsoe accepted this as best available evidence and set an aluminum pipe monument with cap at corner.

Corner References:

Red Pine	5"	N 22°E	61.50 feet
Red Pine	6"	N 71°E	73.30 feet
Aspen	6"	S 61°E	108.40 feet
Aspen	7"	S 04°E	58.20 feet
Steel Sign Post		North	0.70 feet

Stock No. 26273

Sheet 4 of 4

8. West Quarter Corner

In 1986, James J. Fronsoe, RLS. restored the corner position from original corner evidence and original bearing tree stump holes set by James McBride in 1859. Fronsoe set a 2" x 36" aluminum pipe with cap.

Corner References:

Maple	11"	North	38.30 feet
Maple	12"	S 25°W	35.20 feet
Maple	12"	S 71°W	39.55 feet
Maple	6"	N 55°W	37.50 feet
Steel Sign Post		West	1.20 feet

CORNERS ESTABLISHED1. South Sixteenth Corner between Sections 13 and 14

Corner position established on line and midway between the Southwest Section corner and West Quarter corner.

Corner References:

Black Spruce	9"	S 06°E	30.31 feet
Black Spruce	8"	N 81°W	12.57 feet
Steel Sign Post		N 36°E	1.15 feet

2. Center South Sixteenth Corner

Corner position established on line and midway between the South Quarter corner and Center Quarter corner.

Corner References:

Cedar	8"	N 12°E	33.31 feet
Black Spruce	13"	N 86°E	18.34 feet
Steel Sign Post		N 65°W	2.10 feet

3. North Sixteenth Corner between Sections 13 and 18

Corner position established on line and midway between the Northeast Section corner and East Quarter corner.

Corner References:

Black Spruce	7"	S 77°E	16.34 feet
Black Spruce	7"	N 23°W	7.22 feet
Steel Sign Post		N 45°E	1.00 feet

SURVEYOR'S CERTIFICATE

State of Wisconsin)ss
County of Forest)

I, Gary L. Pisoni, a Cadastral Surveyor, and a Registered Land Surveyor in the State of Wisconsin, hereby certify that I have surveyed and sub-divided Section 13, Township 36 North, Range 14 East, Fourth Principal Meridian, State of Wisconsin.

The plat map and survey notes herewith are a correct representation of the land surveyed and divided. I have surveyed and sub-divided said section in accordance with the rules for the survey of public lands and with the statutes of the State of Wisconsin.

Date of Survey: 1993-94

Gary L. Pisoni
Cadastral Surveyor
L.S. State of Wisconsin
Certificate S-1634

