


MAP OF SURVEY

THOSE LANDS DESCRIBED IN DOCUMENT NUMBER 221278
BEING PART OF THE SOUTHWEST 1/4 OF THE NORTHWEST 1/4,
SECTION 28, TOWNSHIP 37 NORTH, RANGE 13 EAST, FOURTH PRINCIPAL MERIDIAN,
TOWN OF ARGONNE, FOREST COUNTY, WISCONSIN

FOREST CO SURVEYOR
FILE # 371328-20260831
DATE 09/01/2026 BY JA



Bearings are referenced to:
The Wisconsin Coordinate
Reference System,
Forest County Zone,
and the West line of the
NW 1/4 of Section 28
Measured to bear
S 00°12'45" E


4327 COLE ROAD
CRANDON, WI 54520
Anderson 715.784.3485
DeMuth 715.482.5237
cardinal.north@outlook.com

cardinal north llc
ENGINEERING | SURVEYING | DRONE

MAP OF SURVEY

CLIENT:
Terry L. Kevilus
SITE ADDRESS:
8866 Bailey Ave.
Argonne, WI 54511

Project: 2026-15-Kevilus Survey
Drawn by: Jeffrey L. DeMuth
Checked by: James E. Anderson
Fieldwork completed: August 2026
Sheet 1 of 1 Sheets



SURVEYOR'S CERTIFICATE

I, Jeffrey L. DeMuth, Professional Land Surveyor S-2656 of the State of Wisconsin, do hereby certify to my client, Terry L. Kevilus, the Owner and under whose direction this survey was performed, that I have surveyed, mapped, and described those lands described in document number 221278; being part of Southwest 1/4 of the Northwest 1/4, Section 28, Township 37 North, Range 13 East, Fourth Principal Meridian, Town of Argonne, Forest County, Wisconsin.

Being more particularly described for mapping purposes as follows:
Commencing at the Northwest corner of Section 28, Thence S 00°12'45" E, along the west of of the Northwest 1/4 said section 28, a distance of 2300.82 feet to the westerly extension of the south line of that property described in document number 221278; Thence, leaving said west line, S 87°53'54" E, along said south line extension, a distance of 393.19 feet to the Southwest corner of said property and the POINT OF BEGINNING of lands surveyed;


Thence, leaving said south line extension, N 02°29'20" E, along the east line of said property, a distance of 303.50 feet to the south right-of-way line of Bailey Avenue; Thence, leaving said west line, S 87°53'51" E, along said right-of-way line, a distance of 140.50 feet to the Northwest corner of that property described in document number 188893; Thence, leaving said right-of-way line, S 02°29'20" W, along the west line of said property, a distance of 303.50 feet to the north line of that property described in document number 247395; Thence, leaving said west line, N 87°53'54" W, a distance of 140.50 feet to the Point of Beginning.

That said parcel contains 0.97 acres of land more or less and is subject to easements, restrictions, reservations, claims, and rights-of-way of record, if any.

That this Map is a true and correct representation of the exterior boundaries of lands surveyed, and that I have fully complied with Chapter A-E 7 of the Wisconsin Administrative Code, to the best of my knowledge and belief.

Volume 23 Page 475

Jeffrey L. DeMuth S-2656
August 31, 2026
Date



LEGEND

Monument sizes = outside diameter measurements.

- 0.75" diameter X 18" long iron rod, weighing 1.5 lbs. per lineal foot, set
- ⊙ 1.4" diameter iron pipe, found
- ⊕ U.S.P.L.S. monument, as noted
- △ Computed position, not set
- () Previously recorded data
- ⊕ Centerline
- P.O.B. Point of Beginning
- R/W Right-of-Way line
- U.S.P.L.S. United States Public Land Survey
- S.F. Square feet
- X- Old barbed - wire fence