
# PLAT OF SURVEY FOR CERTIFIED LAND CORNER RESTORATION AND ESTABLISHMENT

BEING THE CORNERS FOR THE SW 1/4 OF THE SW 1/4 AND THE SOUTH LINE OF THE SW 1/4 OF THE SE 1/4 AND THE CORNERS ON THE PERIMETER OF THE SECTION.

SECTION 9. TOWNSHIP 38 NORTH. RANGE 14 EAST.

COUNTY OF FOREST. STATE OF WISCONSIN



1000 0 1000 GRAPHIC SCALE - 1"-1000 FOREST CO SURVEYOR

FILE # 381409 - 19960200

DATE \_\_\_\_\_\_\_BY \_\_\_\_

## LEGEND

- 2 1/2 INCH DIAMETER GALVANIZED IRON PIPE MONUMENT WITH BRASS CAP
- ☐ I INCH DIAMETER ALUMINUM PIPE MONUMENT 36 INCHES LONG WITH AN ALUMINUM CAP.
- 2 INCH DIAMETER ALUMINUM PIPE MONUMENT WITH AN BRASS CAP
- 2 1/2 INCH DIAMETER ALUMINUM PIPE MONUMENT 36 INCHES LONG WITH AN ALUMINUM CAP
- 2 1/2 INCH DIAMETER ALUMINUM PIPE MONUMENT WITH AN ALUMINUM CAP
- 2 1/2 INCH DIAMETER ALUMINUM PIPE MONUMENT 60 INCHES LONG WITH AN ALUMINUM CAP
  - --- BOUNDARY LINE MARKED TO FOREST SERVICE STANDARD

#### **SURVEY NOTES**

## Section 9. T38N - R14E

This survey was made by Coleman Engineering Company for the U.S. Department of Agriculture - Forest Service under Contract No. 53-56A6-4-00936 for the purpose of restoring and establishing corners on the perimeter of Section 9 and interior corners for subdivision of Section 9, and for locating and marking boundaries of U.S. Government lands along the perimeter and within Section 9, Township 38 North, Range 14 East, Fourth Principal Meridian, Forest County, State of Wisconsin as shown on the plat map herewith.

The original township subdivision survey of T38N, R14E was completed in 1865 by James L. Nowlin.

The corner positions recovered, restored and established by this survey are marked by the monument described in the map legend. The corner positions established were located to a minimum accuracy of 1 part in 5000. Each monumented corner is referenced to blazed scribed, painted and tagged bearing trees. Tie bearings to the bearing trees are magnetic and are not corrected for declination. The bearings between corner positions are true bearings derived from solar observations taken by Coleman Engineering Company using the hour angle method.

The field notes and a copy of the Plat of Survey are on file in the Forest Service Supervisor's office in Rhinelander, Wisconsin and the District Ranger's office at Eagle River, Wisconsin.

#### CORNERS RECOVERED OR RESTORED

#### 1. Northeast Section Corner

Corner position recovered and restored in 1988 by John Schulke R.L.S. 1665; and is on file in the Forest County Register of Deeds office as Document No. 136590.

#### Corner References:

Red Maple	12"	N85°W	18.27 feet
Sugar Maple	9"	N06°W	35.60 feet
Sugar Maple	8"	S05°W	27.65 feet
Red Maple	10"	N29°E	45.73 feet
Steel Sign Post		East	1.5 feet

Monument and 4 B.T.'s were found in good condition this survey.

#### 2. East Ouarter Corner

Corner position was recovered in 1969 by Jean Resvick R.L.S. 802 and recovered in 1988 by John Schulke R.L.S. No. 1665 and is on file in Forest County Register of Deeds office as Document No. 136593.

#### **Existing Corner References:**

Black Ash 13"	N52°W	29.27 feet
Red Maple 16"	East	29.83 feet
G.L.O. Blown down Sugar Maple	S11°E	9.24 feet

#### John Schulke's New Corner References:

Spruce	13"	N57°E	26.95 feet
Red Maple	5"	S86°W	32.53 feet
Steel Sign Post		Southwest	0.90 feet

Monument and 4 B.T.S. were found in good condition this survey.

## 3. Southeast Section Corner

Corner position was recovered in 1959 by Robert Bandow R.L.S. No. 104 and recovered on 1988 by John Schulke R.L.S. 1665 and is on file in Forest County Register of Deeds office as Document No. 136595.

#### Corner References:

Red Maple	10"	N08°E	24.48 feet
Sugar Maple	10"	S69°E	31.09 feet
Red Maple	12"	S17°W	25.00 feet
Twin Red Maple	10"	N23°W	57.18 feet
Steel Sign Post		Northwest	1.00 feet

Monument and B.T.'s were found in good condition this survey.

## 4. South Ouarter Corner

Corner position recovered and restored in 1969 by Jean Resvick R.L.S. 802 and is on file in Forest County Register of Deeds office as Document No. 98923.

## Corner References:

Hemlock	19"	N12°W	21.64 feet
Cedar	6"	S53°W	30.49 feet
Steel Sign Post		Northwest	2.30 feet

Monument and B.T.'s were found in good condition this survey.

## 5. Southwest Section Corner

Corner position recovered and restored in 1970 by Jean Resvick R.L.S. No. 802; and is on file in Forest County Register of Deeds office as Document No. 98922.

#### Corner References:

Sugar	5"	N62°E	18.77 feet
Hemlock	13"	S42°E	40.20 feet
Sugar	17"	S50°W	60.04 feet
Sugar	13"	N78°W	18.29 feet
Steel Sign P	ost	S50°W	1.00 feet

Monument and B.T.'s found in good condition this survey.

#### 6. West Ouarter Corner

Corner position restored as part of this survey by lost corner proportion methods between the Northwest and Southwest Corners of Section 9. Set 2-1/2" x 36" aluminum monument..

#### Corner References:

Sugar	11"	S80°E	54.99 feet
Sugar	7"	S01°W	52.26 feet
Sugar	8"	N77°W	8.81 feet
Sugar	9"	N25°W	33.22 feet
Steel Sign l	Post	Northeast	1.26 feet

#### 7. Northwest Section Corner

Corner position recovered and restored in 1959 by Robert Bandow R.L.S. 104; and is on file in Forest County Register of Deeds office.

## Corner References:

Elm	21"	S74° 30' W	47.90 feet
Elm	9"	N2° 30' W	60.20 feet
Cedar	17"	N62° 00' W	85.80 feet

## 8. North Ouarter Corner

Corner position restored from acceptance of the location of a cairn of stones and an old Hemlock with blazes in four cardinal directions which was found by retracing Melindy's 1913 survey, Set 2-1.2" x 36" aluminum monument in center of stone cairn.

#### Corner References:

Sugar	8"	East	39.72 feet
Sugar	4"	S33°E	19.18 feet
Sugar	6"	S62°W	25.15 feet
Sugar	9"	N12°W	26.51 feet
Steel Sign Pos	t	North	0.81 feet

#### **CORNERS ESTABLISHED**

## 1. South One-Sixteenth Corner between Sections 8 and 9

Set 1" x 36" aluminum monument on line and at the mid-point between the West Quarter Corner and the Southwest Corner of Section 9.

#### Corner References:

Cedar	8"	N75°E	23.39 feet
Cedar	8"	N56°W	37.75 feet
Steel Sign Post		Northwest	1.07 feet

## 2. Southwest One-Sixteenth Corner

Set 1" x 36" aluminum monument at the intersection of the South and West One-Sixteenth lines.

## Corner References:

Maple	<b>7"</b> .	N49°E	41.36 feet
Maple	7"	S08°E	14.05 feet
Steel Sign Post		Northeast	1.15 feet

## 3. West One-Sixteenth Corner between Sections 9 and 16

Set 1" x 36" aluminum monument on line and at the mid-point between the South Quarter Corner and the Southwest Corner of Section 9.

## Corner Reference:

Sugar	7"	N43°W		25.17 feet
Sugar	5"	S30°W		6.63 feet
Steel Sign Post		East	•	1.09 feet

## 4. East One-Sixteenth Corner between Sections 9 and 16

Set a stamped 1" x 60" aluminum monument on line and at the mid-point between the South Quarter Corner and the Southeast Corner of Section 9.

## Corner References:

Black Ash	6"	N25°E	13.84 feet
Maple	9"	S81°E	22.14 feet
Steel Sign Post		West	1.24 feet



#### **SURVEYOR'S AFFIDAVIT**

I, James H. Moore, a registered Land Surveyor in the State of Wisconsin, hereby certify that I have surveyed and sub-divided Section 9, Township 38 North, Range 14 East, Fourth Principal Meridian, Forest County, State of Wisconsin.

The plat map and survey notes herewith are a correct representation of the land surveyed and subdivided. I have surveyed and sub-divided said section in accordance with the rules for the Survey of Public Lands and the Statutes of the State of Wisconsin.

District Ranger

Land Surveyor

R.L.S. State of Wisconsin

Certificate S-1641

Date of Survey February 1996

Survey requested by:

AMES H. MOORE S- MIS MORWAY MICHGAN

Data

FOREST CO. CLERK