

LANGLADE COUNTY U.S. PUBLIC LAND CORNER RESTORATION

The Southeast corner of Section 24, T. 31 N., R. 09 E., Langlade County, WI.

Corner was: (check all that apply)

- Restored through acceptance of an obliterated evidence location.
- Restored through acceptance of a found perpetuated location.
- Determined to be lost and re-established through proportionate methods.
- Show bearings and distances to PLSS corners used for proportioning, and show original distances).
- Restored/recovered/re-established in a location that differs from a previously established position.
- (Show difference in plan view below).
- Check here if additional information is shown on the reverse side of this form.

4310924 0000

Describe record evidence, recovered physical evidence, occupational evidence, testimonial evidence and all other evidence considered in the recovery/restoration of the corner.

The original corner was established in 1859 by Hiram Fellows. Original bearing trees: birch, 20", S20W, 15 links; hemlock, 15", S21E, 28 links; ash, 12", N82E, 32 links and a hemlock, 15", N08W, 33 links. In 1887, B.F. Dorr, FB140-46, ran west from this corner. At 77.64 ch he fell 7.10 ch south. In 1919, Hutchinson, FB122-121, on a road survey "run for the State": "W. bet. 19-30 (in 31-10) V 11°-15' at 80.50 Int 243 S of cor. on range line". He did not describe the corner. In the 1930's resurvey, Hintz "drove iron peg 1/2" x 3" into road. Brass cap 30 feet south and another peg 30' North". On 06/23/06 D. Tlusty found the top of the south wm brass capped pipe. 04/20/10 D. Tlusty now had time to dig to examine 4" iron pipe with brass cap witness monument on south side of STH "64". Exposed the entire monument at a depth of 2.8 feet. Monument is leaning severely to the east but I don't believe it has been hit or moved by heavy equipment. I found the location of the base and redug and reset the monument (4" x 38" pipe with brass tablet) so the top is now 8" below ground level. I re-established the section corner 30' north of this re-set witness monument. The corner falls in line with the approximate centerline of STH "64" to the west. My bearings and distances to the recovered quarter corners to the north and south of this corner, agree well with the 1930's resurvey data.

Physical description of the monument set:

I drove a 6" gearheaded spike for the corner.

Describe the accessories used to perpetuate the corner. Include a plan view drawing and accessories found/set. Describe measuring point on bearing trees. Show any topographic features that would aid in future recovery of the corner.

Langlade County Coordinates
341794.9336 581679.3096
GH SPK SET SE COR SEC 24

